FINAL SURVEY	NOTE BOOK	NO.
SURVEYED		
PLOTTED		
TEMPLATE		
AREAS		
AREAS CHECKED		

BY	DATE

ORIGINAL SURVEY	NOTE BOOK	NO.
SURVEYED		
PLOTTED		
TEMPLATE		
AREAS		
AREAS CHECKED		

BY	DATE

150 140 130 120 110 100 90 80 70 60 50 40 30 20 10 ℄ 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

670
665

MATCH TO IL. 47

1:340.0 1:19.0 1:4.0

670.85

F.O.

CUT (C) = 0 SQ FT
UNDERCUT (UC) = 178 SQ FT
FILL (F) = 8 SQ FT

1:243.4

MATCH TO IL. 47

1408 + 08.08

670
665

670.77

1:61.1 1:5.6 1:4.0

S.D.
666.00

F.O.

C = 0
UC = 118
F = 11

1:4 1:4

S.D.
666.00

MATCH TO IL. 47

1408 + 00.00

675
670
665

PR EASEMENT

EX ROW

1:3 1:4

670.46

S.D
666.17

F.O.

C = 0
UC = 84
F = 26

EX ROW

1:4 1:3

S.D.
666.15

PR EASEMENT

1407 + 50.00

670
665

PR ROW

EX ROW

1:3 1:4

670.29

S.D.
666.34

F.O.

C = 0
UC = 90
F = 23

EX ROW

1:4 1:3

S.D.
666.29

PR ROW

1407 + 00.00

PAVEMENT REMOVAL

150 140 130 120 110 100 90 80 70 60 50 40 30 20 10 ℄ 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

FILE NAME = V:\3195\66B84 (North Section)\CADD Sheets\D366B84-sht-xssht-Newark.dgn	USER NAME = bdecraene	DESIGNED - HLC	REVISED -
		DRAWN - HLC	REVISED -
	PLOT SCALE = 20.0000 ' / in.	CHECKED - CAS	REVISED -
$MODELNAME$	PLOT DATE = 7/14/2014	DATE - 7/01/2014	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

NEWARK ROAD CROSS SECTIONS

SCALE: H=10 V=5 | SHEET 4 OF 4 SHEETS | STA. 1407+00.00 TO STA. 1408+08.08

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(109,110) R-1	KENDALL	619	614
		CONTRACT NO. 66B84		
		ILLINOIS FED. AID PROJECT		