

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				100% STATE	
				ROADWAY 0005	RURAL
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600990	TEMPORARY RAMP	SO YD	1681	1681	
40603243	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, 1L-19.0, FG, N90	TON	29087	29087	
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	9389	9389	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	14602	14602	
44000300	CURB REMOVAL	FOOT	120	120	
44200529	CLASS A PATCHES, TYPE II, 8 INCH	SO YD	232	232	
44213000	PATCHING REINFORCEMENT	SO YD	832	832	
44213200	SAW CUTS	FOOT	2898	2898	
44213204	TIE BARS 3/4"	EACH	112	112	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	5041	5041	
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SO YD	367	367	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	16861	16861	
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1	

FILE NAME :	USER NAME :	DESIGNED :	REVISED :	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pr-work\pwidet\duncanbd\0315542\036653-shs-500.dgn	duncanbd	-	-		SCALE:	SHEET 2 OF	SHEETS	STA.	TO STA.	57	138-3RS-2	186	4
PLOT SCALE :	CHECKED :	REVISED :	REVISED :		CONTRACT NO. 66C53								
PLOT DATE :	DATE :	-	-		ILLINOIS FED. AID PROJECT								