

SCHEDULE OF QUANTITIES

REMOVAL

PCC/HMA SURFACE REMOVAL – BUTT JOINT

LOCATION	TO	LOCATION	THICKNESS (IN)	LENGTH (FOOT)	WIDTH (FEET)	AREA (SQ YD)	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT 40600985 (SQ YD)	
NORTHBOUND								
NB RURAL	306+07.00	306+35.80	1.50	28.80	24.0	76.8	76.8	
STATION EQUATION	306+35.80	305+66.49						
NB RURAL	305+66.49	305+82.69	1.50	16.20	24.0	43.2	43.2	
NB RURAL	340+83.00	341+28.00	1.50	45.00	40.0	200.0	200.0	
NB RURAL	345+59.00	346+04.00	1.50	45.00	40.0	200.0	200.0	
NB RURAL	502+86.00	503+31.00	1.50	45.00	40.0	200.0	200.0	
NB RURAL	506+81.00	507+26.00	1.50	45.00	40.0	200.0	200.0	
NB RURAL	549+10.00	549+55.00	1.50	45.00	40.0	200.0	200.0	
C.H. 12 RAMP B	11+68.00	12+13.00	1.50	45.00	26.0	130.0	130.0	
C.H. 12 RAMP C	7+28.00	7+73.00	1.50	45.00	26.0	130.0	130.0	
C.H. 8 RAMP B	9+31.00	9+76.00	1.50	45.00	26.0	130.0	130.0	
C.H. 8 RAMP C	7+28.00	7+73.00	1.50	45.00	26.0	130.0	130.0	
SOUTHBOUND								
SB RURAL	306+20.00	306+35.80	1.50	15.80	40.0	70.2	70.2	
STATION EQUATION	306+35.80	305+66.49						
SB RURAL	305+66.49	305+95.69	1.50	29.20	40.0	129.8	129.8	
SB RURAL	340+62.00	341+07.00	1.50	45.00	40.0	200.0	200.0	
SB RURAL	345+47.00	345+92.00	1.50	45.00	40.0	200.0	200.0	
SB RURAL	502+86.00	503+31.00	1.50	45.00	40.0	200.0	200.0	
SB RURAL	506+81.00	507+26.00	1.50	45.00	40.0	200.0	200.0	
SB RURAL	549+53.00	549+98.00	1.50	45.00	40.0	200.0	200.0	
C.H. 12 RAMP A	7+25.00	7+70.00	1.50	45.00	26.0	130.0	130.0	
C.H. 12 RAMP D	10+38.00	10+83.00	1.50	45.00	26.0	130.0	130.0	
C.H. 8 RAMP A	6+58.00	7+03.00	1.50	45.00	26.0	130.0	130.0	
C.H. 8 RAMP D	8+28.00	8+73.00	1.50	45.00	26.0	130.0	130.0	
							NB RURAL:	1640.0
							SB RURAL:	1720.0
							TOTAL:	3360.0
							ROUNDED:	3360.0

GUARDRAIL REMOVAL

LOCATION	TO	LOCATION	LENGTH (FOOT)	GUARDRAIL REMOVAL 63200310 (FOOT)	
NORTHBOUND					
NB RURAL	RT	305+03.00	306+35.80	BK 132.80	
NB RURAL	RT	305+66.49	AH 305+76.00	9.51	
NB RURAL	RT	335+17.00	342+80.00	763.00	
NB RURAL	LT	339+30.00	342+71.00	341.00	
NB RURAL	RT	344+17.00	345+76.00	159.00	
NB RURAL	RT	547+02.00	550+69.00	367.00	
SOUTHBOUND					
SB RURAL	RT	305+32.00	306+35.80	BK 103.80	
SB RURAL	RT	305+66.49	AH 308+03.00	236.51	
SB RURAL	LT	305+47.00	306+35.80	BK 88.80	
SB RURAL	LT	305+66.49	AH 308+56.00	289.51	
SB RURAL	LT	337+60.00	342+51.00	491.00	
SB RURAL	LT	343+95.00	348+42.00	447.00	
SB RURAL	RT	344+03.00	347+41.00	338.00	
SB RURAL	LT	546+81.00	551+48.00	467.00	
				NB TOTAL:	1,772.31
				SB TOTAL:	2,461.62
				ROUNDED:	4,250.00

PCC SURFACE REMOVAL – VARIABLE DEPTH

LOCATION	STATION	TO	STATION	SHOULDER WIDTH AT LOCATION (FT)	LENGTH (FOOT)	WIDTH (FEET)	AREA (SQ YD)	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH) X4400100 (SQ YD)
NORTHBOUND								
NB DL SHOULDER	338+28.00		341+28.00	10.0	300.00	6.0	200.0	200.0
NB PL SHOULDER	345+59.00		347+59.00	6.00	200.00	6.0	133.3	133.3
NB DL SHOULDER	356+00.00		357+00.00	10.00	100.00	6.0	66.7	66.7
NB PL SHOULDER	546+55.00		549+55.00	6.00	300.00	6.0	200.0	200.0
SOUTHBOUND								
SB DL SHOULDER	336+07.00		341+07.00	10.00	500.00	6.0	333.3	333.3
SB DL SHOULDER	345+47.00		350+47.00	10.00	500.00	6.0	333.3	333.3
SB PL SHOULDER	345+47.00		347+47.00	6.00	200.00	6.0	133.3	133.3
SB DL SHOULDER	370+00.00		372+00.00	10.00	200.00	6.0	133.3	133.3
SB DL SHOULDER	548+98.00		549+98.00	10.00	100.00	6.0	66.7	66.7
SB PL SHOULDER	548+98.00		549+98.00	6.00	100.00	6.0	66.7	66.7
							NB RURAL:	600.0
							SB RURAL:	1066.7
							TOTAL:	1666.7
							ROUNDED:	1670.0

PAVEMENT MARKING REMOVAL

STATION	TO	STATION	# OF WHITE STRIPES	# OF YELLOW STRIPES	LENGTH (FOOT)	STRIPE WIDTH (IN)	PAVEMENT MARKING REMOVAL 78300100 (SQ FT)	
NORTHBOUND								
SN 057-0206 NB RURAL CL	341+34.00		345+53.00	0.25	0.00	419.0	4 34.9 0.0	
NB RURAL CL	503+31.00		506+81.00	0.25	0.00	350.0	4 29.2 0.0	
SOUTHBOUND								
SN 057-0205 SB RURAL CL	341+13.00		345+41.00	0.25	0.00	428.0	4 35.7 0.0	
NB RURAL CL	503+31.00		506+81.00	0.25	0.00	350.0	4 29.2 0.0	
							NB RURAL TOTAL:	64.1
							NB RURAL ROUNDED:	70.0
							SB RURAL TOTAL:	64.9
							SB RURAL ROUNDED:	70.0
							TOTAL:	140.0