SCHEDULE OF QUANTITIES

DELINEATORS (SHEET 2 OF 2)

CH 12 RAMPS

DELINEATORS 63500105 (EACH)							
LOCATION	STATION	SPACING	SINGLE WHITE	SINGLE AMBER	DOUBLE WHITE	DOUBLE AMBER	TRIPLE AMBER
NORTHBOUND RAMPS							
CH 12 RAMP B	12+00.00		1	1			
CH 12 RAMP B	13+00.00	100.0			1		
CH 12 RAMP B	14+00.00	100.0			1		
CH 12 RAMP B	15+00.00	100.0			1		
CH 12 RAMP B	16+00.00	100.0			1		
CH 12 RAMP B	17+00.00	100.0			1		
CH 12 RAMP B	17+70.00						1
CH 12 RAMP B	18+00.00	100.0			1		
CH 12 RAMP B	19+00.00	100.0			1		
CH 12 RAMP B	20+00.00	100.0			1		
CH 12 RAMP B	21+00.00	100.0			1		
CH 12 RAMP B	22+00.00	100.0			1		
CH 12 RAMP B	23+00.00	100.0			1		
CH 12 RAMP B	24+00.00	100.0			1		
CH 12 RAMP B	25+00.00	100.0			1		
CH 12 RAMP B	26+00.00	100.0			1		
CH 12 RAMP C	27+00.00	100.0			1		
CH 12 RAMP C	0+00.00				1		
CH 12 RAMP C	1+00.00	100.0			1		
CH 12 RAMP C	2+00.00	100.0			1		
CH 12 RAMP C	3+00.00	100.0			1		
CH 12 RAMP C	4+00.00	100.0			1		
CH 12 RAMP C	5+00.00	100.0			1		
CH 12 RAMP C	6+00.00	100.0			1		
CH 12 RAMP C	7+00.00	100.0	1	1			
SOUTHBOUND RAMPS							
CH 12 RAMP A	0+00.00				1		
CH 12 RAMP A	1+00.00	100.0			1		
CH 12 RAMP A	2+00.00	100.0			1		
CH 12 RAMP A	3+00.00	100.0			1		
CH 12 RAMP A	4+00.00	100.0			1		
CH 12 RAMP A	5+00.00	100.0			1		
CH 12 RAMP A	5+45.00						1
CH 12 RAMP A	6+00.00	100.0			1		
CH 12 RAMP A	7+00.00	100.0	1	1			
CH 12 RAMP D	11+00.00		1	1			
CH 12 RAMP D	12+00.00	100.0			1		
CH 12 RAMP D	13+00.00	100.0			1		
CH 12 RAMP D	14+00.00	100.0			1		
CH 12 RAMP D	15+00.00	100.0			1		
CH 12 RAMP D	16+00.00	100.0			1		
CH 12 RAMP D	17+00.00	100.0			1		
CH 12 RAMP D	18+00.00	100.0			1		
CH 12 RAMP D	19+00.00	100.0			1		
CH 12 RAMP D	20+00.00	100.0			1		
CH 12 RAMP D	21+00.00	100.0			1		
CH 12 RAMP D	22+00.00	100.0			1		
CH 12 RAMP D	23+00.00	100.0			1		
	NORTHBOUND RAMPS:		2	2	22	0	1
	SOUTHBOUND RAMPS:		2	2	19	0	1

CH 8 RAMPS

DELINEATORS 63500105 (EACH)							
LOCATION	STATION	SPACING	SINGLE WHITE	SINGLE AMBER	DOUBLE WHITE	DOUBLE AMBER	TRIPLE AMBER
NORTHBOUND RAMPS							
CH 8 RAMP B	10+00.00	1000.0	1	1			
CH 8 RAMP B	11+00.00	100.0			1		
CH 8 RAMP B	12+00.00	100.0			1		
CH 8 RAMP B	13+00.00	100.0			1		
CH 8 RAMP B	14+00.00	100.0			1		
CH 8 RAMP B	15+00.00	100.0			1		
CH 8 RAMP B	16+00.00	100.0			1		
CH 8 RAMP B	17+00.00	100.0			1		
CH 8 RAMP B	18+00.00	100.0			1		
CH 8 RAMP B	19+00.00	100.0			1		
CH 8 RAMP B	20+00.00	100.0			1		
CH 8 RAMP B	21+00.00	100.0			1		
CH 8 RAMP B	22+00.00	100.0			1		
CH 8 RAMP C	0+00.00				1		
CH 8 RAMP C	1+00.00	100.0			1		
CH 8 RAMP C	2+00.00	100.0			1		
CH 8 RAMP C	3+00.00	100.0			1		
CH 8 RAMP C	4+00.00	100.0			1		
CH 8 RAMP C	5+00.00	100.0			1		
CH 8 RAMP C	6+00.00	100.0			1		
CH 8 RAMP C	7+00.00	100.0	1	1			
SOUTHBOUND RAMPS							
CH 8 RAMP A	0+00.00				1		
CH 8 RAMP A	1+00.00	100.0			1		
CH 8 RAMP A	2+00.00	100.0			1		
CH 8 RAMP A	3+00.00	100.0			1		
CH 8 RAMP A	4+00.00	100.0			1		
CH 8 RAMP A	5+00.00	100.0			1		
CH 8 RAMP A	6+00.00	100.0	1	1			
CH 8 RAMP A	7+00.00	100.0	1	1			
CH 8 RAMP D	9+00.00		1	1			
CH 8 RAMP D	10+00.00	100.0			1		
CH 8 RAMP D	11+00.00	100.0			1		
CH 8 RAMP D	12+00.00	100.0			1		
CH 8 RAMP D	13+00.00	100.0			1		
CH 8 RAMP D	14+00.00	100.0			1		
CH 8 RAMP D	15+00.00	100.0			1		
CH 8 RAMP D	16+00.00	100.0			1		
CH 8 RAMP D	17+00.00	100.0			1		
CH 8 RAMP D	18+00.00	100.0			1		
CH 8 RAMP D	19+00.00	100.0			1		
CH 8 RAMP D	20+00.00	100.0			1		
CH 8 RAMP D	21+00.00	100.0			1		
	NORTHBOUND RAMPS:		2	2	19	0	0
	SOUTHBOUND RAMPS:		3	3	18	0	0

SUMMARY

DELINEATORS 63500105 (EACH)				
	NB RURAL		SB RURAL	
TYPE	NB MAINLINE	NB RAMPS	SB MAINLINE	SB RAMPS
SINGLE WHITE	21	4	23	5
SINGLE AMBER	29	4	29	5
DOUBLE WHITE	0	41	0	37
DOUBLE AMBER	1	0	1	0
TRIPLE AMBER	10	1	8	1
SUB TOTALS:	111		109	
ROUNDED TOTALS:	120		110	
GRAND TOTAL:	230			

FILE NAME = c:\pw_work\pwidot\bergenaj\d0373914\D570A20-SHT-SCHEDULE.DGN	USER NAME = bergenaj	DESIGNED -	REVISED -
	PLOT SCALE = 40.0000 ' / in.	DRAWN -	REVISED -
$MODELNAME$	PLOT DATE = 8/7/2014	CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: | SHEET 14 OF 14 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	(57-3,57-4)RS	MCLEAN	90	28
		CONTRACT NO. 70A20		
	ILLINOIS	FED. AID PROJECT		