



TYPICAL DITCH SECTION

FAI 55 NORTHBOUND OUTSIDE	LENGTH
STA 1+24 TO STA 1+09	15.0'
FAI 55 SOUTHBOUND OUTSIDE	
STA 1+81 TO STA 2+11	30.0'
RAMP B	
STA 35+65 TO 35+85	20.0'
RAMP C	
STA 5+32 TO 5+52	20.0'

SURPLUS MATERIAL SHALL BE DISPOSED OF OUTSIDE THE RIGHT OF WAY AS SPECIFIED IN ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS.

EROSION CONTROL MEASURES SHALL BE IMPLEMENTED AS FOLLOWS:

INLET PROTECTION AT THE UPSTREAM END OF ALL PIPE CULVERTS AND BOX CULVERTS RECEIVING FLOW FROM THE RE-GRADED DITCH.

TEMPORARY SEEDING AS REQUIRED BY THE SPECIAL PROVISION FOR TEMPORARY EROSION CONTROL SEEDING.

ALL DISTURBED AREAS SHALL BE SEEDED WITH CLASS 2 MIXTURE. FERTILIZER AND MULCH SHALL BE APPLIED AT THE RATES SPECIFIED IN ARTICLES 250.04 & 251.03 OF THE STANDARD SPECIFICATIONS.

SEE SPECIAL PROVISIONS FOR GRADING & SHAPING DITCHES

FILE NAME =	USER NAME = sparksgw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GRADING & SHAPING DITCHES DETAIL			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et:\pwork\pwork\sparksgw\0351843\0672047-sht-details.dgn		DRAWN -	REVISED -					55	(84-4-1)RS-5	SANGAMON	39	37
		CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.			CONTRACT NO. 72G47		ILLINOIS FED. AID PROJECT		
		DATE -	REVISED -									