

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0014		
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	1118	1118		
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SO YD	112	112		
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	2485	2485		
44001114	HOT-MIX ASPHALT SURFACE REMOVAL (ASBESTOS)	SO YD	903	903		
48203007	HOT-MIX ASPHALT SHOULDERS, 2 1/2"	SO YD	2485	2485		
50102400	CONCRETE REMOVAL	CU YD	68.8	68.8		
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	2	2		
50157300	PROTECTIVE SHIELD	SO YD	358	358		
50200100	STRUCTURE EXCAVATION	CU YD	381	381		
50300225	CONCRETE STRUCTURES	CU YD	78.8	78.8		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	610	610		
50300260	BRIDGE DECK GROOVING	SO YD	1362	1362		
50300300	PROTECTIVE COAT	SO YD	1653	1653		
50500505	STUD SHEAR CONNECTORS	EACH	6244	6244		
14						

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0014		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	140880	140880		
50800515	BAR SPLICERS	EACH	1028	1028		
51500100	NAME PLATES	EACH	2	2		
59000200	EPOXY CRACK INJECTION	FOOT	89	89		
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	174	174		
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	1150	1150		
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4		
63200310	GUARDRAIL REMOVAL	FOOT	1284	1284		
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	2755	2755		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4		
67100100	MOBILIZATION	L SUM	1	1		
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD	EACH	4	4		
13	701401					

* SPECIALTY ITEM