

BRIDGE APPROACH PAVEMENT CONNECTOR SCHEDULE

LOCATION		QUANTITY
LANE	STATION TO STATION	(SQ YD)
EB	250+03.57 250+09.57	28
WB	250+41.07 250+47.07	28
EB	251+33.33 251+39.33	28
WB	251+70.83 251+76.83	28
TOTAL		112

HMA AND RUMBLE STRIP SCHEDULE

				BITUMINOUS MATERIALS (PRIME COAT)	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	HOT-MIX ASPHALT SHOULDERS, 2-1/2"	SHOULDER RUMBLE STRIPS, 16 INCH	
LANE	STATION TO STATION		LENGTH (FOOT)	WIDTH (FOOT)	(POUND)	(SQ FT)	(SQ FT)	(SQ FT)
WBPL	248+24.0	257+19.0	895	10	366	814	814	733
EBPL	245+00.0	253+88.0	888	10	363	807	807	726
WBDL	249+35.5	257+12.0	776.5	6	195	432	432	649
EBDL	245+08.0	252+82.5	774.5	6	194	432	432	647
TOTAL					1118	2485	2485	2755

PAVEMENT MARKING SCHEDULE
(FOR STAGE 1 CONSTRUCTION)

DESCRIPTION		STATION TO STATION		LENGTH	(SQ FT)	(FOOT)	(FOOT)	(EACH)	(EACH)	(FOOT)	(FOOT)
EB LANE	RIGHT	230+00.0	251+78.0	2178	871	174		25	25		
EB LANE	LEFT	245+00.00	254+94.50	994.5	666	174	43.5			888	250
WB LANE	LEFT	248+01.50	257+19.00	917.5	671			25	25	895	250
WB LANE	RIGHT	250+39.00	272+19.00	2180	873						
					3081	348	44	50	50	1783	500

PAVEMENT MARKING SCHEDULE
(FOR STAGE 2 CONSTRUCTION)

DESCRIPTION		STATION TO STATION		LENGTH	(SQ FT)	(FOOT)	(FOOT)	(EACH)	(EACH)	(FOOT)	(FOOT)
EB LANE	LEFT	230+00.0	251+77.5	2177.5	869			25	25		
EB LANE	RIGHT	245+08.0	253+85.5	877.5	607					809	250
WB LANE	RIGHT	248+32.0	257+12.0	880	608	174				811	250
WB LANE	LEFT	250+40.5	272+12.0	2171.5	870	174	43.5	25	25		
					2954	348	44	50	50	1620	500

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -
c:\pw_work\pwwork\steffenmk\d0254366\074187-sh1-schedule.dgn		DRAWN -	REVISED -
Default	PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -
	PLOT DATE = 8/15/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES			
SCALE:	SHEET	OF	SHEETS
		STA.	TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	(18-45HB-1)BR	Cumberland	43	5
CONTRACT NO.			74187	
ILLINOIS FED. AID PROJECT				