

80/20 FED/ST

80/20 FED/ST

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0011		
20100500	TREE REMOVAL, ACRES	ACRE	0.45	0.45		
20200100	EARTH EXCAVATION	CU YD	2053	2053		
20300100	CHANNEL EXCAVATION	CU YD	2211	2211		
20400800	FURNISHED EXCAVATION	CU YD	4065	4065		
20600110	GRANULAR EMBANKMENT, SPECIAL	TON	2783	2783		
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	701	701		
* 25000200	SEEDING, CLASS 2	ACRE	2	2		
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	180	180		
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	180	180		
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	180	180		
* 25100115	MULCH, METHOD 2	ACRE	2	2		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	200	200		
28000305	TEMPORARY DITCH CHECKS	FOOT	360	360		
28000315	AGGREGATE DITCH CHECKS	TON	92	92		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0011		
28000500	INLET AND PIPE PROTECTION	EACH	1	1		
28100105	STONE RIPRAP, CLASS A3	SQ YD	2087	2087		
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	2352.4	2352.4		
28100107	STONE RIPRAP, CLASS A4	SQ YD	2411	2411		
28200200	FILTER FABRIC	SQ YD	4855.4	4855.4		
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	12	12		
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	5330	5330		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	303	303		
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	251	251		
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	90	90		
40701896	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 3/4"	10 SQ YD	2057	2057		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	10	10		
44004000	PAVED DITCH REMOVAL	FOOT	1824	1824		
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	674	674		

13

14 * SPECIALTY ITEM

FILE NAME =	USER NAME = teasleyok	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pwork\pwork\teasleyok\20117991\077950-sht-sq.dgn		DRAWN -	REVISED -			749	122BR/B-1	Colos	60	3	
PLOT SCALE = 1/8"=20' / in.		CHECKED -	REVISED -			CONTRACT NO. 74350					
PLOT DATE = 8/21/2014		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					