

80/20 FED/ST

80/20 FED/ST

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0011		
* A2001020	TREE, ACER RUBRUM (RED MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	9	9		
* A2001720	TREE, ACER SACCHARUM (SUGAR MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	7	7		
* A2006520	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	5	5		
* A2007620	TREE, TAXODIUM DISTICHUM (COMMON BALD CYPRESS), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	10	10		
* B2001116	TREE, CERCIS CANADENSIS (EASTERN REDBUD), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	12	12		
* D2002972	EVERGREEN, PINUS STROBUS (EASTERN WHITE PINE), 6' HEIGHT, BALLED AND BURLAPPED	EACH	6	6		
X0321816	OSTERBERG LOAD CELL TEST	EACH	1	1		
X4201410	BRIDGE APPROACH PAVEMENT CONNECTOR (SPECIAL)	SO YD	102	102		
X5030305	CONCRETE WEARING SURFACE, 5"	SO YD	229.8	229.8		
X5040100	PRECAST BRIDGE APPROACH SLAB	SO FT	2030	2030		
X5860110	GRANULAR BACKFILL FOR STRUCTURES	CU YD	264	264		
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28	28		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0011		
Z0001495	BRIDGE APPROACH SHOULDER REMOVAL	SO YD	20	20		
Z0004552	APPROACH SLAB REMOVAL	SO YD	146	146		
Z0016702	DETOUR SIGNING	L SUM	1	1		
Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	4	4		
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	174	174		
<del>Z0076600</del>	<del>TRAINEES</del>	<del>HOOR</del>	<del>500</del>	<del>500</del>		

|| \* SPECIALTY ITEM

FILE NAME =	USER NAME = teeslayok	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
\\pcr\work\psidot\teeslayok\08117991\077	250-411-000.dgn	DRAWN -	REVISED -			749	(122BRIB-1)	Colos	60	6	
PLOT SCALE = 100,0000' / 1"		CHECKED -	REVISED -			CONTRACT NO. 74350					
PLOT DATE = 8/21/2014		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					

SCALE: SHEET OF SHEETS STA. TO STA.