

INDEX OF SHEETS

SHEET NO.	ITEM
1	COVER SHEET
2	INDEX OF SHEETS, GENERAL NOTES, & LOCATION DESCRIPTIONS
3	SUMMARY OF QUANTITIES
4-14	EXISTING STRUCTURE PLANS
15	LOCATION MAP

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED AFTER SHEET NO. 15:

STD. NO.	DESCRIPTION
000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
701001-02	OFF-ROAD OPERATIONS, 2L2W, 15' MINIMUM AWAY FROM PAVEMENT EDGE
701006-05	OFF-ROAD OPERATIONS, 2L2W, 15' AWAY TO EDGE OF PAVEMENT
701201-04	LANE CLOSURE, 2L2W, DAY ONLY
701901-03	TRAFFIC CONTROL DEVICES

GENERAL NOTES

THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS, THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" ADOPTED JANUARY 1, 2012; THE SUPPLEMENTAL SPECIFICATIONS, THE RECURRING SPECIAL PROVISIONS, AND THE SPECIAL PROVISIONS INCLUDED IN THE PROPOSAL.

THE PROPOSED PROJECT IS LOCATED AT 2 LOCATIONS ON ILLINOIS ROUTE 15 IN WAYNE COUNTY IN DISTRICT 7.

THE WORK INCLUDED IN THIS SECTION CONSISTS OF CLEANING AND PAINTING THE BRIDGES AS SPECIFIED IN THE PLANS AND SPECIAL PROVISIONS.

THE STRUCTURAL STEEL SHALL BE CLEANED AND PAINTED AS SPECIFIED IN THE PLANS AND THE SPECIAL PROVISIONS.

ALL DECK DRAINS SHALL BE PAINTED ACCORDING TO THE REQUIREMENTS OF PAINT SYSTEM 1 - OZ/E/U. ANY DAMAGE CAUSED BY THE CONTRACTOR SHALL BE REPAIRED AT THEIR OWN EXPENSE AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

ONLY STRUCTURAL STEEL IS TO BE PAINTED. ALL OTHER SURFACES WILL BE PROTECTED FROM BEING PAINTED. ALL PAINT AND OVERSPRAY WILL BE REMOVED AT THE CONTRACTOR'S EXPENSE.

THE SSPC QP1 AND QP2 PAINTING CONTRACTOR CERTIFICATION WILL BE REQUIRED FOR THIS PROJECT.

BRIDGE LOCATION DESCRIPTIONS

LOCATION #1

ROUTE: FAP 823
 MARKED: IL 15
 SECTION: 22BR-7
 STATION: 492+75
 STRUCTURE NUMBER: 096-0010

TYPE OF BRIDGE: Plate Girder-3 Spans (5 Girders)
 & Wide Flange I-Beams-18 Spans (5 Beams)

LOCATION: 4.5 miles west of the Edwards County line
 FEATURE CARRIED/SPANNED: IL 15 over the Little Wabash River

COLOR OF THE FINISH COAT SHALL BE GREEN, MUNSELL 10B 3/6

Cleaning and painting of the existing structural steel shall be as specified in the special provision for "Cleaning and Painting Existing Steel Structures". All structural steel including beams, girders, bearings and diaphragms/lateral bracing, within 5' (measured along the beam/girder) of the abutments and any expansion joints at piers, shall be cleaned by SSPC-SP10- Near White Metal Blast Cleaning. The fascia beams/girders, for the entire length of the bridge, shall be cleaned in their entirety by SSPC-SP10- Near White Metal Blast Cleaning.

The designated areas cleaned per Near White Metal Blast Cleaning - SSPC-SP10 shall be painted according to the requirements of Paint System 1 - OZ/E/U.

2 air monitors will be required at this location.

LOCATION #2

ROUTE: FAP 823
 MARKED: IL 15
 SECTION: 22-BR-3
 STATION: 348+61.5
 STRUCTURE NUMBER: 096-0061

TYPE OF BRIDGE: Wide Flange I-Beams-6 Spans (5 Beams)
 LOCATION: 2 miles west of the Edwards County line
 FEATURE CARRIED/SPANNED: IL 15 over White Oak Slough

COLOR OF THE FINISH COAT SHALL BE GREEN, MUNSELL 10B 3/6

Cleaning and painting of the existing structural steel shall be as specified in the special provision for "Cleaning and Painting Existing Steel Structures". All structural steel, including beams, bearings and diaphragms, within 5' (measured along the beam) of the abutments and any expansion joints at piers shall be cleaned by SSPC-SP10- Near White Metal Blast Cleaning. The outside and bottom of the bottom flange of the fascia beams, for the entire length of the bridge, shall be cleaned in their entirety by SSPC-SP10- Near White Metal Blast Cleaning.

The designated areas cleaned per Near White Metal Blast Cleaning - SSPC-SP10 shall be painted according to the requirements of Paint System 1 - OZ/E/U.

No air monitors will be required at this location.

FILE NAME =	USER NAME = steffenhk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, GENERAL NOTES AND BRIDGE LOCATION DESCRIPTIONS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
g:\pwork\psidot\stehfennk\0848359\0	74700-idx-index.dgn	DRAWN -	REVISED -			823 D7 BRIDGE PAINTING 2015-4	WAYNE	15	2	
Default	PLOT SCALE = 100,0000 1/16"	CHECKED -	REVISED -			CONTRACT NO. 74700				
	PLOT DATE = 6/5/2014	DATE -	REVISED -			SCALE: N/A	SHEET 1 OF 1 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT	