



VIEW A-A

From Sta. 9+99.75 to Sta. 10+75.79
**PART SECTION THRU PARAPET
 FOR PANEL POINTS 0 THRU 3**

Notes:
 See existing parapet erection plans and sheet S31 for additional details.
 Drilled and set dowel bars shall be installed according to Article 584 of the Standard Specifications.
 Non shrink grout according to Article 1024 of the Standard Specifications shall be used for the grout pad.
 Dowel bars shall be threaded and the material shall conform to the requirements of ASTM A307.
 The cost of grout pad, dowel bars, chemical adhesive and installation shall be included in the cost of Steel Post, Attached to Structure.



USER NAME *	DESIGNED - ZJB	REVISED
	CHECKED - YSS	REVISED
PLOT SCALE *	DRAWN - PRC	REVISED
PLOT DATE * 05/02/2014	CHECKED - ZJB	REVISED

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

MAIN SPANS ALUMINUM PARAPET DETAILS - CONCRETE DECK-2
 S.N. 082-6001 MLK BRIDGE OVER MISSISSIPPI RIVER

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
799	1BR, ORS-2	ST. CLAIR	156	50
			CONTRACT NO. 76B03	
ILLINOIS FED. AID PROJECT				