

PATCHING SCHEDULE

LOCATION	NB/SB	LENGTH	WIDTH	CLASS B PAVEMENT PATCHES 9"	SAW CUTS	DOWEL BARS
				TYPE 2		
MILE PT.		(FEET)	(FEET)	(SQ YD)	(FOOT)	(EACH)
0.000	NB	10	12	13.3	56	20
0.000	SB	10	12	13.3	56	20
0.008	NB	6	12	8.0	48	20
0.008	SB	6	12	8.0	48	20
0.018	NB	6	12	8.0	48	20
0.018	SB	6	12	8.0	48	20
0.117	SB	6	12	8.0	48	20
0.136 TO 0.164 BRIDGE OMISSION						
0.238	NB	6	12	8.0	48	20
0.265	SB	6	12	8.0	48	20
0.304	SB	6	12	8.0	48	20
0.351	NB	6	12	8.0	48	20
0.351	SB	6	12	8.0	48	20
0.361	NB	6	12	8.0	48	20
0.364	SB	6	12	8.0	48	20
0.784	EMERALD RD					
1.609	NB	6	12	8.0	48	20
1.614	SB	6	12	8.0	48	20
1.629	NB	6	12	8.0	48	20
1.629	SB	6	12	8.0	48	20
SUBTOTAL						
				154.7	880	360

LOCATION	NB/SB	LENGTH	WIDTH	CLASS B PAVEMENT PATCHES 9"	SAW CUTS	DOWEL BARS
				TYPE 2		
1.652	SB	6	12	8.0	48	20
1.661	NB	6	12	8.0	48	20
1.661	SB	6	12	8.0	48	20
1.671	SB	6	12	8.0	48	20
1.680	NB	6	12	8.0	48	20
1.680	SB	6	12	8.0	48	20
1.689	NB	6	12	8.0	48	20
1.689	SB	6	12	8.0	48	20
1.700	NB	6	12	8.0	48	20
1.700	SB	6	12	8.0	48	20
1.704	NB	6	12	8.0	48	20
1.704	SB	6	12	8.0	48	20
1.708	NB	6	12	8.0	48	20
1.718	NB	6	12	8.0	48	20
1.724	SB	6	12	8.0	48	20
1.728	NB	6	12	8.0	48	20
1.735	WALCOTT RD					
1.738	NB	6	12	8.0	48	20
1.792 TO 1.835 BRIDGE OMISSION						
1.885	SB	6	12	8.0	48	20
1.893	NB	6	12	8.0	48	20
SUBTOTAL						
				152.0	912	380