

# PATCHING SCHEDULE

LOCATION	NB/SB	LENGTH	WIDTH	CLASS B PAVEMENT PATCHES 9" TYPE 2	SAW CUTS	DOWEL BARS
1.937	NB	6	12	8.0	48	20
1.941	NB	6	12	8.0	48	20
1.941	SB	6	12	8.0	48	20
1.946	NB	6	12	8.0	48	20
1.946	SB	6	12	8.0	48	20
1.952	SB	6	12	8.0	48	20
1.956	SB	6	12	8.0	48	20
1.961	SB	6	12	8.0	48	20
1.966	SB	6	12	8.0	48	20
1.978	NB	6	12	8.0	48	20
1.993	NB	6	12	8.0	48	20
2.003	NB	6	12	8.0	48	20
2.012	NB	6	12	8.0	48	20
2.022	NB	6	12	8.0	48	20
2.031	NB	6	12	8.0	48	20
2.031	SB	6	12	8.0	48	20
2.036	NB	6	12	8.0	48	20
2.036	SB	6	12	8.0	48	20
2.038	NB	6	12	8.0	48	20
2.041	NB	6	12	8.0	48	20
2.041	SB	6	12	8.0	48	20
<b>SUBTOTAL</b>				168.0	1008	420

LOCATION	NB/SB	LENGTH	WIDTH	CLASS B PAVEMENT PATCHES 9" TYPE 2	SAW CUTS	DOWEL BARS
2.050	SB	6	12	8.0	48	20
2.060	NB	6	12	8.0	48	20
2.060	SB	6	12	8.0	48	20
2.069	NB	6	12	8.0	48	20
2.069	SB	6	12	8.0	48	20
2.079	NB	6	12	8.0	48	20
2.079	SB	6	12	8.0	48	20
2.088	NB	6	12	8.0	48	20
2.432	NB	6	12	8.0	48	20
2.452	NB	6	12	8.0	48	20
2.455	NB	6	12	8.0	48	20
2.499	NB	6	12	8.0	48	20
2.523	NB	6	12	8.0	48	20
2.523	SB	6	12	8.0	48	20
2.528	NB	6	12	8.0	48	20
2.547	NB	6	12	8.0	48	20
2.556	NB	6	12	8.0	48	20
2.582	NB	6	12	8.0	48	20
2.594	NB	6	12	8.0	48	20
2.614	NB	6	12	8.0	48	20
2.633	NB	6	12	8.0	48	20
2.642	NB	6	12	8.0	48	20
2.651	NB	6	12	8.0	48	20
2.665	NB	6	12	8.0	48	20
2.680	NB	6	12	8.0	48	20
2.686	NB	6	12	8.0	48	20
2.691	NB	6	12	8.0	48	20
2.719	NB	6	12	8.0	48	20
2.738	SB	6	12	8.0	48	20
2.749	NB	6	12	8.0	48	20
2.749	SB	6	12	8.0	48	20
<b>2.801 KEYESPORT RD</b>						
<b>SUBTOTAL</b>				248	1488	620
<b>TOTAL</b>				723	4288	1780
<b>15% ANT. FAILURES</b>				108	643	267
<b>TOTAL + 15%</b>				831	4931	2047

LOCATION			PAINT PAVEMENT MARKING		RAISED REFLECTIVE PAVEMENT MARKERS
			4"		
M.P.	TO	M.P.	EDGE LINE (FOOT)	SKIP DASH LINE (FOOT)	(EACH)
0.000	TO	3.403	542	542	8

NOTE: PAVEMENT MARKING AND RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE APPLIED IN THE PATCHING AREA ONLY