

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				80% FEDERAL 20% STATE ROADWAY	80% FEDERAL 20% STATE BRIDGE
				0004 NONE	0014 NONE
28100109	STONE RIPRAP, CLASS A5	SO YD	182		182
28200200	FILTER FABRIC	SO YD	126		126
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	842	842	
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	36	36	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	176	176	
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	92	92	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SO YD	76	76	
44000100	PAVEMENT REMOVAL	SO YD	233	233	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	418	418	
50102400	CONCRETE REMOVAL	CU YD	19.8		19.8
50104650	SLOPE WALL REMOVAL	SO YD	70		70
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1		1
50200100	STRUCTURE EXCAVATION	CU YD	120		120
50300100	FLOOR DRAINS	EACH	20		20

\* SEE SPECIAL PROVISIONS  
 Δ DENOTES SPECIALTY ITEM

FILE NAME = 0978231-sht-500.dgn  
 MODEL = Default  
 PLOT DRIVER = 1001.pdf.plt



USER NAME = twalker  
 FILE NAME = 0978231-sht-500.dgn  
 PLOT SCALE = 100.0000 / in.  
 PLOT DATE = 7/8/2014

DESIGNED - MCV  
 DRAWN - CMM  
 CHECKED - MTM  
 DATE - 8/12

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 2 OF 6 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
877	100B-1	WHITE	54	4
			CONTRACT NO. 78231	
[ILLINOIS] FED. AID PROJECT				