

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				80% FEDERAL 20% STATE ROADWAY	80% FEDERAL 20% STATE BRIDGE
				0004 NONE	0014 NONE
50300225	CONCRETE STRUCTURES	CU YD	54.8		54.8
50300255	CONCRETE SUPERSTRUCTURE	CU YD	316.5		316.5
50300260	BRIDGE DECK GROOVING	SQ YD	800		800
50300300	PROTECTIVE COAT	SQ YD	1036		1036
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	5180		5180
50500505	STUD SHEAR CONNECTORS	EACH	2880		2880
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	77150		77150
50800515	BAR SPLICERS	EACH	70		70
51100300	SLOPE WALL 6 INCH	SQ YD	40		40
51500100	NAME PLATES	EACH	1		1
52000110	PREFORMED JOINT STRIP SEAL	FOOT	68		68
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	12		12
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	6		6
52100505	ANCHOR BOLTS, 5/8"	EACH	36		36

* SEE SPECIAL PROVISIONS
 Δ DENOTES SPECIALTY ITEM

FILE NAME : 0978231-101-500.dgn
 MODEL : 0a1.dwg
 PLOT DRIVER : TDT_PDF.plt



USER NAME : walker
 FILE NAME : 0978231-101-500.dgn
 PLOT SCALE : 100.0000 / 1 in.
 PLOT DATE : 7/8/2014

DESIGNED - MCV
 DRAWN - CMM
 CHECKED - MTM
 DATE - 8/12

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 3 OF 6 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
877	100B-1	WHITE	54	5
CONTRACT NO. 78231				
ILLINOIS FED. AID PROJECT				