Rubblization Pavement and Subsurface Investigation

FAI 57

Contract 78380

Northbound

Station	Location				Thickness, in.			Subbase condition			Subgrade IBV					Soil Information						
	PS	PL	DL	DS	AC Overlay	PCC	Subbase	Sound	SI Deter	Deter	0-6"	6-12"	12-18"	18-24"	24-30"	Classification	Sand	Silt	Clay	LL	PI	% H_2O
18+00					4 1/4	10 1/2	4		AGG		8.5	16.0	27.0	23.0		SAL A-4(0)	54	30	16	23	4.7	12
" "					7		8		AGG		30.0	30.0	30.0									
8+00					4 1/4	10 3/4	4		AGG		7.0	12.0	21.0	20.0								
" "					8		8		AGG		16.0	14.0	12.0	12.0								
1569+00					6 1/2	8	4		AGG		8.5	4.0	8.5	10.0								
New 3rd Lane Built - Skipped																						
1559+00					6	10	4		AGG		12.0	7.0	8.5	10.0		SIC-SICL A7-6(21)	12	59	29	41.5	23.4	21
" "					10		6		AGG		8.5	8.5	7.0	7.0								
1551+00					5 1/2	10 1/2	4		AGG		4.0	5.5	7.0	5.5								
New 3rd Lane Built - Skipped																						

FILE NAME =	USER NAME = colemm	DESIGNED -	REVISED -
c:\pw_work\pwidot\colemm\d0351283\78380-sht1-details.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
Default	PLOT DATE = 8/22/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

RUBBLIZATION PAVEMENT & SUBSURFACE INVESTIGATION

SCALE: | SHEET OF SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	WILLIAMSON	107	10
		CONTRACT NO. 78380		
		ILLINOIS FED. AID PROJECT		

(X1-8,X1-7-1,X1-7,X1-6-1)R-1