

Rubblization Pavement and Subsurface Investigation

FAI 57

Contract 78380

Southbound

Station	Location				Thickness, in.			Subbase condition			Subgrade IBV					Soil Information						
	PS	PL	DL	DS	AC Overlay	PCC	Subbase	Sound	SI Deter	Deter	0-6"	6-12"	12-18"	18-24"	24-30"	Classification	Sand	Silt	Clay	LL	PI	% H ₂ O
302+00					4 1/2	9 1/2					7.0	5.5	16.0	17.0								
" "					2	12	4		AGG		10.0	14.0	7.0	10.0								
313+00					4	9 1/2	4		AGG		10.0	30.0	30.0	30.0								
" "					8 1/2		6		AGG		7.0	17.0	14.0	14.0								
323+00					3 3/4	10	6		AGG		12.0	12.0	8.5	10.0		SICL A-6(9)	21	59	20	31.4	12.3	14
" "					7		6		AGG		14.0	14.0	20.0	20.0								
333+50					4	10	6		AGG		5.5	7.0	14.0	14.0								
" "					8		6		AGG		4.0	10.0	12.0	14.0								
343+00					4	10 1/2	6		AGG		14.0	14.0	14.0	17.0		SICL A-6(12)	2	75	23	33.0	12.3	21
" "					6 3/4		6		AGG		17.0	14.0	17.0	17.0								
354+00					3 1/2	10	4		AGG		2.9		14.0	12.0								
" "					7 1/2		6		AGG		12.0	7.0	10.0	8.5								
366+00					4	10 1/4	4		AGG		8.5	30.0	30.0	30.0								
" "					12 1/2		6		AGG		7.0	12.0	21.0	21.0								
372+00					4	9 1/2	6		AGG		8.5	30.0	30.0	30.0								
" "					8		6		AGG		7.0	30.0	30.0	30.0								
382+00					4	10	4		AGG		20.0	23.0	30.0	30.0								
" "					13 1/4		6		AGG		20.0	30.0	30.0	30.0								
393+00					3 3/4	12	4		AGG		1.8	2.9	30.0	30.0								
" "					13 1/2						4.0	7.0	8.5	14.0								
405+00					4 1/4	11	4		AGG		8.5	14.0	30.0	30.0								
" "					14						5.5	30.0	30.0	30.0								