

CROSS ROAD PIPES AND ESTIMATED FILL HEIGHT

STATION	ESTIMATED FILL (FT)		DESCRIPTION
	NB	SB	
1545+19	6.0		36" RCCP
1546+60		4.2	36" RCCP
1563+34	7.7		48" RCCP
1564+00		5.1	48" RCCP
2+30	16.1	15.2	48" RCCP
7+50	6.8		24" RCCP
8+66	8.0		36" RCCP
10+48		6.0	36" RCCP
25+00	4.8		24" RCCP
32+10	14.0		36" RCCP
33+22		9.0	36" RCCP
49+02		7.1	24" RCCP
56+00	7.0	7.1	60" RCCP
78+05		11.0	24" RCCP
81+15	8.9	9.0	60" RCCP
84+15		7.9	24" RCCP
89+18	6.6		24" RCCP
96+70	3.0	7.3	36" RCCP
101+34		7.6	48" RCCP
102+77	5.5		48" RCCP
108+96		7.6	36" RCCP
109+31	4.8		36" RCCP
123+34	11.5	2.7	36" RCCP
128+15		5.2	36" RCCP
129+15	11.1		36" RCCP
139+52		12.4	42" RCCP
139+97	15.8		42" RCCP
147+45	6.2	4.7	36" RCCP

STATION	ESTIMATED FILL (FT)		DESCRIPTION
	NB	SB	
159+00	25.4	23.8	60" RCCP
163+38	5.6	8.6	36" RCCP
172+50	9.6	4.3	36" RCCP
177+17	9.4	3.6	36" RCCP
182+00	7.4		24" RCCP
183+40		3.8	36" RCCP
183+02	11.5		36" RCCP
186+50	10.4	3.7	48" RCCP
197+54	7.2		24" RCCP
208+52	13.8		36" RCCP
208+71		4.2	36" RCCP
212+03	5.0		24" RCCP
222+99	22.1	20.9	54" RCCP
226+61	9.5	6.7	36" RCCP
234+40	8.6	5.0	36" RCCP
245+00		6.1	24" RCCP
246+44		17.6	8' X6' BOX
247+12	17.9		8' X6' BOX
249+17	11.2	1.4	8' X6' BOX
253+00	13.5	9.1	60" RCCP
261+00		3.6	24" RCCP
268+50		2.1	24" RCCP
272+85		7.1	24" RCCP
287+00	1.8		24" RCCP
289+00		6.7	24" RCCP
293+39		4.7	48" RCCP
295+14	7.0		48" RCCP
296+00	4.8	1.8	24" RCCP

STATION	ESTIMATED FILL (FT)		DESCRIPTION
	NB	SB	
305+00	6.8		24" RCCP
300+00		2.1	24" RCCP
303+00		5.4	24" RCCP
303+54	4.9		6' X6' BOX
304+59		5.3	6' X6' BOX
320+30		3.1	36" RCCP
322+00		4.6	24" RCCP
321+94	3.5		36" RCCP
328+78		7.8	5' X3' BOX
330+29	8.7		5' X3' BOX
355+02		18.8	60" RCCP
356+41	18.2		60" RCCP
362+00		3.6	24" RCCP
376+40	7.1		24" RCCP
386+00	5.3		24" RCCP
388+15	14.9	15.3	60" RCCP
391+64	0.0		16' X14' BOX
392+63		0.0	16' X14' BOX
392+44		4.0	36" RCCP
393+21		5.6	36" RCCP
411+00	5.8		24" RCCP
412+00	12.0	8.2	36" RCCP
434+00		3.8	24" RCCP
436+25	31.5		5' X4' BOX
440+72		40.9	5' X4' BOX
440+17		57.0	5' X4' BOX
440+98	28.5		5' X4' BOX
443+52		5.9	24" RCCP
453+85	22.3	29.8	4' X6' BOX
455+00		4.9	24" RCCP

ESTIMATED FILL WAS CALCULATED FROM THE TOP OF PIPE TO TOP OF EXISTING PAVEMENT
IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY FIELD CONDITIONS