

SB MAINLINE RESURFACING SCHEDULE

LOCATION				LENGTH	HMA SURFACE REMOVAL, 4"	HMA SURFACE REMOVAL, 2"	PAV' T REM., 14"	RUBB. PCC PAV' T	HMA BINDER COURSE	POLY HMA BINDER COURSE	POLY HMA SURFACE COURSE	MATERIAL TRANSFER DEVICE	HOT-MIX ASPHALT SHLD*
STATION TO STATION													
				FEET	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	TON	TON	TON
SOUTHBOUND													
1542+30.00		TO	1556+00.00	1370.00	0	3943	4567	0	3197	575	724	4496	232
1556+00.00		TO	1572+91.61	BK 1691.61	0	5357	4511	0	3158	568	758	4484	347
00+00.00	AH	TO	01+00.79	100.79	0	319	269	0	188	34	45	267	21
01+00.79		TO	02+55.79	155.00	0	77	413	0	289	52	46	388	68
02+55.79		TO	17+65.41	BK 1509.62	4026	0	0	4026	1691	507	451	2649	1238
17+82.93	AH	TO	39+20.00	2137.07	5699	0	0	5699	2394	718	638	3750	1752
39+20.00		TO	43+10.00	390.00	0	306	1040	0	728	131	116	976	154
43+10.00		TO	51+00.00	790.00	2107	0	0	2107	885	265	236	1386	648
51+00.00		TO	53+00.00	200.00	533	0	0	533	224	67	60	351	212
53+00.00		TO	63+53.00	1053.00	0	3600	2808	0	1966	354	314	2634	524
63+53.00		TO	66+52.00	299.00	0	0	0	0	0	0	0	0	0
66+52.00		TO	74+00.00	748.00	0	2430	1995	0	1396	251	223	1871	393
74+00.00		TO	76+00.00	200.00	533	0	0	533	224	67	60	351	212
76+00.00		TO	92+58.36	BK 1658.36	4422	0	0	4422	1857	557	495	2910	1359
92+39.80	AH	TO	170+31.62	BK 7791.82	20778	0	0	20778	8727	2618	2327	13672	6388
170+47.27	AH	TO	215+39.65	BK 4492.38	11980	0	0	11980	5031	1509	1342	7883	3683
215+35.61	AH	TO	218+25.55	BK 289.94	773	0	0	773	325	97	87	509	238
217+83.13	AH	TO	261+15.00	4331.87	11552	0	0	11552	4852	1456	1294	7601	3551
261+15.00		TO	265+35.00	420.00	0	249	1120	0	784	141	125	1051	167
265+35.00		TO	361+90.00	9655.00	25747	0	0	25747	10814	3244	2884	16941	7915
361+90.00		TO	366+19.00	429.00	0	380	1144	0	801	144	128	1073	173
366+19.00		TO	409+00.00	4281.00	11416	0	0	11416	4795	1438	1279	7512	3509
409+00.00		TO	413+20.00	420.00	0	365	1120	0	784	141	125	1051	174
413+20.00		TO	434+45.00	2125.00	5667	0	0	5667	2380	714	635	3729	1742
434+45.00		TO	438+80.00	435.00	0	391	1160	0	812	146	130	1088	163
438+80.00		TO	462+04.07	2324.07	5784	0	0	5784	2446	760	696	3902	1846
SB MAINLINE SUBTOTAL					111016	17417	20146	111016	60746	16558	15219	92522	36710

* SEE PAVED SHOULDER REMOVAL AND REPLACEMENT SCHEDULE FOR ADDITIONAL QUANTITY