

**RAMP RESURFACING SCHEDULE**

LOCATION			LENGTH	HMA SURFACE REMOVAL, 4"	HMA SURFACE REMOVAL, 2"	PAV' T REM., 14"	RUBB. PCC PAV' T	HMA BINDER COURSE	POLY HMA BINDER COURSE	POLY HMA SURFACE COURSE	MATERIAL TRANSFER DEVICE	HOT-MIX ASPHALT SHLD*	
STATION TO STATION				FEET	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	TON	TON	TON
NB WEIGH STATION													
00+00.00	TO	07+61.00	761.00	0	539	0	0	177	89	92	0	340	
42+34.00	TO	58+63.56	1629.56	0	1311	0	0	415	186	179	0	759	
SB WEIGH STATION													
00+00.00	TO	01+79.68	179.68	0	160	160	0	112	20	18	0	74	
01+79.68	TO	05+55.00	375.32	0	196	0	0	72	45	54	0	154	
32+53.00	TO	50+00.00	1747.00	0	1415	0	0	447	199	190	0	816	
RAMP CB													
45+14.00	TO	55+48.00	1034.00	0	1172	0	0	372	168	163	0	472	
55+48.00	TO	57+38.05	190.05	0	253	0	0	0	0	9	0	80	
RAMP BC													
00+00.00	TO	07+63.00	763.00	0	540	0	0	178	89	92	0	341	
RAMP AC													
00+00.00	TO	13+82.00	1382.00	3685	0	0	3685	1548	464	413	0	666	
13+82.00	TO	18+83.00	501.00	0	923	0	0	301	147	151	0	277	
RAMP CA													
40+15.00	TO	45+73.00	558.00	0	1075	0	0	303	148	168	0	316	
45+73.00	TO	49+93.00	420.00	0	467	980	0	686	123	110	0	314	
49+93.00	TO	62+12.00	1219.00	0	1219	0	0	375	154	137	0	588	
RAMP A													
00+00.00	TO	04+27.00	427.00	0	759	0	0	0	0	43	0	185	
04+27.00	TO	07+98.00	371.00	0	660	0	0	147	76	75	0	129	
07+98.00	TO	17+14.95	916.95	0	2853	0	0	0	0	183	0	137	
RAMP B													
00+30.00	TO	04+29.00	399.00	0	709	0	0	0	0	40	0	173	
04+29.00	TO	06+75.00	246.00	0	437	0	0	79	48	50	0	80	
06+75.00	TO	17+50.62	1075.62	0	3346	0	0	0	0	214	0	161	
RAMP C													
00+12.00	TO	11+56.00	1144.00	0	3559	0	0	0	0	228	0	171	
11+56.00	TO	14+18.00	262.00	0	466	0	0	88	51	53	0	87	
RAMP D													
00+12.00	TO	11+23.00	1111.00	0	3456	0	0	0	0	221	0	166	
11+23.00	TO	21+89.00	1066.00	0	1895	0	0	528	232	213	0	397	
RAMP SUBTOTAL					3685	27410	1140	3685	5827	2240	3096	0	6881
NB MAINLINE SUBTOTAL					111853	18206	18676	111853	60068	16478	15161	91707	37719
SB MAINLINE SUBTOTAL					111016	17417	20146	111016	60746	16558	15219	92522	36710
TOTAL					226554	63033	39962	226554	126641	35275	33475	184229	81310

\* SEE PAVED SHOULDER REMOVAL AND REPLACEMENT SCHEDULE FOR ADDITIONAL QUANTITY