

**RAMP RESURFACING SCHEDULE**

LOCATION			LENGTH	POLY BIT. MAT'L (PRIME COAT)	BIT. MAT'L (PRIME COAT)	SUBBASE GRANULAR MATERIAL, TYPE A, 12"	SHLD RUMBLE STRIPS, 16"	HMA SURFACE REMOVAL - BUTT JOINT	TEMP RAMP
STATION TO STATION									
			FEET	POUND	POUND	SO YD	FEET	SO YD	SO YD
NB WEIGH STATION									
00+00.00	TO	09+16.00	916.00	304	723	0	0	124	0
40+79.00	TO	58+63.56	1784.56	652	1548	0	0	124	0
SB WEIGH STATION									
00+00.00	TO	01+79.68	179.68	72	144	160	0	0	0
01+79.68	TO	07+10.00	530.32	150	357	0	0	124	0
30+98.00	TO	50+00.00	1902.00	699	1660	0	0	124	0
RAMP CB									
43+59.00	TO	55+48.00	1189.00	620	1086	0	0	124	124
55+48.00	TO	57+38.05	190.05	38	76	0	0	0	0
RAMP BC									
00+00.00	TO	09+18.00	918.00	305	725	0	0	124	124
RAMP AC									
00+00.00	TO	13+82.00	1382.00	1658	1866	0	0	0	0
13+82.00	TO	18+83.00	501.00	601	789	0	0	178	0
RAMP CA									
38+60.00	TO	45+73.00	713.00	670	879	0	0	178	0
45+73.00	TO	49+93.00	420.00	441	651	980	0	0	0
49+93.00	TO	62+12.00	1219.00	549	1189	0	0	0	0
RAMP A									
00+00.00	TO	04+27.00	427.00	171	171	0	0	0	0
04+27.00	TO	09+53.00	526.00	297	371	0	0	0	0
09+53.00	TO	17+14.95	761.95	734	550	0	0	0	124
RAMP B									
00+30.00	TO	04+29.00	399.00	160	160	0	0	0	0
04+29.00	TO	08+30.00	401.00	197	246	0	0	0	0
08+30.00	TO	17+50.62	920.62	860	645	0	0	0	124
RAMP C									
00+12.00	TO	10+01.00	989.00	915	686	0	0	0	124
10+01.00	TO	14+18.00	417.00	210	262	0	0	0	0
RAMP D									
00+12.00	TO	09+68.00	956.00	889	667	0	0	0	124
09+68.00	TO	21+89.00	1221.00	853	1066	0	0	0	0
<b>RAMP SUBTOTAL</b>				<b>12044</b>	<b>16515</b>	<b>1140</b>	<b>0</b>	<b>1100</b>	<b>747</b>
<b>NB MAINLINE SUBTOTAL</b>				<b>60881</b>	<b>94968</b>	<b>18676</b>	<b>98206</b>	<b>191</b>	<b>922</b>
<b>SB MAINLINE SUBTOTAL</b>				<b>61107</b>	<b>94987</b>	<b>20146</b>	<b>97997</b>	<b>191</b>	<b>811</b>
<b>TOTAL</b>				<b>134032</b>	<b>206470</b>	<b>39962</b>	<b>196203</b>	<b>1482</b>	<b>2480</b>