

GUARDRAIL SCHEDULE

LOCATION STATION TO STATION				GUARDRAIL REMOVAL	SPBGR TYPE A	SPBGR TYPE A 9' POST	TRAFFIC BARRIER TERMINAL				GUARDRAIL MARKERS	TERMINAL MARKERS DIRECT APPLIED	CONCRETE CURB, TYPE B	VERTICAL ADJUSTMENT	COMMENTS
							TY 1, SPL (TAN)	TYPE 2	TYPE 6	TYPE 6B					
				FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH	FOOT	FOOT		
SOUTHBOUND															
1567+81	TO STA	1570+86	LT	305.03	162.50		1		1		4	1	16		NW QUAD OF SN 100-0055
37+40	TO STA	41+11	LT	370.65	250.00		1		1		5	1			NW QUAD OF SN 100-0003
61+30	TO STA	63+91	LT	45.65					1		1		0	215.63	NE QUAD OF SN 100-0077
61+06	TO STA	64+29	RT	45.65					1		1		0	278.13	NW QUAD OF SN 100-0077
65+64	TO STA	66+06	LT	NA							1				SE QUAD OF SN 100-0077
66+02	TO STA	66+43	RT	NA							1				SW QUAD OF SN 100-0077
155+17	TO STA	160+09	RT	492.40	425.00		1	1			7	1			
227+80	TO STA	230+10	RT		162.50		1	1							
237+94	TO STA	240+24	RT		162.50		1	1							
259+50	TO STA	262+55	RT	304.90	212.50		1		1		5	1			NW QUAD OF SN 100-0044
277+86	TO STA	281+77	RT		337.50		1								
281+24	TO STA	284+63	RT	53.13			1					1		286.15	Damaged
280+61	TO STA	284+63	LT											401.77	OVERHEAD SIGN TRUSS
340+10	TO STA	344+12	LT											401.77	OVERHEAD SIGN TRUSS
340+73	TO STA	344+12	RT	53.13										286.15	OVERHEAD SIGN TRUSS
361+18	TO STA	363+86	RT	70.52	0.00				1		1			196.88	NW QUAD OF SN 100-0039
368+62	TO STA	372+89	LT											426.77	OVERHEAD SIGN TRUSS
369+25	TO STA	372+89	RT											364.27	OVERHEAD SIGN TRUSS
384+63	TO STA	389+03	LT											439.27	OVERHEAD SIGN TRUSS
385+26	TO STA	389+03	RT	1.77										376.77	OVERHEAD SIGN TRUSS
389+03	TO STA	392+79	RT		362.50			1			5				EXTEND EXISTING
436+93	TO STA	444+85	RT	792.40		725.00	1	1			10	1			SW QUAD OF SN 100-0060
450+37	TO STA	455+67	RT	529.90	462.50		1	1			7	1			
453+30	TO STA	457+32	LT	401.77										401.77	OVERHEAD SIGN TRUSS
IL 148 RAMP C*															
11+56	TO STA	14+11	RT			187.50	1	1					254.90		
SOUTHBOUND SUBTOTAL				3466.9	2537.5	912.5	11	7	3	3	48	7	271	4075	
NORTHBOUND SUBTOTAL				3468.0	2800.0	0.0	11	7	3	3	42	7	16	3029	
PROJECT TOTAL				6934.8	5337.5	912.5	22	14	6	6	90	14	287	7105	

* ROCK CORING MAY BE REQUIRED FOR POSTS ALONG IL 148 RAMP C. IF SO, THIS WORK SHALL BE PAID FOR ACCORDING TO ARTICLE 109.04(b) (41 POSTS)