81 McLEAN BLVD 82 83

N

200+00

CONC PAVEMENT

NEW B6.12 C&G

GRAVEL

BUILDING REMOVAL No. 1

DIRT, GRAVEL, RECYCLED HMA, CONSTRUCTION DEBRIS

EDGE OF CONC IS BURRIED UNDER DIRT AND GRAVEL

CONC PAVEMENT

EDGE OF CONC IS BURRIED UNDER DIRT AND GRAVEL

CONC WALK

57.3'

8.6'

5.2'

1 STORY FRAME & CONC. BLOCK BUILDING

23.0'

19.5'

CONC

CONC PAVEMENT

NEW B6.12 C&G

CONC PAVEMENT

APPROXIMATE LIMIT OF CONSTRUCTION SHOWN FOR REFERENCE ONLY. FOR R.O.W., LOT LINES ETC. SEE "PLAT OF HIGHWAYS"

OVERGROWN AREA (GRASS, WEEDS, SHRUBS)

DBH= 9"

DBH= 9"

62.6'

CONC

CONC. BLOCK SHED

GRAVEL

OVERGROWN AREA (GRASS, WEEDS, SHRUBS)

BIT

EX CURB ALONG THE EAST LINE TO REMAIN

DBH= 4"

DBH= 4"

DBH= 5"

BIT

BIT

APPROXIMATE LIMIT OF CONSTRUCTION SHOWN FOR REFERENCE ONLY. FOR R.O.W., LOT LINES ETC. SEE "PLAT OF HIGHWAYS"

TEMP GRAVEL ENTRANCE

43.1'

1 Story Conc. Block Building

25.1'

201 LILLIAN ST

LEGEND

- BUILDING REMOVAL
- CONCRETE REMOVAL (PAID AS PAVEMENT REMOVAL)
- X — REMOVAL ITEM
- CURB REMOVAL

FILE NAME = c:\pw_work\pwidot\velichkovvv\d0400762\I141814-sht-plan.dgn	USER NAME = Velichkovvv	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 20.0000 ' / in.	CHECKED -	REVISED -
Default	PLOT DATE = 8/6/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

US 20 (LAKE ST) over McLEAN BLVD (McLEAN & LILLIAN ST)
REMOVAL PLAN

SCALE: | SHEET OF SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
345	(BR&RI)DM	KANE	7	4
		CONTRACT NO. 60Y51		
	ILLINOIS	FED. AID PROJECT		