• (0203.1 & 0312-708W) R-3 CONTRACT NO. 62108

F.A.I. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	•	COOK	870	13
STA.		TO STA.		
FED ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODE	PAY ITEM	UNIT	TOTAL	ROADWAY I-94 (ACNHI 90% FED. 10% STATE, URBAN)	ROADWAY IL 394 (ACNHF 80% FED. 20% STATE)	IL 394 SB OVER I-80 SN-016-2796 (ACNHF 80% FED. 20% STATE)	IL 394 SB OVER CNRR SN-016-2798 (ACNHF 80% FED. 20% STATE)	IL 394 SB OVER THORN CREEK SN-016-2800 (ACNHF 80% FED. 20% STATE)	I-94 EB OVER THORN CREEK SN-016-2807 (ACNHI 90% FED. 10% STATE)	RETAINING WALL SN-016-W866 (ACNHI 90% FED. 10% STATE)	CULVERT SN-016-C012 (ACNHI 90% FED. 10% STATE)	LIGHTING I-94 (ACNHF 80% FED. 20% STATE)	LIGHTING IL 394 (ACNHI 90% FED. 10% STATE)	SIGNING I-94 (ACNHF 80% FED. 20% STATE)	SIGNING IL 394 (ACNHF 80% FED. 20% STATE)	RAMP F (ISTHA-ACNHF)	THORN CREEK OVER IL 394 SB SN-016-2845 (ACNHI)	VILLAGE OF SOUTH HOLLAND (ACNHI)
				CONSTRUCTION TYPE CODE														
• M8120100	CONDUIT EMBEDDED IN STRUCTURE, 25MM DIA., RIGID GALVANIZED STEEL	METER	6										6					
• MX033579	CONDUIT EMBEDDED IN STRUCTURE, 1- 100MM DIA., 30MM DIA., CNC, 4 WIDE BY 2 HIGH	METER	1371.6									1371.6						
* M8120230	CONDUIT EMBEDDED IN STRUCTURE, 50 MM DIA. PVC	METER	2238										2238					
* M8120270	CONDUIT EMBEDDED IN STRUCTURE, 100 MM DIA. PVC	METER	256									16	240					
* M8130195	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 300MM X 300MM X 150MM	EACH	3									1	2					
* M8131400	JUNCTION BOX, NON-METALLIC, EMBEDDED IN STRUCTURE, 525MM X 275MM X 200MM	EACH	34									4	30					
* M8150200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	668.1									416.9	251.2					
* M8360100	LIGHT POLE FOUNDATION, 600MM DIAMETER	METER	62									62						
△△ MX033581	BARRIER SUPPORT STRUCTURE FOR NOISE ABATEMENT WALL	METER	1,314	1,314														
• M7802012	POLYUREA PAVEMENT MARKING TYPE I - LINE 125MM	METER	3699	2080	1619													
• MX033555	PAINT PAVEMENT MARKING - LINE 125MM (SPECIAL)	METER	155	112	43													
MX033571	ERECTING FLOATING BEARINGS, GUIDED EXPANSION 2000 KN	EACH	10					10										
MX033572	ERECTING FLOATING BEARINGS, GUIDED EXPANSION 8000 KN	EACH	1						1									
MX030573	ERECTING FLOATING BEARINGS, FIXED - 2250 KN	EACH	12					12										
MX033573	SLIP-ON FLAT BOTTOM CHECK VALVE, 375MM	EACH	1	1														
MX033533	ERECTING MODULAR EXPANSION JOINT 160MM	METER	14.7						14.7									
• MX033558	CONDUIT ATTACHED TO STRUCTURE, 3-100MM DIA., GALVANIZED STEEL, PVC COATED	METER	208.4										208.4					
• MZ008990	DRILLED SHAFT IN SOIL 1980MM	METER	12.9						12.9									
MZ001045	AGGREGATE SUBGRADE 225MM	SQ M	1119		1119													
MX033574	RECLAIMED ASPHALT PAVEMENT (RAP), 75MM	SQ M	1119		1119													
X0325176	CONCRETE FILLED STEEL POST	EACH	7	7														
* X0325130	TUBULAR TRAFFIC SIGN POST	EACH	6											6				
MX030144	CATCH BASINS, 1.2M BY 0.9M SPECIAL, TYPE 20 FRAME AND GRATE	EACH	25	20	5													
MX030170	CATCH BASINS, 1.2M BY 1.5M SPECIAL, TYPE 22 FRAME AND GRATE	EACH	3	3														
MX030236	REMOVE STEEL SHEET PILING	SQ M	185				185											
MX030257	ERECTING FLOATING BEARINGS, GUIDED EXPANSION 1250KN	EACH	2						2									
MX030258	ERECTING FLOATING BEARINGS, GUIDED EXPANSION 1500KN	EACH	12						12									
MX030272	ERECTING FLOATING BEARINGS, GUIDED EXPANSION 750KN	EACH	12						12									

• SPECIALTY ITEM
** SFTY-3N
△ Y080
△△ Y220 NOISE ABATEMENT WALL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-94 EAST BOUND / IL 394 SOUTH BOUND

SUMMARY OF QUANTITIES

HORIZ SCALE: NONE
VERT SCALE: NONE
DATE: JULY 18, 2005
DRAWN BY: JYMC
CHECKED BY: JES

HNTB

J:\345628\cadd\11\cds\Contract19_SB\sq190094a.dgn
slauer 15-SEP-2005 15:09