F.A.I. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	*	COOK	870	15
STA.		TO STA.		
FED ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODE	PAY ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE														
				J000-2A	J000-2A	X271-2A	X181-2A	X071-2A	X071-2A	Y007	Y007	Y030-1E	Y030-1E	Y002-1C	Y002-1C	J000-2A	X071-2A	Y102
			URBAN	ACNHI 90%FED./10%STATE	ACNHF 80%FED./20%STATE				ACNHI 90%FED./10%STATE			ACNHF 80%FED./20%STATE	ACNHI 90%FED./10%STATE	ACNHF 80%FED./20%STATE	ISTHA-ACNHF		ACNHI	
				ROADWAY I-94	ROADWAY IL 394	IL 394 SB OVER I-80 SN-016-2796	IL 394 SB OVER CNRR SN-016-2798	IL 394 SB OVER THORN CREEK SN-016-2800	IL 394 SB OVER THORN CREEK SN-016-2807	I-94 EB RETAINING WALL SN-016-W866	CULVERT SN-016-C012	LIGHTING I-94	LIGHTING IL 394	SIGNING I-94	SIGNING IL 394	RAMP F	THORN CREEK SN-016-2845 OVER IL 394 SB	VILLAGE OF SOUTH HOLLAND
MZ001050	AGGREGATE SUBGRADE 300MM	SQ M	5852	2226	3595											31		
* MZ008810	DRILLED SHAFT IN SOIL 610MM	METER	25.0						25.0									
* MZ008830	DRILLED SHAFT IN SOIL 915MM	METER	49.0						49.0									
* MZ008860	DRILLED SHAFT IN SOIL 1220MM	METER	298.1						298.1									
* MZ008876	DRILLED SHAFT IN SOIL 1676MM	METER	130.1						130.1									
MZ013825	CONTROLLED LOW-STRENGTH MATERIAL	CU M	61.8			16.2	14.6	31										
MZ022800	FENCE REMOVAL	METER	1784	1776	8													
MZ039300	PERMANENT CASING	METER	286.4						286.4									
MZ047300	PROTECTIVE SHIELD	SQ M	803			562	241											
MZ064800	SELECTIVE CLEARING	UNIT	93		93													
MZ065755	SLOTTED DRAIN 300MM WITH VARIABLE SLOT HEIGHT	METER	239.5		239.5													
X0301229	ACCIDENT INVESTIGATION SITE	CAL MO	16	8	8													
X0320333	ROADWAY CLEANING (SPECIAL)	EACH	18	9	9													
X0322917	PROPOSED STORM SEWER CONNECTION TO EXISTING MANHOLE	EACH	18	1	17													
X0323082	DRAINAGE SCUPPERS, DS-33	EACH	3				1	2										
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	331	295	36													
X0323830	DRAINAGE SCUPPERS, DS-11	EACH	15			1		9	5									
X0324044	EROSION CONTROL, TEMPORARY PIPE SLOPE DRAIN	EACH	10	3	7													
X0324045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	4	2	2													
X0324587	NOISE ABATEMENT WALL ANCHOR ROD ASSEMBLY	EACH	46							46								
X0324698	APPLY DUST SUPPRESSION AGENTS	UNITS	8884	1404	7480													
X0504200	CONCRETE HEADWALL	EACH	1	1														
X0976500	END SECTIONS TO BE REMOVED	EACH	6	1	5													
X4210390	LUG SYSTEM COMPLETE (SPECIAL)	EACH	1		1													
X6020166	DRAINAGE STRUCTURES, TYPE 1 SPECIAL WITH TWO TYPE 20 FRAME AND GRATES	EACH	4	4														
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	0.44	0.53											0.03		
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	240	108	132													
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	8		8													

* SPECIALTY ITEM
** SFTY-3N
△ Y080
△△ Y220 NOISE ABATEMENT WALL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-94 EAST BOUND / IL 394 SOUTH BOUND

SUMMARY OF QUANTITIES

HORIZ SCALE: NONE
VERT SCALE: NONE
DATE: JULY 18, 2005
DRAWN BY: JYMC
CHECKED BY: JES

HNTB

J:\345620\cadd\11\ods\Contract19_SB\sq190114a.dgn
slauer 15-SEP-2005 15:08