

F.A.I. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	•	COOK	870	44
STA.		TO STA.		
FED ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

**DRAINAGE SCHEDULE - PROPOSED**

LOCATION	CATCH BASINS, TYPE A, 1.5m DIAMETER TIF, OL	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, CLOSED LID	MANHOLES, TYPE A, 1.5M DIAMETER, TYPE 1 FRAME, CLOSED LID	CATCH BASINS, 1.2M BY 0.9M SPECIAL, TYPE 20 FRAME AND GRATE	CATCH BASINS, 1.2M BY 1.5M SPECIAL, TYPE 22 FRAME AND GRATE	SLOTTED DRAIN 300MM WITH VARIABLE SLOT HEIGHT	PROPOSED STORM SEWER CONNECTION TO EXISTING MANHOLE	DRAINAGE STRUCTURES, TYPE 1 SPECIAL WITH TWO TYPE 20 FRAME AND GRATES		
	EACH	EACH	EACH	EACH	EACH	METER	EACH	EACH		
I-94	18+363 TO 18+725	0	0	3	0	0	0	4		
	18+725 TO 19+050	0	0	4	1	0	0	0		
	19+050 TO 19+350	0	0	3	0	0	0	0		
	19+350 TO 19+700	0	0	4	1	0	0	0		
	19+700 TO 20+000	0	1	0	3	1	0	1	0	
I-94 EB	20+625 TO 20+925	0	0	0	0	0	0	0		
I-94 SUBTOTAL		0	1	17	3	0	1	4		
IL 394	38+265 TO 38+615	0	0	0	0	0	1	0		
	38+615 TO 38+865	0	0	0	0	0	1	0		
	38+865 TO 39+240	0	0	0	0	0	4	0		
	39+240 TO 39+600	0	0	0	3	0	9	0		
	39+600 TO 39+850	0	0	0	2	0	117.3	2	0	
	39+850 TO 440+200	0	0	0	0	0	0	0	0	
	400+200 TO 440+525	0	0	0	0	0	0	0	0	
	440+525 TO 440+835	0	0	0	0	0	0	0	0	
440+900 TO 441+167.161	1	2	3	3	0	121.9	0	0		
IL 394 SUBTOTAL		1	2	3	8	239.5	17	0		
TOTAL		1	3	3	25	239.5	18	4		

**TOLLWAY DRAINAGE SCHEDULE - PROPOSED**

LOCATION	POROUS GRANULAR BACKFILL	RIP RAP, HAND-LAID	REINFORCED CONCRETE PIPE (600MM)	COARSE AGGREGATE BACKFILL	SUBSURFACE PAVEMENT DRAIN (FILTER FABRIC) 150MM	OUTLET SUBDRAIN	CONCRETE HEADWALL FOR PIPE UNDERDRAIN (PAVEMENT DRAIN)	CONCRETE PIPE END SECTIONS 600MM	CONCRETE HEADWALL REMOVAL	STORM SEWER REMOVAL 600MM
	CU M	SQ M	METER	METER	METER	METER	EACH	EACH	EACH	METER
RAMP F	78	164	57.5	200	368.5	16.5	3	2	1	36.0
TOTAL	78*	164	57.5	200	368.5	16.5	3	2	1	36.0

\* POROUS GRANULAR BACKFILL USED AT RAMP E. ADDITIONAL 46 CU M PAID UNDER STRUCTURE NO. SN 016-2845.

- NOTES:
- THE SCHEDULES ON THIS PAGE MAY NOT REFLECT ITEMS QUANTIFIED BETWEEN:
    - Q I-94 EB STA. 20+657.900 TO STA. 21+222.210,
    - Q I-94 WB STA. 30+785.473 TO STA. 31+020.000, AND
    - MDTPE94 STA. 25+178.451 TO STA. 25+516.450
  - TOLLWAY ITEMS RIPRAP, HAND-LAID AND POROUS GRANULAR BACKFILL INCLUDE QUANTITIES FROM SNO16-2845

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
I-94 EAST BOUND / IL 394 SOUTH BOUND

**SCHEDULE OF QUANTITIES**

HORIZ SCALE:  
VERT SCALE:  
DATE: JULY 18, 2005

DRAWN BY: BJM  
CHECKED BY: JES



SC-5