

M4210360 CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 360MM

DRAWING NO.	BEGINNING STATION	WIDTH METER	END STATION	WIDTH METER	AREA SQ M	DESCRIPTION
PF-24	20+657.900	7.2	20+850.000	7.2	1,383	I-94 EB
	20+850.000	7.5	20+932.500	10.8	755	I-94 EB
	20+932.500	10.8	20+950.000	10.8	189	I-94 EB
PF-25	20+950.000	10.8	20+991.466	10.8	448	I-94 EB
TOTAL					2,775	

M4402000 PAVEMENT REMOVAL

DRAWING NO.	BEGINNING STATION	WIDTH METER	END STATION	WIDTH METER	AREA SQ M	DESCRIPTION
PF-24	25+178.451		25+322.597	20.20	2294	MDTPE94
	25+322.597	11.500	25+474.984	11.50	1752	MDTPE94
	25+322.597	11.500	25+442.549	11.50	1379	MDTPE94
PF-25	25+474.984	12.000	25+516.450	12.00	498	MDTPE94
TOTAL					5924	

M4830360 PORTLAND CEMENT CONCRETE SHOULDERS - 360MM

DRAWING NO.	BEGINNING STATION	WIDTH METER	END STATION	WIDTH METER	OFFSET	AREA SQ M	DESCRIPTION
PF-24	20+657.900	3.60	20+950.000	3.60	LT.	1,052	I-94 EB
	20+657.900	3.60	20+792.220	3.60	RT.	484	I-94 EB
	20+792.220	10.71	20+850.000	7.82	RT.	535	I-94 EB
	20+850.000	7.52	20+869.021	5.81	RT.	127	I-94 EB
	20+869.021	5.81	20+890.267	6.23	RT.	128	I-94 EB
PF-25	20+890.267	6.23	20+932.500	2.40	RT.	182	I-94 EB
	20+932.500	2.40	20+950.000	2.40	RT.	42	I-94 EB
	30+785.473	3.00	30+900.000	3.00	RT.	344	I-94 WB
	20+950.000	3.60	21+044.600	3.60	LT.	341	I-94 EB
	20+950.000	2.40	20+991.466	2.40	RT.	100	I-94 EB
	30+900.000	3.00	31+020.000	3.00	RT.	360	I-94 WB
TOTAL						3,693	

M4402030 GUTTER REMOVAL

DRAWING NO.	BEGINNING STATION	END STATION	OFFSET	LENGTH METER	DESCRIPTION
PF-24	25+330.016	25+368.091	LT.	38	MDTPE94
TOTAL				38	

M6320030 GUARDRAIL REMOVAL

DRAWING NO.	BEGINNING STATION	END STATION	OFFSET	LENGTH METER	DESCRIPTION
PF-24	25+177.519	25+213.962	RT.	38.10	MDTPE94
TOTAL				38.10	

M7200300 SIGN PANEL - TYPE 3

DRAWING NO.	STATION	LENGTH METER	WIDTH METER	AREA SQ M	DESCRIPTION
SI-7	30+786	2.380	3.220	7.66	I-94 WB
SI-8	20+935	3.990	5.120	20.43	I-94 EB
TOTAL					28.09

M4812360 AGGREGATE SHOULDERS, TYPE B 360MM

DRAWING NO.	BEGINNING STATION	END STATION	OFFSET	WIDTH METER	AREA SQ M	DESCRIPTION
PF-24	30+843.667	30+900.000	RT.	0.45	25	I-94 WB
PF-25	20+960.675	20+991.466	RT.	0.45	14	I-94 EB
	20+980.000	21+052.861	LT.	0.45	33	I-94 EB
	30+900.000	31+020.000	RT.	0.45	54	I-94 WB
TOTAL					126	

M7802000 POLYUREA PAVEMENT MARKING, TYPE I - LETTERS AND SYMBOLS

DRAWING NO.	BEGINNING STATION	LETTERS SQ M	SYMBOLS SQ M	AREA SQ M	DESCRIPTION
PM-13	20+932.500	1.93	1.47	3.40	I-94 EB RIGHT TURN ONLY
PM-14	21+104.430	1.93	1.47	3.40	I-94 EB RIGHT TURN ONLY
TOTAL					7

M4830150 PORTLAND CEMENT CONCRETE SHOULDERS - 150MM

DRAWING NO.	BEGINNING STATION	WIDTH METER	END STATION	WIDTH METER	OFFSET	AREA SQ M	DESCRIPTION
PF-24	30+782.514	0.75	30+826.359	0.75	RT.	33	I-94 WB
	30+826.359	0.75	30+841.559	1.054	RT.	14	
	30+841.559	1.054	30+843.667	0	RT.	1	
TOTAL						48	

M7802010 POLYUREA PAVEMENT MARKING, TYPE I - LINE 100MM

DRAWING NO.	BEGINNING STATION	END STATION	LENGTH METER	DESCRIPTION
PM-12	20+657.90	20+725.00	134	I-94 EB LT & RT EDGE - SOLID
PM-13	20+725.00	21+025.00	300	I-94 EB LEFT EDGE - YELLOW - SOLID
	20+725.00	20+842.50	118	I-94 EB RIGHT EDGE - WHITE - SOLID
PM-14	21+025.00	21+222.21	197	I-94 EB LEFT EDGE - YELLOW - SOLID
TOTAL				749

M6060270 CONCRETE GUTTER, TYPE A (MODIFIED)

DRAWING NO.	BEGINNING STATION	END STATION	OFFSET	LENGTH METER	DESCRIPTION
PF-24	20+861.290	20+950.000	LT.	89	I-94 EB
PF-25	20+950.000	20+980.000	LT.	30	I-94 EB
TOTAL					119

POLYUREA PAVEMENT MARKING, TYPE I - LINE 125MM

DRAWING NO.	BEGINNING STATION	END STATION	LENGTH METER	DESCRIPTION
PM-12	20+657.90	20+725.00	17	I-94 EB WHITE SKIP-DASH
PM-13	20+725.00	21+025.00	75	I-94 EB WHITE SKIP-DASH
PM-14	21+025.00	21+222.21	49	I-94 EB WHITE SKIP-DASH
TOTAL				142

CONCRETE BARRIER, SINGLE FACE, 1065 MM HEIGHT, REINFORCED

BEGINNING STATION	END STATION	OFFSET	LENGTH METER	DESCRIPTION
20+657.900	20+850.000	LT.	192	I-94 EB
20+657.900	20+792.220	RT.	134	I-94 EB
20+792.220	20+936.715	RT.	144	I-94 EB
20+936.715	20+943.215	RT.	12	I-94 EB
TOTAL				484

M6300100 STEEL PLATE BEAM GUARD RAIL, TYPE A

DRAWING NO.	BEGINNING STATION	END STATION	LENGTH METER	TRAFFIC BARRIER TERMINAL END SECTIONS	
				EACH	EACH
PF-24	30+792.039	30+826.359	34.32	TRAF BAR TERM T6	TR BAR TRM T1 SPL TAN
TOTAL					34.32

M7802020 POLYUREA PAVEMENT MARKING, TYPE I - LINE 200MM

DRAWING NO.	BEGINNING STATION	END STATION	LENGTH METER	DESCRIPTION
PM-13	20+842.50	20+932.50	90	I-94 EB RIGHT EDGE - WHITE
	20+932.50	21+025.00	93	I-94 EB RIGHT EDGE - WHITE
	20+932.50	21+025.00	19	I-94 EB WHITE - SKIP DASH
PM-14	21+025.00	21+222.21	197	I-94 EB WHITE
	21+025.00	21+222.21	39	I-94 EB WHITE - SKIP DASH
TOTAL				438

SC-9

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION I-94 EASTBOUND / IL 394 SOUTHBOUND
NAME	DATE	
		SCHEDULE OF QUANTITIES DRAWN BY: CTT CHECKED BY: RCH DATE: JULY 18, 2005 