

F.A.I. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	*	COOK	870	51
STA.		TO STA.		
FED ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

ISTHA ITEMS

ROADWAY SCHEDULE - REMOVAL

RAMP F (ISTHA)	LOCATION	CLEARING	RIGHT-OF-WAY FENCE REMOVAL	WOOD SIGN SUPPORT	FURNISH AND INSTALL SIGN, TYPE 2
		(HA)	(METER)	(METER)	(SQ M)
	110+296.37 TO 110+667.626	2	325	5	1.44

ROADWAY SCHEDULE - PROPOSED

RAMP F (ISTHA)	LOCATION	PORTLAND CEMENT CONCRETE PAVEMENT (300MM)	BITUMINOUS CONCRETE SHOULDER (150MM)	AGGREGATE SHOULDER WITH FILTER FABRIC	AGGREGATE BASE COURSE	GRANULAR SUBBASE	SELECTED SUBGRADE	RIGHT-OF-WAY FENCE, TYPE 1	CORNER POST, RIGHT-OF-WAY FENCE, TYPE 1	END POST AT STRUCTURE, RIGHT-OF-WAY FENCE, TYPE 1	SINGLE VEHICULAR GATE, RIGHT-OF-WAY FENCE, TYPE 1
		(SQ M)	(SQ M)	(M TON)	(SQ M)	(CU M)	(CU M)	(METER)	(EACH)	(EACH)	(EACH)
	110+296.37 TO 110+667.626	1747	1517	303	65.7	522	739	383	6	1	1

EARTHWORK

RAMP F (ISTHA)	LOCATION	ROADWAY EXCAVATION, COMMON	ROADWAY EXCAVATION, UNCOMMON	EARTH EMBANKMENT ZONE A	EARTH EMBANKMENT ZONE B
		(CU M)	(CU M)	(CU M)	(CU M)
	110+296.37 TO 110+400.000	0	270	5755	3260
	110+400.000 TO 110+500.000	1196	319	1918	1750
	110+500.000 TO 110+600.000	10648	700	326	414
	110+600.000 TO 110+667.626	2161	395	646	2536
	SUBTOTAL	14005	1684	8645	7960

	CUBIC METERS
ROADWAY EXCAVATION, COMMON	14005
ROADWAY EXCAVATION, UNCOMMON	1684
EARTH EMBANKMENT ZONE A	8645
EARTH EMBANKMENT ZONE B	7960

SC-12

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-94 EAST BOUND / IL 394 SOUTH BOUND

REVISIONS	
NAME	DATE

SCHEDULE OF QUANTITIES

HORIZ SCALE:
VERT SCALE:
DATE: JULY 18, 2005

DRAWN BY: BJM
CHECKED BY: JES

