

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GIRDER 6

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	SHEET NO. 9 56 SHEETS
F. A. I. 80/94	*	COOK	870	619	
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT-			

CONTRACT NO. 62108

Location	Station	Offset (m)	Theoretical Grade Elev.	Theoretical Grade Elev. Adjusted for Dead Load Defln.
Bk. W. Abut.	20+440.950	6.700	185.989	185.989
⊕ Brg. W. Abut.	20+442.000	6.700	185.990	185.990
A	20+444.965	6.700	185.992	185.998
B	20+447.929	6.700	185.994	186.003
C	20+450.894	6.700	185.994	186.007
D	20+453.858	6.700	185.994	186.007
E	20+456.823	6.700	185.993	186.005
F	20+459.788	6.700	185.992	186.000
G	20+462.752	6.700	185.989	185.993
H	20+465.717	6.700	185.986	185.987
⊕ Pier 1	20+470.000	6.700	185.980	185.980
I	20+472.965	6.700	185.974	185.978
J	20+475.929	6.700	185.968	185.979
K	20+478.894	6.700	185.962	185.979
L	20+481.858	6.700	185.954	185.979
M	20+484.823	6.700	185.946	185.976
N	20+487.788	6.700	185.936	185.969
O	20+490.752	6.700	185.926	185.959
P	20+493.717	6.700	185.915	185.945
Q	20+496.681	6.700	185.904	185.928
R	20+499.646	6.700	185.891	185.908
S	20+502.610	6.700	185.878	185.888
T	20+505.575	6.700	185.864	185.867
⊕ Pier 2	20+509.000	6.700	185.847	185.847
U	20+511.965	6.700	185.832	185.835
V	20+514.929	6.700	185.817	185.826
W	20+517.894	6.700	185.803	185.818
X	20+520.858	6.700	185.788	185.810
Y	20+523.823	6.700	185.773	185.801
Z	20+526.787	6.700	185.758	185.789
AA	20+529.752	6.700	185.743	185.775
AB	20+532.716	6.700	185.728	185.758
AC	20+535.681	6.700	185.714	185.739
AD	20+538.645	6.700	185.699	185.718
AE	20+541.610	6.700	185.684	185.696
AF	20+544.575	6.700	185.669	185.674
⊕ Pier 3	20+548.000	6.700	185.652	185.652
AG	20+550.965	6.700	185.637	185.638
AH	20+553.929	6.700	185.622	185.626
AI	20+556.894	6.700	185.608	185.616
AJ	20+559.858	6.700	185.593	185.605
AK	20+562.823	6.700	185.578	185.593
AL	20+565.787	6.700	185.563	185.579
AM	20+568.752	6.700	185.548	185.563
AN	20+571.716	6.700	185.533	185.546
AO	20+574.681	6.700	185.519	185.527
AP	20+577.645	6.700	185.504	185.508
AQ	20+580.610	6.700	185.489	185.490
⊕ Pier 4	20+583.000	6.700	185.477	185.477
AR	20+585.965	6.700	185.462	185.464
AS	20+588.929	6.700	185.447	185.454
AT	20+591.894	6.700	185.433	185.444
AU	20+594.858	6.700	185.418	185.433
AV	20+597.823	6.700	185.403	185.421
AW	20+600.788	6.700	185.388	185.407
AX	20+603.752	6.700	185.373	185.391
AY	20+606.717	6.700	185.358	185.372
AZ	20+609.681	6.700	185.344	185.353
BA	20+612.646	6.700	185.329	185.333
BB	20+615.610	6.700	185.314	185.315
⊕ Pier 5	20+618.000	6.700	185.302	185.302
BC	20+620.965	6.700	185.287	185.290
BD	20+623.929	6.700	185.272	185.280
BE	20+626.894	6.700	185.258	185.271
BF	20+629.858	6.700	185.243	185.261
BG	20+632.823	6.700	185.228	185.250
BH	20+635.787	6.700	185.213	185.236
BI	20+638.752	6.700	185.198	185.219
BJ	20+641.716	6.700	185.183	185.199
BK	20+644.681	6.700	185.169	185.178
⊕ Brg. E. Abut.	20+648.000	6.700	185.152	185.152
Bk. E. Abut.	20+649.050	6.700	185.147	185.147

I:\Reaching EA_34522\CADD\bl\SN_2807\wp190044s_2807.dgn
 08-JUL-2005 14:19

DESIGNED	R.A.
CHECKED	M.R.
DRAWN	R.A.
CHECKED	M.R. / H.T.

Notes:

1. Work this sheet with Sheet No. 6, 7 & 8 of 56 sheets.
2. All elevations and offsets are in meters (m).

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-94 EAST BOUND / IL 394 SOUTH BOUND
TOP OF SLAB ELEVATION - 3
EB I-94 OVER THORN CREEK
F.A.P. 332 SECTION (0203.1 & 0312-708W) R-3
COOK COUNTY
STA. 20+809.000 STRUCTURE NO. 016-2807
DATE: 6/28/05
SCALE: NTS
Soodan
Soodan & Associates, Inc.
100 North LaSalle Street, Suite 1800
Chicago, Illinois 60602