

SUMMARY OF QUANTITIES

F.A.I. RTE. 80/94	SECTION 2626.2-R-2	COUNTY COOK/LAKE	TOTAL SHEETS 1207	SHEET NO. 5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 62114		INDOT DES. NO. 0100987		

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY	LIGHTING-	SURVEIL-	SIGNING	ROADWAY	LIGHTING	SURVEIL-	SIGNING	VILLAGE		
				ILLINOIS	ILLINOIS	LANCE	ILLINOIS	INDIANA	INDIANA	LANCE	INDIANA	OF		
				CONSTRUCTION TYPE CODE								Y060		
				J000-2A	Y030-1E	Y032-1F	Y002-1C	J000-2A	Y030-1E	Y032-1F	Y002-1C	Y060		
* 89502380	REMOVE EXISTING HANDHOLE	EACH	3	0	0	0	0	3	0	0	0	0		
M2010500	TREE REMOVAL, HECTARES	HA	1.7	0	0	0	0	1.7	0	0	0	0		
M2020010	EARTH EXCAVATION	CU M	1034.3	1034.3	0	0	0	0	0	0	0	0		
M2021200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU M	1904.6	1904.6	0	0	0	0	0	0	0	0		
M2040800	FURNISHED EXCAVATION	CU M	63340.2	63340.2	0	0	0	0	0	0	0	0		
M2070220	POROUS GRANULAR EMBANKMENT	CU M	185	185	0	0	0	0	0	0	0	0		
M2080150	TRENCH BACKFILL	CU M	9550.6	8327.5	0	0	0	0	0	0	0	1223.1		
M2101000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ M	58401	58401	0	0	0	0	0	0	0	0		
M2113100	TOPSOIL FURNISH AND PLACE, 100MM	SQ M	250	0	0	0	0	0	0	0	0	250		
M2113150	TOPSOIL FURNISH AND PLACE, 150MM	SQ M	10926	940	0	0	0	9986	0	0	0	0		
M2113300	TOPSOIL FURNISH AND PLACE, 300MM	SQ M	4640	4640	0	0	0	0	0	0	0	0		
M2114100	COMPOST FURNISH AND PLACE, 100MM	SQ M	4632	4632	0	0	0	0	0	0	0	0		
M2130201	EXPLORATION TRENCH 2.1 METER DEPTH	METER	140	90	0	0	0	0	0	0	0	50		
M2500210	SEEDING, CLASS 2A	HA	3.13	.1	0	0	0	3	0	0	0	.03		
M2500400	NITROGEN FERTILIZER NUTRIENT	KG	341	41	0	0	0	297	0	0	0	3		
M2500500	PHOSPHORUS FERTILIZER NUTRIENT	KG	341	41	0	0	0	297	0	0	0	3		
M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	341	41	0	0	0	297	0	0	0	3		
M2500750	MOWING	HA	1.3	1.3	0	0	0	0	0	0	0	0		
M2510125	MULCH, METHOD 3	HA	.03	0	0	0	0	0	0	0	0	.03		
M2510630	EROSION CONTROL BLANKET	SQ M	52071	4552	0	0	0	47519	0	0	0	0		
M2520110	SODDING, SALT TOLERANT	SQ M	4473	4473	0	0	0	0	0	0	0	0		
M2520200	SUPPLEMENTAL WATERING	UNIT	581	581	0	0	0	0	0	0	0	0		
M2800250	TEMPORARY EROSION CONTROL SEEDING	KG	625	50	0	0	0	575	0	0	0	0		
M2810101	STONE RIPRAP, CLASS A1	SQ M	72	72	0	0	0	0	0	0	0	0		
M2810107	STONE RIPRAP, CLASS A4	SQ M	72	72	0	0	0	0	0	0	0	0		
M2820200	FILTER FABRIC	SQ M	231	231	0	0	0	0	0	0	0	0		
M3111300	SUB-BASE GRANULAR MATERIAL, TYPE B 300MM	SQ M	58401	58401	0	0	0	0	0	0	0	0		
M3120150	STABILIZED SUB-BASE 150MM	SQ M	58401	58401	0	0	0	0	0	0	0	0		
M3511010	AGGREGATE BASE COURSE, TYPE B	M TON	1780.9	1611.9	0	0	0	0	0	0	0	169		
M4210360	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 360MM	SQ M	41475	41475	0	0	0	0	0	0	0	0		
M4214360	PAVEMENT REINFORCEMENT 360MM	SQ M	41475	41475	0	0	0	0	0	0	0	0		
M4217180	LUG SYSTEM COMPLETE 18 METER	EACH	3	3	0	0	0	0	0	0	0	0		
M4218000	PROTECTIVE COAT	SQ M	32514	32514	0	0	0	0	0	0	0	0		

- SPECIALTY ITEMS
- • 100% STATE
- • • 100% INDIANA
- • • • 100% VILLAGE OF LANSING

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-80/94/US 6
KINGERY-BORMAN EXPRESSWAY
BURNHAM ROAD TO US 41

SUMMARY OF QUANTITIES

SCALE: _____ DATE: 07/05

DRAWN BY ACE/CAD
CHECKED BY TAE

AMERICAN
CONSULTING ENGINEERS

Rev.