

SCHEDULE OF QUANTITIES

ALL DIMENSIONS IN METERS EXCEPT PAY ITEMS AND UNLESS NOTED OTHERWISE

F.A.I. RTE. 80/94	SECTION 2626.2-R-2	COUNTY COOK/LAKE	TOTAL SHEETS 1207	SHEET NO. 30
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 62114		INDOT DES. NO. 0100987		

STORM SEWER REMOVAL 1350MM

STATION	OFFSET(m)	-	STATION	OFFSET(m)	METERS
ILLINOIS					
7+934.609	43.45 LT	-	7+966.037	53.04 LT	32.9
7+966.037	53.04 LT	-	7+965.651	56.01 LT	3.0
7+960.342	97.88 LT	-	7+957.903	117.71 LT	20.0
TOTAL =					56

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-22.45

STATION	OFFSET(m)	-	STATION	OFFSET(m)	METERS
ILLINOIS					
GATEWAY LANDSCAPING					
7+588.880	27.38 LT	-	7+597.130	27.38 LT	8.3
7+597.130	27.38 LT	-	7+598.970	30.34 LT	3.4
7+598.970	30.34 LT	-	7+599.070	31.52 LT	1.2
TOTAL =					13

CONCRETE MEDIAN SURFACE, 100MM (SPECIAL)

STATION	WIDTH(m)	-	STATION	WIDTH(m)	SQ METER
ILLINOIS					
GATEWAY LANDSCAPING					
7+588.880	1.200	-	7+648.820	1.200	71.9
7+648.820	2.000	-	7+701.840	0.000	53.0
TOTAL =					125

GUARDRAIL REMOVAL

STATION	OFFSET(m)	-	STATION	OFFSET(m)	METERS
ILLINOIS					
6+814.721	17.94 RT	-	7+066.780	17.86 RT	252.1
7+589.060	25.68 LT	-	7+676.880	24.92 LT	87.8
TOTAL =					340

GUARDRAIL REMOVAL

STATION	OFFSET(m)	-	STATION	OFFSET(m)	METERS
INDIANA					
8+042.920	18.00 LT	-	8+193.710	18.00 LT	150.80
8+246.160	18.00 LT	-	8+407.900	20.50 LT	161.80
8+585.580	22.00 LT	-	8+725.340	24.00 LT	139.80
8+769.240	24.70 LT	-	8+927.060	28.00 LT	157.90
8+781.900	23.50 RT	-	8+863.260	26.15 RT	81.40
HOHMAN AVE					
79+983.450	8.57 LT	-	80+022.921	8.71 LT	39.50
79+970.480	8.14 RT	-	80+034.480	8.30 RT	64.00
HARRISON AVE					
89+977.350	4.01 LT	-	89+983.365	4.11 LT	6.00
90+020.935	4.12 LT	-	90+052.310	4.93 LT	31.40
89+937.900	7.39 RT	-	89+980.480	5.33 RT	42.60
90+018.240	5.38 RT	-	90+030.968	5.35 RT	12.70
TOTAL =					887.9

CONCRETE BARRIER, SINGLE FACE, 1065 MM HEIGHT

STATION	OFFSET(m)	-	STATION	OFFSET(m)	METERS
ILLINOIS					
7+541.215	25.68 LT	-	7+589.056	25.68 LT	47.80
7+543.379	25.68 RT	-	7+621.420	25.68 RT	78.00
TOTAL =					125.8

CONCRETE BARRIER, DOUBLE FACE, 1065 MM HEIGHT

STATION	OFFSET(m)	-	STATION	OFFSET(m)	METERS
ILLINOIS					
6+850.000	0.00 RT	-	6+947.238	0.00 RT	97.20
6+955.718	0.00 RT	-	7+235.300	0.00 RT	279.60
7+243.780	0.00 RT	-	7+308.450	0.00 RT	64.70
7+316.930	0.00 RT	-	7+569.530	0.00 RT	252.60
7+594.090	0.00 RT	-	7+941.220	0.00 RT	347.10
7+342.041	29.28 LT	-	7+354.041	29.28 LT	12.00
TOTAL =					1,053.2

CONCRETE BARRIER TRANSITION

STATION	OFFSET(m)	-	STATION	OFFSET(m)	METERS
ILLINOIS					
6+947.238	0.00 RT	-	6+949.838	0.00 RT	2.60
6+953.118	0.00 RT	-	6+955.718	0.00 RT	2.60
7+235.300	0.00 RT	-	7+237.900	0.00 RT	2.60
7+241.180	0.00 RT	-	7+243.780	0.00 RT	2.60
7+308.450	0.00 RT	-	7+311.050	0.00 RT	2.60
7+314.330	0.00 RT	-	7+316.930	0.00 RT	2.60
7+564.840	0.00 RT	-	7+569.530	0.00 RT	4.70
7+589.490	0.00 RT	-	7+594.090	0.00 RT	4.60
7+941.220	0.00 RT	-	7+945.320	0.00 RT	4.10
7+948.980	0.00 RT	-	7+955.130	0.00 RT	6.20
TOTAL =					35.2

BARRIER BASE

STATION	OFFSET(m)	-	STATION	OFFSET(m)	METERS
ILLINOIS					
SEE MX637150 CONC BAR 1F 1065 HT SPL					
					112.80
SEE M6370175 CONC BAR 1F 1065HT					
					125.80
SEE M6370275 CONC BAR 2F 1065HT					
					1,053.20
SEE M6370805 CONC BAR TRANS					
					35.20
TOTAL =					1,327.0

POLYUREA PAVEMENT MARKING TYPE I - LINE 100MM

STATION	OFFSET(m)	-	STATION	OFFSET(m)	METERS
ILLINOIS					
WESTBOUND YELLOW					
6+814.721	4.08 LT	-	7+050.000	4.08 LT	235.30
7+050.000	4.08 LT	-	7+380.276	4.08 LT	330.30
7+380.276	4.08 LT	-	7+750.000	4.08 LT	369.70
7+750.000	4.08 LT	-	7+951.532	4.08 LT	201.50
WESTBOUND WHITE					
6+814.721	26.13 LT	-	6+852.438	26.13 LT	37.70
6+852.438	26.13 LT	-	7+050.000	25.68 LT	197.60
7+050.000	25.68 LT	-	7+361.215	25.68 LT	311.20
7+361.215	25.68 LT	-	7+421.215	24.48 LT	60.00
7+421.215	24.48 LT	-	7+481.215	23.28 LT	60.00
7+481.215	23.28 LT	-	7+541.215	22.08 LT	60.00
7+541.215	22.08 LT	-	7+750.000	22.08 LT	208.80
7+750.000	22.08 LT	-	7+946.292	22.08 LT	196.30
EASTBOUND YELLOW					
6+814.721	4.08 RT	-	7+050.000	4.08 RT	235.30
7+050.000	4.08 RT	-	7+380.276	4.08 RT	330.30
7+380.276	4.08 RT	-	7+400.000	4.08 RT	19.70
7+400.000	4.08 RT	-	7+750.000	4.08 RT	350.00
7+750.000	4.08 RT	-	7+953.942	4.08 RT	203.90
EASTBOUND WHITE					
6+814.721	24.10 RT	-	6+955.111	22.08 RT	140.40
6+955.111	22.08 RT	-	7+050.000	22.08 RT	94.90
7+050.000	22.08 RT	-	7+380.276	22.08 RT	330.30
7+380.276	22.08 RT	-	7+400.000	22.08 RT	19.70
7+400.000	22.08 RT	-	7+750.000	22.08 RT	350.00
7+750.000	22.08 RT	-	7+959.333	22.08 RT	209.30
TOTAL =					4,552.2

POLYUREA PAVEMENT MARKING TYPE I - LINE 125MM

STATION	OFFSET(m)	-	STATION	OFFSET(m)	METERS
ILLINOIS					
EASTBOUND - 9M SKIP - 3M DASH					
6+814.721	7.68 RT	-	7+050.000	7.68 RT	58.8
6+814.721	11.28 RT	-	7+050.000	11.28 RT	58.8
6+814.721	14.88 RT	-	7+050.000	14.88 RT	58.8
6+814.721	18.48 RT	-	7+050.000	18.48 RT	58.8
7+050.000	7.68 RT	-	7+380.276	7.68 RT	82.6
7+050.000	11.28 RT	-	7+380.276	11.28 RT	82.6
7+050.000	14.88 RT	-	7+380.276	14.88 RT	82.6
7+050.000	18.48 RT	-	7+380.276	18.48 RT	82.6
7+380.276	7.68 RT	-	7+750.000	7.68 RT	92.4
7+380.276	11.28 RT	-	7+750.000	11.28 RT	92.4
7+380.276	14.88 RT	-	7+750.000	14.88 RT	92.4
7+380.276	18.48 RT	-	7+750.000	18.48 RT	92.4
7+750.000	7.68 RT	-	7+951.532	7.68 RT	50.4
7+750.000	11.28 RT	-	7+951.532	11.28 RT	50.4
7+750.000	14.88 RT	-	7+951.532	14.88 RT	50.4
7+750.000	18.48 RT	-	7+951.532	18.48 RT	50.4
WESTBOUND - 9M SKIP - 3M DASH					
6+814.721	7.68 LT	-	6+852.395	7.68 LT	9.4
6+814.721	11.28 LT	-	6+852.395	11.28 LT	9.4
6+814.721	14.88 LT	-	6+852.395	14.88 LT	9.4
6+814.721	18.48 LT	-	6+852.395	18.48 LT	9.4
6+814.721	22.54 LT	-	6+852.395	22.08 LT	9.4
6+852.395	7.68 LT	-	7+050.000	7.68 LT	49.4
6+852.395	11.28 LT	-	7+050.000	11.28 LT	49.4
6+852.395	14.88 LT	-	7+050.000	14.88 LT	49.4
6+852.395	18.48 LT	-	7+050.000	18.48 LT	49.4
6+852.395	22.08 LT	-	7+050.000	22.08 LT	49.4
7+050.000	7.68 LT	-	7+380.276	7.68 LT	82.6
7+050.000	11.28 LT	-	7+380.276	11.28 LT	82.6
7+050.000	14.88 LT	-	7+380.276	14.88 LT	82.6
7+050.000	18.48 LT	-	7+380.276	18.48 LT	82.6
7+050.000	22.08 LT	-	7+380.276	22.08 LT	82.6
7+380.276	7.68 LT	-	7+750.000	7.68 LT	92.4
7+380.276	11.28 LT	-	7+750.000	11.28 LT	92.4
7+380.276	14.88 LT	-	7+750.000	14.88 LT	92.4
7+380.276	18.48 LT	-	7+750.000	18.48 LT	92.4
7+750.000	7.68 LT	-	7+951.532	7.68 LT	50.4
7+750.000	11.28 LT	-	7+951.532	11.28 LT	50.4
7+750.000	14.88 LT	-	7+951.532	14.88 LT	50.4
7+750.000	18.48 LT	-	7+951.532	18.48 LT	50.4
TOTAL =					2,415

POLYUREA PAVEMENT MARKING TYPE I - LINE 300MM

STATION	OFFSET(m)	-	STATION	OFFSET(m)	METERS
ILLINOIS					
EASTBOUND YELLOW					
6+814.721	0.48 RT	-	6+818.321	4.08 RT	5.10
6+964.721	0.48 RT	-	6+968.321	4.08 RT	5.10
7+114.721	0.48 RT	-	7+118.321	4.08 RT	5.10
7+264.721	0.48 RT	-	7+268.321	4.08 RT	5.10
7+413.792	0.48 RT	-	7+417.531	4.08 RT	5.20
7+562.599	0.48 RT	-	7+566.163	4.08 RT	5.10
7+711.044	0.48 RT	-	7+714.655	4.08 RT	5.10
7+859.489	0.48 RT	-	7+863.100	4.08 RT	5.10
EASTBOUND WHITE					
6+814.721	27.70 RT	-	6+818.374	24.05 RT	5.20
6+964.721	25.68 RT	-	6+968.321	22.08 RT	5.10
7+114.721	25.68 RT	-	7+118.321	22.08 RT	5.10
7+264.721	25.68 RT	-	7+268.321	22.08 RT	5.10
7+413.792	30.01 RT	-	7+421.525	22.08 RT	11.50
7+562.599	25.68 RT	-	7+566.237	22.08 RT	5.10
7+711.044	25.68 RT	-	7+714.682	22.08 RT	5.10
7+859.489	25.68 RT	-	7+863.127	22.08 RT	5.10