

EARTHWORK SCHEDULE OF QUANTITIES

STA. - STA. INDIANA	EXCAVATION COMMON (CU M)			TOTAL SUITABLE EXCAVATION (CU M)			EXCAVATION TO BE USED IN EMBANKMENT (ADJUSTED FOR SHRINKAGE 15%) (CU M)			EMBANKMENT (CU M)			EARTHWORK BALANCE WASTE (-) OR SHORTAGE (+) (CU M)		
	STAGE 1	STAGE 2	STAGE 3	STAGE 1	STAGE 2	STAGE 3	STAGE 1	STAGE 2	STAGE 3	STAGE 1	STAGE 2	STAGE 3	STAGE 1	STAGE 2	STAGE 3
9+100 - 9+125	13.50	115.63	231.00	13.50	115.63	231.00	11.48	98.28	196.35	111.50	0.00	2.00	-100.03	98.28	194.35
9+125 - 9+150	53.75	128.50	295.13	53.75	128.50	295.13	45.69	109.23	250.86	71.25	0.00	0.63	-25.56	109.23	250.23
9+150 - 9+175	114.25	156.25	363.00	114.25	156.25	363.00	97.11	132.81	308.55	33.13	0.00	0.13	63.99	132.81	308.43
9+175 - 9+200	123.88	187.88	395.75	123.88	187.88	395.75	105.29	159.69	336.39	26.25	0.00	0.00	79.04	159.69	336.39
9+200 - 9+225	124.75	187.75	449.13	124.75	187.75	449.13	106.04	159.59	381.76	22.25	0.00	0.00	83.79	159.59	381.76
9+225 - 9+250	97.00	148.88	508.63	97.00	148.88	508.63	82.45	126.54	432.33	8.75	0.00	0.00	73.70	126.54	432.33
9+250 - 9+275	59.50	93.63	511.13	59.50	93.63	511.13	50.58	79.58	434.46	2.38	0.00	0.00	48.20	79.58	434.46
9+275 - 9+300	91.38	62.75	380.88	91.38	62.75	380.88	77.67	53.34	323.74	0.00	0.00	0.00	77.67	53.34	323.74
9+300 - 9+325	143.38	59.38	254.00	143.38	59.38	254.00	121.87	50.47	215.90	0.00	0.00	0.00	121.87	50.47	215.90
9+325 - 9+350	137.63	60.25	216.50	137.63	60.25	216.50	116.98	51.21	184.03	0.00	0.00	0.00	116.98	51.21	184.03
9+350 - 9+375	104.25	54.38	204.25	104.25	54.38	204.25	88.61	46.22	173.61	0.00	0.00	0.00	88.61	46.22	173.61
9+375 - 9+395	72.92	35.60	144.12	72.92	35.60	144.12	61.98	30.26	122.50	0.00	0.00	0.00	61.98	30.26	122.50

PAY ITEM SUMMARY FOR INDIANA TOTAL				
	STAGE 1	STAGE 2	STAGE 3	TOTAL
EXCAVATION COMMON (INDIANA)	1226.05	1537.35	4755.27	7518.7
BORROW (INDIANA)	12465.51	4594.56	13835.57	30895.6

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-80/94/US 6
KINGERY-BORMAN EXPRESSWAY
BURNHAM ROAD TO US 41
EARTHWORK SCHEDULE OF QUANTITIES

SCALE: _____ DATE: 07/05

DRAWN BY ACE/CAD
CHECKED BY TAE

AMERICAN
CONSULTING ENGINEERS