

Revised 1-15-2021

Designer Note: If your project is to be cold milled and it is anticipated/scheduled such that it will not be completed with the final surface in one or more construction seasons, use the following General Note. This note assures that all milled areas have at least a LB/binder course placed, all lanes opened and properly marked, and manholes have been adjusted. Discuss with Construction before using. Revision: eliminated Rural/Urban selection - kept urban for all work. Article revised 7-1-94.

This can also be used for SMART and PPP projects to ensure that milled surfaces are overlaid before winter shutdown.

WINTER SHUTDOWN RESTRICTIONS ON COLD MILLED PROJECTS

Prior to winter shutdown manholes, where applicable, shall be adjusted to the elevation of the binder course/leveling binder to ease in plowing snow, and re-adjusted to finished grade in the Spring. The initial manhole adjustment will be paid for at the contract unit price and any re-adjustment, as directed by the Engineer, will be paid for in accordance with Article 109.04.