

## GENERAL NOTES:

- Temporary Drainage This work consists of furnishing and installing a 3 PVC pipe in the proposed inlet to facilitate drainage off the pavement prior to the placement of bituminous surface course.
- 2. Adequate pavement drainage shall be maintained during all phases of constructiion.
- 3. The PVC pipe is to be filled with mortar prior to surface course placement.
- 4. This detail applies to all inlet types.

USER NAME = Eric. Thomas	DESIGNED -	REVISED -		TEMPORARY INLET DRAINAGE TREATMENT						F.A.	SECTION	COUNTY	TOTAL	SHEET	
	DRAWN -	REVISED -	STATE OF ILLINOIS												
	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION							DIS	DISTRICT 4 DETAIL NO. 602401		CONTRACT NO.		
PLOT DATE = 12/7/2022	DATE -	REVISED _		SCALE: NOT TO SCALE	SHEET	OF	SHE	EETS	STA.	TO STA.		ILLINOIS FED. AID PRO.			

## All dimensions are in inches unless otherwise noted.