

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

Various Routes  
D 1 OVD SIN STR REPL 2010-29  
Various Counties  
Sheet 3 of 16  
Contract Number 46092

District 1  
Schedule of Overhead Sign Structure Repair & Replacement

Location No.:	1-01	State I.D. No.:	1S045U030R000.0-001(KG6)				
County:	Kane	Route:	US-30	M.P.:	0.0	Direction:	EB
Description of Work	Unit	Quantity					
Remove & Re-erect Overhead Sign Structure - Span	Each	1.00					
Structural Steel Support Overhead Sign Structure	Each	2.00					
Furnish & Install Internal Truss Damper	Each	1.00					
Furnish & Install Safety Chain	Each	2.00					
Overhead Sign Support Grout Repair	Each	4.00					
Overhead Sign Structure Walkway	Foot	70.00					
Furnish & Install Saddle Shim Block	Each	4.00					
This work shall be completed during District 1 night-time hours.							

Location No.:	1-02	State I.D. No.:	1S049U041R000.0-004 (T3)				
County:	Lake	Route:	US-41	M.P.:	0.0	Direction:	NB
Description of Work	Unit	Quantity					
Remove Light Glare Reduction System	Each	1.00					
This work shall be completed during District 1 night-time hours.							

Location No.:	1-03	State I.D. No.:	1S045S056L000.0 (HG3)				
County:	Kane	Route:	IL 56	M.P.:	0.0	Direction:	WB
Description of Work	Unit	Quantity					
Remove & Re-erect Overhead Sign Structure-Span	Each	1.00					
Structural Steel Sign Support Overhead Sign Structure	Each	2.00					
Furnish & Install Internal Truss Damper	Each	1.00					
Furnish & Install Safety Chain	Each	2.00					
Overhead Sign Support Grout Repair	Each	4.00					
Overhead Sign Structure Walkway	Foot	67.00					
Furnish & Install Saddle Shim Block	Each	4.00					
Repair Concrete Foundation for Overhead Sign Structure	Each	2.00					
This work shall be completed during District 1 night-time hours.							

Location No.:	1-04	State I.D. No.:	1S016I057R341.9 (W2)				
County:	Cook	Route:	I-57	M.P.:	341.9	Direction:	NB
Description of Work	Unit	Quantity					
Remove & Re-erect Overhead Sign Structure-Span	Each	1.00					
Structural Steel Sign Support Overhead Sign Structure	Each	2.00					
Furnish & Install Internal Truss Damper	Each	1.00					
Furnish & Install Safety Chain	Each	2.00					
Overhead Sign Structure Walkway	Foot	111.50					
Furnish & Install Saddle Shim Block	Each	4.00					
Furnish & Install Metal Screen	Each	4.00					
This work shall be completed during District 1 night-time hours.							

Location No.:	1-05	State I.D. No.:	1S016I057L342.4 (W1)				
County:	Cook	Route:	I-57	M.P.:	342.4	Direction:	SB
Description of Work	Unit	Quantity					
Remove & Re-erect Overhead Sign Structure-Span	Each	1.00					
Structural Steel Sign Support Overhead Sign Structure	Each	2.00					
Furnish & Install Internal Truss Damper	Each	1.00					
Furnish & Install Safety Chain	Each	2.00					
Overhead Sign Structure Walkway	Foot	112.50					
Furnish & Install Saddle Shim Block	Each	4.00					
Furnish & Install Metal Screen	Each	4.00					
This work shall be completed during District 1 night-time hours.							

Location No.:	1-06	State I.D. No.:	1S016I057L342.4 (W1)				
County:	Cook	Route:	I-57	M.P.:	342.4	Direction:	NB
Description of Work	Unit	Quantity					
Remove & Re-erect Overhead Sign Structure-Span	Each	1.00					
Structural Steel Sign Support Overhead Sign Structure	Each	2.00					
Furnish & Install Internal Truss Damper	Each	1.00					
Furnish & Install Safety Chain	Each	2.00					
Overhead Sign Structure Walkway	Foot	112.50					
Furnish & Install Saddle Shim Block	Each	4.00					
Furnish & Install Metal Screen	Each	4.00					
This work shall be completed during District 1 night-time hours.							

Location No.:	1-07	State I.D. No.:	1C016I080R154.3 (E2)				
County:	Cook	Route:	I-80	M.P.:	154.3	Direction:	EB
Description of Work	Unit	Quantity					
Remove & Re-erect Overhead Sign Structure - Span	Each	1.00					
Structural Steel Support Overhead Sign Structure	Each	2.00					
Furnish & Install Internal Truss Damper	Each	1.00					
Furnish & Install Safety Chain	Each	2.00					
Overhead Sign Support Grout Repair	Each	4.00					
Overhead Sign Structure Walkway	Foot	89.50					
Furnish & Install Saddle Shim Block	Each	4.00					
Replace Anchor Bolt	Each	3.00					
This work shall be completed during District 1 night-time hours.							

Location No.:	1-08	State I.D. No.:	1S016I094L000.0 (P2)				
County:	Cook	Route:	I-94	M.P.:	0.0	Direction:	WB
Description of Work	Unit	Quantity					
Remove & Re-erect Overhead Sign Structure - Span	EACH	1.00					
Structural Steel Support Overhead Sign Structure	EACH	2.00					
Furnish & Install Internal Truss Damper	EACH	1.00					
Furnish & Install Safety Chain	EACH	2.00					
Overhead Sign Support Grout Repair	EACH	4.00					
Overhead Sign Structure Walkway	FOOT	60.00					
Furnish & Install Saddle Shim Block	EACH	4.00					
This work shall be completed during District 1 night-time hours.							

Location No.:	1-09	State I.D. No.:	1S016I057L345.0 (T3)				
County:	Cook	Route:	I-57	M.P.:	345.0	Direction:	SB
Description of Work	Unit	Quantity					
Remove & Re-erect Overhead Sign Structure - Span	EACH	1.00					
Structural Steel Support Overhead Sign Structure	EACH	2.00					
Furnish & Install Internal Truss Damper	EACH	1.00					
Furnish & Install Safety Chain	EACH	2.00					
Overhead Sign Structure Walkway	FOOT	116.50					
Furnish & Install Saddle Shim Block	EACH	4.00					
Furnish & Install Metal Screen	EACH	4.00					
This work shall be completed during District 1 night-time hours.							

Location No.:	1-10	State I.D. No.:	1S016I057L344.6 (T5)				
County:	Cook	Route:	I-57	M.P.:	344.6	Direction:	SB
Description of Work	Unit	Quantity					
Remove & Re-erect Overhead Sign Structure - Span	EACH	1.00					
Structural Steel Support Overhead Sign Structure	EACH	2.00					
Furnish & Install Internal Truss Damper	EACH	1.00					
Furnish & Install Safety Chain	EACH	2.00					
Overhead Sign Structure Walkway	FOOT	128.50					
Furnish & Install Saddle Shim Block	EACH	4.00					
Furnish & Install Metal Screen	EACH	4.00					
This work shall be completed during District 1 night-time hours.							