

SUMMARY OF QUANTITIES			80% FEDERAL, 20% STATE		
CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITIES	ROADWAY 1000	BRIDGE X281-2A
20200100	EARTH EXCAVATION	CU YD	160	160	
21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	299	299	
25000310	SEEDING, CLASS 4	ACRE	0.1	0.1	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	9	9	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	9	9	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	9	9	
25100630	EROSION CONTROL BLANKET	SQ YD	299	299	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	10	10	
28000400	PERIMETER EROSION BARRIER	FOOT	307	307	
28000510	INLET FILTERS	EACH	4	4	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2	2	
40600300	AGGREGATE (PRIME COAT)	TON	4	4	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	3	3	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	44	44	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	10	10	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	152	152	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	98	98	
44000100	PAVEMENT REMOVAL	SQ YD	377	377	
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	787	787	
44000700	APPROACH SLAB REMOVAL	SQ YD	105		105
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	239	239	
44002207	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 1 3/4"	SQ YD	99	99	
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	18	18	
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	36	36	
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	45	45	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1320	1320	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1
50102400	CONCRETE REMOVAL	CU YD	5		5
50300225	CONCRETE STRUCTURES	CU YD	29		29

\* SPECIALTY ITEMS

SUMMARY OF QUANTITIES			80% FEDERAL, 20% STATE		
CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITIES	ROADWAY 1000	BRIDGE X281-2A
50300255	CONCRETE SUPERSTRUCTURE	CU YD	171		171
50300300	PROTECTIVE COAT	SQ YD	470		470
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	4433		4433
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	39360		39360
50800515	BAR SPLICERS	EACH	460		460
50901720	BICYCLE RAILING	FOOT	85		85
50901750	PARAPET RAILING	FOOT	131		131
51205200	TEMPORARY SHEET PILING	SQ FT	550		550
51500100	NAME PLATES	EACH	1		1
<del>5810100</del>	<del>WATERPROOFING MEMBRANE SYSTEM (SPECIAL)</del>	<del>SQ YD</del>	<del>545</del>		<del>545</del>
<del>58300100</del>	<del>PORTLAND CEMENT MORTAR FAIRING COURSE</del>	<del>FOOT</del>	<del>1391</del>		<del>1391</del>
59000200	EPOXY CRACK INJECTION	FOOT	374		374
60300105	FRAME AND GRATES TO BE ADJUSTED	EACH	4	4	
60300305	FRAME AND LIDS TO BE ADJUSTED	EACH	2	2	
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	135	135	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1	
* 63200710	STEEL PLATE BEAM GUARD RAIL REMOVAL, TYPE A	FOOT	282	282	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	9	9	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	24	24	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	672	672	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1156	1156	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	37	37	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2220	2220	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	85	85	

**LOCO, INC.**  
CONSULTING ENGINEERS  
1560 WALL ST, SUITE 222  
NAPERVILLE, ILLINOIS 60563 PH: (630) 517-9100

DESIGNED - MJY  
DRAWN - ST, TSC  
CHECKED - MJY, DC  
DATE - 10/16/2009

REVISED -  
REVISED -  
REVISED -  
REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES  
IL ROUTE 176 (ROCKLAND AVE) OVER US ROUTE 41 (SKOKIE HWY)**

SCALE: NONE SHEET NO. 3 OF 38 SHEETS STA. 99+20 TO STA. 102+90

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1238	1255B-1-R	LAKE	38	3
D-91-045-08			CONTRACT NO. 60D57	
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		