	SUMMARY OF QUANTITIES				80% FEDERAL, 20% STATE	
	CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 1000	BRIDGE X281-2A
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	12	12	
*	78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	8		8
*	78200500	BARRIER WALL MARKERS	EACH	56	56	
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	512	512	
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	20	12	8
*	81400115	HANDHOLE TO BE ADJUSTED	EACH	1	1	
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	335	335	
	X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	315		315
	X0325490	FURNISH AND INSTALL ACCESS DOOR	EACH	1		1
	X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	7998	7998	
	X0325837	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 6 INCH	FOOT	213	213	
	X0325840	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 12 INCH	FOOT	122	122	
	X0325842	WET REFLECTIVE TEMPORARY TAPE, TYPE III, LETTERS AND SYMBOLS	SQ FT	110	110	
△ ▲	XX005656	INLET FILTER CLEANING	EACH	4	4	
	XX006860	CLEANING & PAINTING METAL STRUCTURES	L SUM	1		1
	Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	72		72
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
	Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2	
	Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	4	4	
	X0326800	MASONRY WATERPROOFING PAINT	SQ YD	138		138

SUMMARY OF QUANTITIES				80% FEDERAL, 800% STATE	
CODE NO.	ITEM	UNIT	TOTAL	ROADWAY 1000	BRIDGE X281-2A

* SPECIALTY ITEMS ▲ Nonparticipating

LOYCO, INC.
CONSULTING ENGINEERS
1560 WALL ST. SUITE 222
NAPERVILLE, ILLINOIS 60563 PH: (630) 577-9100

DESIGNED - MJY	REVISED -		
DRAWN - ST, TSC	REVISED -		
CHECKED - MJY, DC	REVISED -		
DATE - 10/16/2009	REVISED -		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL ROUTE 176 (ROCKLAND AVE) OVER US ROUTE 41 (SKOKIE HWY)

SCALE: NONE | SHEET NO. 4 OF 38 SHEETS | STA. 99+20 TO STA. 102+90

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1238	125SB-1-R	LAKE	38	4
	D-91-045-08	CONTRACT NO. 60D57		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		