

SPECIALTY ITEM	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY		SURVEILLANCE		BRIDGE SN 022-0101 SN 022-0102		BRIDGE (See Note A)	
					90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE		
					CONSTRUCTION TYPE CODE							
	X0325822	CONCRETE BARRIER WALL REMOVAL AND REPLACEMENT (PARTIAL DEPTH REPAIR)	FOOT	8	8							
	X0325842	WET REFLECTIVE TEMPORARY TAPE, TYPE III, LETTERS AND SYMBOLS	SQ FT	1,634	1,634							
	X0325840	WET REFLECTIVE TEMPORARY TAPE TYPE III, 12 INCH	FOOT	8,119	8,119							
	X0325876	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 8 INCH	FOOT	67,276	67,276							
	X0326090	ERECTING STRUCTURAL STEEL	POUND	9,260								9,260
	X0326107	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 5 INCH	FOOT	41,690	41,690							
	X4066580	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	60,176	60,176							
	X4066685	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80	TON	49,923	49,923							
	X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1							
	X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	149	149							
	X8730312	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 4/C, TWISTED, SHIELDED	FOOT	11,546			11,546					
	X8850102	INDUCTION LOOP	FOOT	3,139			3,139					
	Z0001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)	SQ YD	99.6				28.3				71.3
	Z0003600	BEAM STRAIGHTENING	L SUM	1	1							
	Z0006220	BRIDGE DECK HYDRO-SCARIFICATION 2 1/4"	SQ YD	21,341				2,792				18,549
	Z0006225	BRIDGE DECK HYDRO-SCARIFICATION 2 1/2"	SQ YD	8,121								8,121
**	* X0322059	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	10	10							
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1							
**	* X0036120	MULCH PLACEMENT 4"	SQ YD	3600	3600							
	Z0018001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	370.0				39.8				330.2
**	X2010300	TREE REMOVAL (UNDER 6 UNITS DIAMETER)	UNIT	960	960							
	Z0018002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	894.0				55.2				838.8
**	Z0004800	SELECTIVE CLEARING	UNIT	600	600							
Δ	Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	25	25							
**	* X0325222	WEED CONTROL, BASAL TREATMENT	GALLON	60	60							
	Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	8	8							
	Z0018700	DRAINAGE STRUCTURE TO BE REMOVED	EACH	1	1							
	Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3	EACH	12	12							
**	* X0322856	WEED CONTROL, NON-SELECTIVE AND NON-RESIDUAL	GALLON	2.4	2.4							
	Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	5	5							
**	* X0036660	MOWING CYCLES	EACH	2	2							
	Z0030270	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, WIDE), TEST LEVEL 3	EACH	2	2							
	Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	5	5							
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1							
	Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	16	16							
	Z0073200	TEMPORARY SHORING CRIBBING	EACH	6	6							6
**	* X0326701	WEED CONTROL AND BROADLEAF IN TURF	POUND	1.4	1.4							
	Z0073351	TEMPORARY SLAB SUPPORT SYSTEM	L SUM	1	1							1
**	* A2012122	TREE, AESCULUS AUTUMN SPLENDOR (AUTUMN SPLENDOR BUCKEYE) 1 3/4" CALIPER, BALLED AND BURLAPPED, MATCHING HEADS	EACH	25	25							32
	Z0073400	TEMPORARY SUPPORT SYSTEM	EACH	32	32							
	Z0075810	TIE BARS 3/4"	EACH	47	47							
	X0326768	CONDUIT IN TRENCH, HIGH DENSITY POLYETHYLENE, COIL ABLE	FOOT	100			100					
	X0326818	CONCRETE BARRIER REMOVAL AND REPLACEMENT SINGLE FACE	FOOT	100	100							
	X0326791	NOISE ABATEMENT WALL REPAIRS	L SUM	1	1							
	X0326819	CONCRETE BARRIER REMOVAL AND REPLACEMENT DOUBLE FACE	FOOT	230	230							
	X0326792	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 3/4 INCHES	SQ YD	1,297								1,297
**	* A2002614	TREE, CARYA CORDIFORNIS (BITTERNUT HICKORY), 1 3/4" CALIPER, BALLED AND BURLAPPED	EACH	20	20							
	X0326793	BRIDGE DECK HYDRO-SCARIFICATION 2 3/4"	SQ YD	1,297								1,297
**	* A2002914	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 1 3/4" CALIPER, BALLED AND BURLAPPED	EACH	25	25							
	X0326765	CLEANING AND PAINTING EXPOSED REBAR (SPECIAL)	SQ FT	770				69				701
**	* A2005014	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEE TREE), 1 3/4" CALIPER, BALLED AND BURLAPPED	EACH	45	45							
	X0326794	CLEAN AND RESEAL RELIEF JOINT (AND)	FOOT	901.5				163.5				738
**	* A2006514	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1 3/4" CALIPER, BALLED AND BURLAPPED	EACH	30	30							
	X0326795	MODIFY EXISTING PIN LINK CONNECTION (AND)	L SUM	1	1							1
**	* A2001664	TREE, CRATAEGUS CRUSGALLI INERMIS (THORNLESS COCKSPUR HAWTHORNE), 5' HEIGHT, SHALB FORM BALLED AND BURLAPPED	EACH	30	30							
Δ	X0326796	CLEAN TROUGH	EACH	4	4							4
**	* B2000116	TREE SYRINGA PEKINENSIS MORTON (CHINA SYDOW PEKING ULAC), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	25	25							
	X0326797	REATTACH GUARD RAIL TO STRUCTURE	EACH	4	4							
	X0326798	PIN REPLACEMENT	EACH	32								32
	Z0076600	TRAINEES	HOUR	1,500	1,500							
	X0326799	CLIP EXISTING BEAM FLANGE	EACH	11								11


** FOR LOCATIONS AND EXTENTS OF WORK NOT SHOWN IN THE PLANS, THE CONTRACTOR SHALL COORDINATE WITH THE ENGINEER AND CONTACT RICK WANNER, ROADSIDE DEVELOPMENT ARCHITECT, IDOT ROADSIDE DEVELOPMENT UNIT AT (847) 705-4172 AT LEAST 72 HOURS PRIOR TO STARTING WORK.

NOTE A: SN 022-0092, SN 022-0194, SN 022-0095, SN 022-0096, SN 022-0097, SN 022-0098, SN 022-0099, SN 022-0100, SN 022-0104, SN 022-0105, SN 022-0111, SN 022-0112, SN 022-0137, SN 022-0138

Δ Non-participating

Rev. 1-B-10

Rev

FILE NAME =	DESIGNED - AJP	REVISED -		STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#	DRAWN - TMB	REVISED -			SCALE: N.T.S.	SHEET NO. 4 OF 4 SHEETS	STA.	TO STA.	2211, 1-1, 2&3RS-7	DUPAGE	546	6
USER NAME = #USER#	CHECKED - JMM	REVISED -						*290,355		CONTRACT NO. 60G51		
PLOT DATE = #DATE#	DATE - 10/16/09	REVISED -						FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		