

SPECIALTY ITEM	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	SURVEILLANCE	BRIDGE SN 016-0088	BRIDGE SN 016-0090	BRIDGE SN 016-0086 SN 016-2758	BRIDGE SN 016-0085 SN 016-0986 SN 016-2759
					90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE
					CONSTRUCTION TYPE CODE					
					1000-2A	Y032-1F	X020-2A	X071-2A	X231-2A	X271-2A
	X0325739	HOT-MIX ASPHALT SHOULDER REMOVAL AND REPLACEMENT (SPECIAL)	SQ YD	25,740	25,740					
	X0325754	REPLACEMENT OF SENSORS FOR ROADWAY WEATHER INFORMATION SYSTEM	L SUM	1		1				
	X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	176,098	176,098					
	X0325840	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 12 INCH	FOOT	6,841	6,841					
	X0325876	WET REFLECTIVE TEMPORARY TAPE TYPE III, 8 INCH TYPE III	FOOT	51,323	51,323					
	X0325842	WET REFLECTIVE TEMPORARY TAPE, LETTERS AND SYMBOLS	SQ FT	109	109					
	X0326107	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 5 INCH	FOOT	44,592	44,592					
	X4066580	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	57,738	57,738					
	X0326849	CLEANING OF WET PIT	TON	2,070	2,070					
	X4066685	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80	TON	47,902	47,902					
	X0326850	MAIN DRAIN JOINT REPAIR	FOOT	357	357					
	X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	10	10					
	X0325095	MAIN DRAIN CLEANING	FOOT	18,005	18,005					
	X011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1						
**	X0322059	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	200	200					
	X013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	65	65					
**	X2010300	TREE REMOVAL (UNDER 6 UNITS DIAMETER)	UNIT	248	248					
	X8730312	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 4/C, TWISTED, SHIELDED	FOOT	14,932		14,932				
**	Z0064800	SELECTIVE CLEARING	UNIT	305	305					
	X8850102	INDUCTION LOOP	FOOT	4,086		4,086				
**	X0325222	WEED CONTROL, BASAL TREATMENT	GALLON	15	15					
	Z001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)	SQ YD	124.0			24.4	49.0	20.6	30.0
**	X0325921	PLANT CARE	SQ YD	6,790	6,790					
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1					
**	X0322856	WEED CONTROL, NON-SELECTIVE AND NON-RESIDUAL	GALLON	2	2					
	Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	82.5			18.6	10.0	38.3	15.6
**	K0036120	MULCH PLACEMENT 4"	SQ YD	4,150	4,150					
	Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	738	738					
**	K1003660	MOWING CYCLES	EACH	2	2					
	Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	27	27					
	XX005656	INLET FILTER CLEANING	EACH	738	738					
	Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	18	18					
	Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	2	2					
	Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2					
	Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	13	13					
	Z0048685	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					
**	X2186500	ASPHALTIC EMULSION SLURRY SEAL	SQ YD	10,000	10,000					
	Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	6						6
	Z0070600	TRAINEES	HOOR	1500	1500					
	X0326768	CONDUIT IN TRENCH, HIGH DENSITY POLYETHYLENE, COILABLE	FOOT	100		100				
**	X0325223	FIBER ASPHALT	POUND	334	334					
	X0326765	CLEANING AND PAINTING EXPOSED REBAR (SPECIAL)	SQ FT	10					10	
**	X0326701	WEED CONTROL, BROADLEAF IN TURF	POUND	0.8	0.8					
**	X0326766	CLEAN & RESEAL RELIEF JOINT	FOOT	798.5			189.0	217.5	144.0	248.0
**	X0326843	STAINING EXISTING COLORED CONCRETE SURFACES	SQ FT	2,000	2,000					
	X0326769	REMOVE AND REINSTALL CHAIN LINK FENCE POST	EACH	7				7		

△ - Non-participating
 * - Specialty Items
 ○ - Y080

** FOR LOCATIONS AND EXTENT OF WORK NOT SHOWN IN THE PLANS, THE CONTRACTOR SHALL COORDINATE WITH THE ENGINEER AND CONTACT RICK WANNER, ROADSIDE DEVELOPMENT ARCHITECT, IDOT ROADSIDE DEVELOPMENT UNIT AT (847) 705-4172 AT LEAST 72 HOURS PRIOR TO STARTING WORK.

Rev. 1-4-10

Rev.

FILE NAME =	DESIGNED - AJP	REVISED -	benesch	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
...pprIn_ABC_C2_sq_83.dgn	DRAWN - TMB	REVISED -						290	(3031.1, ETC., 3838/RS-5	COOK	298	5	
USER NAME = tblank	CHECKED - JMM	REVISED -						CONTRACT NO. 60G52					
PLOT DATE = 10/16/09	DATE - 10/16/09	REVISED -						SCALE: N.T.S.	SHEET NO. 3 OF 3 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT