

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

Reinforcement bars shall conform to the requirements of ASTM A 706 Gr 60. See Special Provisions.

Plan dimensions and details relative to existing plans are subject to nominal construction variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.

Concrete Sealer shall be applied to the bridge decks, top and inside faces of parapets, approach slabs, abutment seats and abutment backwalls. All surfaces to be sealed shall be cleaned thoroughly prior to sealer application. Cost included in Concrete Sealer.

Stage construction shall be utilized to maintain traffic during construction.

INDEX OF SHEETS

1. General Plan and Elevation
2. General Notes, Bill of Material and Index of Sheets
3. Stage Construction Details
4. Bridge Deck and Approach Slab Repairs
5. Chain Link Fence Post and Bridge Parapet Repairs

TOTAL BILL OF MATERIAL

ITEM	UNIT	SUPER	SUB	TOTAL
Concrete Sealer	Sq. Ft.	28,100	1,327	29,427
Silicone Joint Sealer	Foot	199.5		199.5
Approach Slab Repair (Partial Depth)	Sq. Yd.	49.0		49.0
Deck Slab Repair (Partial)	Sq. Yd.	10.0		10.0
Clean & Reseal Relief Joint	Foot	217.5		217.5
Remove and Reinstall Chain Link Fence Post	Each	7		7

**GENERAL NOTES, BILL OF MATERIAL
AND INDEX OF SHEETS
STRUCTURE NO. 016-0090**

DESIGNED -	DMS
CHECKED -	EFS
DRAWN -	RMG
CHECKED -	KJN

benesch

alfred benesch & company
Engineers • Surveyors • Planners
205 North Michigan Avenue, Suite 2400
Chicago, Illinois 60601
312-565-0450 Job No. 10050

SHEET NO. 2 5 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	290	(3031.1, ETC., 3838)RS-5	COOK	298	247
FED. ROAD DIST. NO.			ILLINOIS	CONTRACT NO. 60G52	
FED. ROAD DIST. NO.			ILLINOIS	FED. AID PROJECT	