


WESTBOUND SIGN SCHEDULE

SIGN NO.	STATION	LEGEND/DESCRIPTION	EXISTING PANEL DIMENSIONS		PROPOSED PANEL DIMENSIONS		REMOVE SIGN PANEL-TYPE 1 (SQ FT)	REMOVE SIGN PANEL-TYPE 2 (SQ FT)	REMOVE SIGN PANEL-TYPE 3 (SQ FT)	REMOVE SIGN PANEL ASSEMBLY - TYPE A EACH	REMOVE SIGN PANEL ASSEMBLY - TYPE B EACH	SIGN PANEL TYPE 1 (SQ FT)	SIGN PANEL TYPE 2 (SQ FT)	SIGN PANEL TYPE 3 (SQ FT)	WOOD SIGN SUPPORT (FOOT)	TELESCOPING STEEL SIGN SUPPORT (FOOT)	REMOVAL OF SIGN LIGHTING, NO SALVAGE (EACH)
			WIDTH (FT)	HEIGHT (FT)	WIDTH (FT)	HEIGHT (FT)											
WB-CL-59	489+90	EXIT 15B - I 294 NORTH TOLLWAY - MILWAUKEE - EXIT ONLY	11.0	8.0	14.0	12.5			88.0					175.0			1.0
WB-WP-60	503+00	EXIT 15A	7.5	5.0	7.0	5.0					1.0			35.0	36.0		
WB-TR-61	505+00	LEFT EXIT 15A - I 88 WEST TOLLWAY I-294 SOUTH TOLLWAY - AURORA INDIANA - EXIT ONLY	25.0	10.5	25.0	11.5			262.5					287.5			1.0
WB-TR-62	505+00	EXIT 15B - I 290 WEST I-294 NORTH TOLLWAY - ROCKFORD MILWAUKEE	25.0	10.5	25.0	11.5			262.5					287.5			1.0
WB-WM-62A*	509+00	WOLF RD	1.8	8.7	1.8	8.7		15.2				15.2					
WB-TR-63	522+50	LEFT EXIT 15A - I 88 WEST TOLLWAY I-294 SOUTH TOLLWAY - AURORA INDIANA - EXIT ONLY	25.0	10.5	25.0	11.5			262.5					287.5			1.0
WB-TR-64	522+50	EXIT 15B - I 290 WEST I-294 NORTH TOLLWAY - ROCKFORD MILWAUKEE	25.0	10.5	25.0	11.5			262.5					287.5			1.0
WB-PM-64A	522+50	R2-1 (55 MPH)	4.0	5.0	4.0	5.0		20.0				20.0					
WB-GM-65	530+00	O'HARE - USE I 294 NORTH - EXIT 15B	16.0	10.0	16.0	10.5			160.0					168.0			
WB-WP-66	535+00	EXIT 16	6.0	5.0	6.0	5.0					1.0			30.0	36.0		
WB-WM-66A	540+81	W13-3 (30 MPH)	3.0	4.0	4.0	5.0		12.0				20.0					
WB-TR-67	541+20	LEFT EXIT 15A - I 88 WEST TOLLWAY I-294 SOUTH TOLLWAY - AURORA INDIANA - EXIT ONLY	23.5	9.5	23.5	9.5			223.3					223.3			1.0
WB-TR-68	541+20	EXIT 16 - WOLF RD	14.5	8.5	14.5	8.5			123.3					123.3			1.0
WB-TR-69	546+40	LEFT EXIT 15A - I 88 WEST TOLLWAY I-294 SOUTH TOLLWAY - AURORA INDIANA - EXIT ONLY	24.0	12.0	25.0	12.0			288.0					300.0			1.0
WB-TR-70	546+40	EXIT 15B - I 290 WEST I-294 NORTH TOLLWAY - ROCKFORD MILWAUKEE	24.0	12.0	25.0	12.0			288.0					300.0			1.0
WB-WP-70A	558+77	W4-1R	4.0	4.0	4.0	4.0					1.0		16.0		18.0		
WB-BM-71	565+70	EXIT 16 - WOLF RD - 1/2 MILE	11.0	8.0	11.5	8.0			88.0					92.0			1.0
WB-BM-71A*	565+70	US RT 12-20-45 - MANNHEIM RD	9.4	2.5	9.4	2.5		23.6				23.6					
WB-WP-71B	568+32	W4-3R	4.0	4.0	4.0	4.0		16.0						16.0		18.0	
WB-PM-71C	572+00	END - TRUCK - LANE - RESTRICTIONS	4.0	5.0	4.0	5.0		20.0					20.0				
WB-WP-72	576+50	EXIT 17	6.0	5.0	6.0	5.0					1.0			30.0	36.0		
WB-BM-72A*	579+21	WESTCHESTER BLVD	10.8	1.5	10.8	1.5		16.2					16.2				
WB-TS-72B	580+08	W13-3 (30 MPH)	3.0	4.0	4.0	5.0					1.0		20.0			18.0	
WB-TR-73	582+85	LEFT EXIT 15A - I 88 WEST TOLLWAY I-294 SOUTH TOLLWAY - AURORA INDIANA - LEFT 1 1/2 MILES	23.5	12.5	24.0	12.5			293.8					300.0			1.0
WB-TR-74	582+85	EXIT 16 - WOLF RD - 3/4 MILE	14.0	10.0	14.0	10.0			140.0					140.0			1.0
WB-TR-75	582+85	EXIT 17 - 12 20 45 - MANNHEIM RD	17.0	12.0	18.0	12.0			204.0					216.0			1.0
WB-PM-75A	584+58	RIGHT - LANE - MUST - EXIT	4.0	5.0	4.0	5.0		20.0					20.0				
WB-TS-75B1	590+92	M3-4	2.5	1.3	2.5	1.3				1.0		3.1				18.0	
WB-TS-75B2	590+92	M1-1-3 (I 290)	PER MUTCD STD (9FT ²)		PER MUTCD STD (9FT ²)					1.0		9.0					
WB-CL-76	595+90	EXIT 17 - 12 20 45 - MANNHEIM RD - 1/4 MILE	17.0	12.0	17.5	12.0			204.0					210.0			1.0
WB-WP-76A	602+06	W4-3R	4.0	4.0	4.0	4.0					1.0		16.0		18.0		
WB-WP-77	615+50	EXIT 18A	7.5	5.0	7.0	5.0					1.0			35.0	36.0		
WB-PM-77A	616+52	W13-3 (25 MPH)	3.0	4.0	4.0	5.0		12.0					20.0				
WB-BM-78	619+50	EXIT 18A - SOUTH - 25TH AVE	15.5	7.5	15.5	8.0			116.3					124.0			1.0
WB-BM-78A*	619+50	25TH AVE	6.3	1.5	6.3	1.5		9.4					9.4				
WB-BM-78B	619+50	14FT 4IN	5.5	1.5	5.5	1.5		8.3				8.3					
WB-WP-79	623+70	EXIT 18B	7.5	5.0	7.0	5.0			37.5					35.0	36.0		
WB-TR-80	624+50	EXIT 17 - 12 20 45 - MANNHEIM RD - 3/4 MILE	18.0	12.0	18.0	12.0			216.0					216.0			1.0
WB-TR-81	624+50	EXIT 18A - SOUTH - 25TH AVE - 1/4 MILE	18.0	12.0	18.0	12.0			216.0					216.0			1.0
WB-TR-82	624+50	EXIT 18B - NORTH - 25TH AVE	17.0	12.0	17.0	12.0			204.0					204.0			1.0
WB-PM-82B	625+02	W13-3 (30 MPH)	3.0	4.0	4.0	5.0		12.0					20.0				
WB-WP-82A	635+48	W4-1R	4.0	4.0	4.0	4.0					1.0			16.0		18.0	
WB-GM-83	646+20	EXIT 18B - NORTH - 25TH AVE - 1/2 MILE	14.0	10.0	14.0	10.0			140.0					140.0			
WB-GM-83A*	646+20	17TH AVE	6.1	1.5	6.1	1.5		9.2					9.2				
WB-BM-83B	646+20	14FT 4IN	5.5	1.5	5.5	1.5				1.0		8.3					
WB-WP-84	654+00	EXIT 19A	7.5	5.0	7.0	5.0					1.0			35.0	36.0		
WB-PM-84A	655+90	W13-3 (30 MPH)	3.0	4.0	4.0	5.0		12.0					20.0				
WB-CL-85	661+10	EXIT 19A - 17TH AVE	15.0	7.0	15.0	7.0			105.0					105.0			1.0
WB-BM-86	673+00	EXITS 18A -B - 25TH AVE - 1 MILE	13.5	8.5	13.0	8.5			114.8					110.5			1.0
WB-BM-87	673+00	EXIT 19A - 17TH AVE - 1/4 MILE	13.0	8.5	13.0	8.5			110.5					110.5			1.0
WB-BM-87B	673+00	14FT 3IN	5.5	1.5	5.5	1.5		8.3					8.3				
WB-BM-87A*	673+00	9TH AVE	5.7	1.5	5.7	1.5		8.5					8.5				
WB-WP-88	678+30	EXIT 19B	7.5	5.0	7.0	5.0					1.0			35.0	36.0		
WB-PM-88A	679+49	W13-3 (30 MPH)	3.0	4.0	4.0	5.0		12.0					20.0				
WB-BM-89	686+40	EXIT 19B - 9TH AVE	15.0	7.0	15.0	7.0			105.0					105.0			1.0
WB-BM-89A*	686+40	5TH AVE	5.7	1.5	5.7	1.5		8.5					8.5				
WB-BM-89B	686+40	14FT 4IN	5.5	1.5	5.5	1.5		8.3					8.3				
WB-PM-89C1	688+53	M3-4	2.5	1.3	2.5	1.3		3.1					3.1				
WB-PM-89C2	688+53	M1-1-3 (I 290)	PER MUTCD STD (9FT ²)		PER MUTCD STD (9FT ²)				9.0				9.0				
WB-TS-89D	692+52	W4-1R	4.0	4.0	4.0	4.0					1.0		16.0			18.0	
WB-PM-89E	691+78	R2-1 (55 MPH)	4.0	5.0	4.0	5.0			20.0				20.0				
WB-BM-90	699+70	EXIT 19A - 17TH AVE - 3/4 MILE	13.0	8.5	13.0	8.5			110.5					110.5			1.0
WB-BM-90A	699+70	14FT 5IN	5.5	1.5	5.5	1.5		8.3					8.3				
WB-BM-91	699+70	EXIT 19B - 9TH AVE - 1/4 MILE	12.0	8.5	12.0	8.5			102.0					102.0			1.0
WB-TS-91A*	699+70	ILL RTE 171 - 1ST AVE	7.2	2.5	7.2	2.5					1.0		17.9		18.0		
WB-WP-92	706+50	EXIT 20	6.0	5.0	6.0	5.0					1.0			30.0	36.0		
WB-PM-92A	708+23	W13-3 (30 MPH)	3.0	4.0	4.0	5.0		12.0					20.0				

*EXISTING SIGN DIMENSIONS NOT AVAILABLE; PROPOSED SIGN DIMENSIONS USED

FILE NAME =	DESIGNED - SEW	REVISED -	 LIN ENGINEERING, LTD. Consulting Engineers Channah, Illinois Westmont, Illinois	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION			SCHEDULE OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILEL#	DRAWN - SEW	REVISED -								290	(30311, ETC., 3838)RS-5	COOK	413	301
USER NAME = #USER#	CHECKED - FML	REVISED -								CONTRACT NO. 60G52				
PLOT DATE = #DATE#	DATE - 12/2009	REVISED -								SCALE: N.T.S.	SHEET NO. 3 OF 4 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.