SIGN DETAIL
1:75

WB-GM-65
STA. 530+00

SIGN NUMBER	name	
WIDTH x HGHT.	16'-0" x 10'-6"	
BORDER WIDTH	2"	
CORNER RADIUS	12"	
MOUNTING	Ground	
BACKGROUND	TYPE:	Reflective
	COLOR:	Green
LEGEND/BORDER	TYPE:	Reflective
	COLOR:	White/White

SYMBOL	ROT	X	Y	WID	HT
M1_1	0	56.5	40.8	45	36

Panel Style: sign_default.ssi
Dimensions are in inches.tenths

Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)																																							LENGTH	SERIES/SIZE
O	'	H	a	r	e																																			ClearviewHwy-5-W-R
35.2	53.9	61.7	78.2	94.1	104.5																																		81	16/13
U	S	E																																						ClearviewHwy-5-W
12.6	25.7	38.3																																					33.3	12
N	O	R	T	H																																				ClearviewHwy-5-W
113.5	130.7	146.1	158	170.3																																			65.9	15,12
E	X	I	T	1	5	B																																		ClearviewHwy-5-W
56.5	66.7	80.4	86.3	105	116.9	132.6																																	87.5	12,15

FILE NAME =	DESIGNED - SEW	REVISED -
$FILEL$	DRAWN - SEW	REVISED -
USER NAME = $USER$	CHECKED - FML	REVISED -
PLOT DATE = $DATE$	DATE - 12/2009	REVISED -

LIN ENGINEERING, LTD.
Consulting Engineers
Chatham, Illinois Westmont, Illinois

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIGNING DETAILS

SCALE: N.T.S. | SHEET NO. 41 OF 77 SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
290	(3031.1, ETC., 3838)RS-5	COOK	413	369
		CONTRACT NO. 60G52		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		