

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
FAU 1321	0303 VB-I	COOK	21	4

CONTRACT NO.: 60H80

CONSTRUCTION TYPE CODE: SFTY - 2A *URBAN*

CODE NO.	ITEMS	UNITS	TOTAL QUANTITIES
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	320
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	45
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	34
50102400	CONCRETE REMOVAL	CU YD	16
50157300	PROTECTIVE SHIELD	SQ YD	101
50300255	CONCRETE SUPERSTRUCTURE	CU YD	18
50300260	BRIDGE DECK GROOVING	SQ YD	683
50300300	PROTECTIVE COAT	SQ YD	727
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2100
52000110	PREFORMED JOINT STRIP SEAL	FOOT	103
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3
67100100	MOBILIZATION	L SUM	1
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	20.8
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1781
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	50

*\* Specialty Items*

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES