



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

December 30, 2009

SUBJECT: FAU Route 3578(Southwest Highway)
Project ACM-ACBRF-3578(010)
Section 15VB-1-R-1
Cook County
Contract No. 62388
Item No. 125, January 15, 2010 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised page iv of the Table of Contents to the Special Provisions.
3. Added pages 235-236 to the Special Provisions.
4. Revised Sheet 3 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Charles Ingersoll, Chief
Bureau of Design and Environment

A handwritten signature in cursive script, appearing to read "Ted B. Walschleger" followed by a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Mike Renner; R.E. Anderson;
Estimates

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62388

State Job # - C-91-050-02
 PPS NBR - 1-73777-0200
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 15VB-1-R-1

Project Number
 ACM-ACBRF-3578/010/

Route
 FAU 3578

* REVISED : DECEMBER 30, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
A2005020	T-GYMNOCLA DIO 2-1/2	EACH	4.000				
A2005616	T-OSTRYA VIRG 2	EACH	12.000				
A2008080	T-TILIA CORD LINDEN 2	EACH	15.000				
C2C05824	S-RHUS AROMA GRO 2'C	EACH	200.000				
C2C06136	S-RHUS TYPH LAC 3'C	EACH	50.000				
C2008224	S-ROSA NEAR WILD 24	EACH	75.000				
C2011736	S-VIBURN DENT 3'	EACH	30.000				
MX030063	STORM SEW WM REQ 300	METER	83.000				
MX030199	TEMP PAVEMENT	SQ M	1,576.000				
MX030243	CON ATS 75 GALVS PVC	METER	400.000				
MX032178	TEMP INFO SIGNING	SQ M	37.000				
MX032651	MULCH PLACEMENT 100	SQ M	65.000				
MX032680	WEED CONTR PRE-EM GRN	KG	200.000				
MX032723	PREFORM DETECT LOOP	METER	44.000				
MX032819	ELCBL C TRACER 14 1C	METER	134.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62388

State Job # - C-91-050-02
 PPS NBR - 1-73777-0200
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 15VB-1-R-1

Project Number
 ACM-ACBRF-3578/010/

Route
 FAU 3578

* REVISED : DECEMBER 30, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
MX033276	TEMP SOIL RETEN SYSTM	SQ M	62.000				
MX033399	CON ATS 50 RGS PVC	METER	424.000				
MX033445	DRILL/SET SOLD P SOIL	CU M	9.400				
MX033460	WET TEM PM TAP T3 100	METER	25,009.000				
MX033461	WET TEM PM TAP T3 150	METER	937.000				
MX033724	GROUND ROD 16X3	EACH	19.000				
MX033761	ANCHOR BOLTS M30	EACH	136.000				
MX033767	WET TEM PM TAP T3 L&S	SQ M	75.000				
MX033781	WET TEM PM TAP T3 300	METER	301.000				
MX033782	WET TEM PM TAP T3 600	METER	192.000				
MX033783	TEMP CH LK FENCE	METER	300.000				
MX207010	POR GRN EMB SUBGR 300	SQ M	535.000				
MX816008	UD 3#6 #8G EPRRH 30	METER	758.000				
MX816060	UD 2#6 #6G EPRRH 25	METER	105.000				
MX871055	FOCC62.5/125 MM12SM12	METER	134.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

62388

State Job # - C-91-050-02
 PPS NBR - 1-73777-0200
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 15VB-1-R-1

Project Number
 ACM-ACBRF-3578/010/

Route
 FAU 3578

* REVISED : DECEMBER 30, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
MX873027	ELCBL C GROUND 6 1C	METER	7.000				
MX873030	ELCBL C 20 3C TW SH	METER	726.000				
MZ001050	AGG SUBGRADE 300	SQ M	8,225.000				
MZ020500	EPOXY PAVT MK REMOV	METER	4,668.000				
MZ020600	EPOXY PAVT MK REMOV	SQ M	7.000				
MZ034390	MODULAR EXPAN JT 160	METER	36.600				
MZ064800	SELECTIVE CLEARING	UNIT	15.000				
M2010110	TREE REMOV 6-15	UNIT	49.000				
M2010210	TREE REMOV OVER 15	UNIT	5.000				
M2011000	TEMPORARY FENCE	METER	64.000				
M2011300	TREE PRUN 25-250	EACH	12.000				
M2011350	TREE PRUN OVER 250	EACH	10.000				
M2011400	NITROGEN FERT NUTR	KG	26.000				
M2011500	PHOSPHORUS FERT NUTR	KG	26.000				
M2011600	POTASSIUM FERT NUTR	KG	26.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

62388

State Job # - C-91-050-02
 PPS NBR - 1-73777-0200
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 15VB-1-R-1

Project Number
 ACM-ACBRF-3578/010/

Route
 FAU 3578

* REVISED : DECEMBER 30, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M2020010	EARTH EXCAVATION	CU M	741.000				
M2021200	REM & DISP UNS MATL	CU M	324.000				
M2030100	CHANNEL EXCAV	CU M	914.000				
M2040800	FURNISHED EXCAV	CU M	1,812.000				
M2070400	POROUS GRAN EMB SPEC	CU M	192.000				
M2080150	TRENCH BACKFILL	CU M	141.000				
M2113150	TOPSOIL F & P 150	SQ M	3,650.000				
M2500200	SEEDING CL 2	HA	0.110				
M2510630	EROSION CONTR BLANKET	SQ M	1,128.000				
M2520110	SODDING SALT TOLERANT	SQ M	2,522.000				
M2800250	TEMP EROS CONTR SEED	KG	41.000				
M2800400	PERIMETER EROS BAR	METER	1,135.000				
M2810107	STONE RIPRAP CL A4	SQ M	1,461.000				
M2820200	FILTER FABRIC	SQ M	1,355.000				
M4202255	PCC PVT 250 JOINTED	SQ M	7,551.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62388

State Job # - C-91-050-02
 PPS NBR - 1-73777-0200
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 15VB-1-R-1

Project Number
 ACM-ACBRF-3578/010/

Route
 FAU 3578

* REVISED : DECEMBER 30, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M4205050	BR APPROACH PAVT SPL	SQ M	367.000				
M4205200	PROTECTIVE COAT	SQ M	9,076.000				
M4230200	PCC DRIVEWAY PAVT 200	SQ M	324.000				
M4240125	PC CONC SIDEWALK 125	SQ M	512.000				
M4248000	DETECTABLE WARNINGS	SQ M	7.500				
M4402000	PAVEMENT REM	SQ M	7,216.000				
M4402010	DRIVE PAVEMENT REM	SQ M	477.000				
M4402040	COMB CURB GUTTER REM	METER	770.000				
M4402050	SIDEWALK REM	SQ M	557.000				
M4402060	APPROACH SLAB REM	SQ M	243.000				
M4402310	CONC MEDIAN SURF REM	SQ M	17.000				
M4402420	MEDIAN REMOVAL	SQ M	420.000				
M4820550	HMA SHOULDERS 150	SQ M	80.000				
M5010240	CONC REM	CU M	98.300				
M5010570	PROTECTIVE SHIELD	SQ M	371.400				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62388

State Job # - C-91-050-02
 PPS NBR - 1-73777-0200
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 15VB-1-R-1

Project Number
 ACM-ACBRF-3578/010/

Route
 FAU 3578

* REVISED : DECEMBER 30, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M5020100	STRUCTURE EXCAVATION	CU M	1,526.000				
M5020200	COFFERDAM EXCAVATION	CU M	560.000				
M5030350	CONC STRUCT	CU M	1,386.000				
M5030360	CONC SUP-STR	CU M	1,798.200				
M5030390	BR DECK GROOVING	SQ M	4,971.000				
M5030400	SEAL COAT CONC	CU M	155.500				
M5030450	PROTECTIVE COAT	SQ M	7,465.000				
M5050305	ERECT STRUCT STEEL	L SUM	1.000				
M5050405	F & E STRUCT STEEL	KG	7,860.000				
M5080205	REINF BARS, EPOXY CTD	KG	347,910.000				
M5090500	BICYCLE RAILING	METER	417.600				
M5090505	BICYCLE RAILING SPL	METER	5.700				
M5120160	F STL PILE HP310X79	METER	3,599.200				
M5120250	FUR SOLDIER PILES HP	METER	36.500				
M5120335	DRIVING PILES	METER	3,599.200				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62388

State Job # - C-91-050-02
 PPS NBR - 1-73777-0200
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 15VB-1-R-1

Project Number
 ACM-ACBRF-3578/010/

Route
 FAU 3578

* REVISED : DECEMBER 30, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M5120460	TEST PIL ST HP310X79	EACH	7.000				
M5200225	PREF JT STRIP SEAL	METER	65.000				
M5210022	ANCHOR BOLTS M24	EACH	40.000				
M5210024	ANCHOR BOLTS M36	EACH	196.000				
M5500030	STORM SEW CL A 1 300	METER	97.000				
M5510025	STORM SEWER REM 300	METER	135.000				
M5610950	ADJ WATER MAIN 350	METER	45.000				
M5870300	CONCRETE SEALER	SQ M	99.000				
M5910100	GEOCOMPOSITE WALL DR	SQ M	122.000				
M6010610	PIPE UNDERDRAINS 150	METER	439.000				
M6011100	P UNDR - STRUCT 100	METER	75.000				
M6020185	CB A 1.2M D T24F&G	EACH	10.000				
M6060400	COMB CC&G TB15.15	METER	18.000				
M6060700	COMB CC&G TB15.60	METER	658.000				
M6063600	CONC MEDIAN SURF 100	SQ M	82.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62388

State Job # - C-91-050-02
 PPS NBR - 1-73777-0200
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 15VB-1-R-1

Project Number
 ACM-ACBRF-3578/010/

Route
 FAU 3578

* REVISED : DECEMBER 30, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M6066000	CORRUGATED MED	SQ M	34.000				
M6300101	SPBGR TY A 1.83 POSTS	METER	20.000				
M6320030	GUARDRAIL REMOV	METER	98.000				
M6380605	TEMP MOD GLARE SCREEN	METER	520.000				
M6640110	CH LK FENCE 1.5	METER	222.000				
* M6690200	NON SPL WASTE DISPOSL	CU M	2,190.000				
M7030210	TEMP PVT MK LTR & SYM	SQ M	14.000				
M7030220	TEMP PVT MK LINE 100	METER	2,307.000				
M7030240	TEMP PVT MK LINE 150	METER	82.000				
M7030260	TEMP PVT MK LINE 300	METER	9.000				
M7030280	TEMP PVT MK LINE 600	METER	25.000				
M7031000	WORK ZONE PAVT MK REM	SQ M	1,845.000				
M7040100	TEMP CONC BARRIER	METER	994.000				
M7040200	REL TEMP CONC BARRIER	METER	499.000				
M7200200	SIGN PANEL T2	SQ M	15.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62388

State Job # - C-91-050-02
 PPS NBR - 1-73777-0200
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 15VB-1-R-1

Project Number
 ACM-ACBRF-3578/010/

Route
 FAU 3578

* REVISED : DECEMBER 30, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M7800115	THPL PVT MK LINE 150	METER	115.000				
M7800600	EPOXY PVT MK LTR-SYM	SQ M	7.000				
M7800605	EPOXY PVT MK LN 100	METER	4,590.000				
M7800615	EPOXY PVT MK LN 150	METER	36.000				
M7800625	EPOXY PVT MK LN 300	METER	27.000				
M7800640	EPOXY PVT MK LN 600	METER	15.000				
M7802000	POLYUREA PM T1 LTR&SY	SQ M	44.000				
M7802010	POLYUREA PM T1 LN 100	METER	3,931.000				
M7802015	POLYUREA PM T1 LN 150	METER	901.000				
M7802030	POLYUREA PM T1 LN 300	METER	39.000				
M7802060	POLYUREA PM T1 LN 600	METER	84.000				
M8100060	CON T 50 GALVS	METER	146.000				
M8100070	CON T 65 GALVS	METER	6.000				
M8100100	CON T 100 GALVS	METER	12.000				
M8101040	CON P 40 GALVS	METER	28.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62388

State Job # - C-91-050-02
 PPS NBR - 1-73777-0200
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 15VB-1-R-1

Project Number
 ACM-ACBRF-3578/010/

Route
 FAU 3578

* REVISED : DECEMBER 30, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M8101050	CON P 50 GALVS	METER	101.000				
M8101060	CON P 65 GALVS	METER	3.000				
M8101070	CON P 75 GALVS	METER	88.000				
M8101090	CON P 100 GALVS	METER	124.000				
M8120230	CON EMB STR 50 PVC	METER	29.000				
M8120250	CON EMB STR 75 PVC	METER	2.000				
M8130120	JBX SS AS 150X150X100	EACH	8.000				
M8180143	A CBL 3-1C4 AL MESS W	METER	656.000				
M8190200	TR & BKFIL F ELECT WK	METER	440.000				
M8301130	LT P A 15.2MH 4.5MA	EACH	3.000				
M8305020	LT P A 14.5MH 2.5MA	EACH	8.000				
M8305050	LT P A 14.5MH 4.5MA	EACH	1.000				
M8307390	LT P WD 18.30 CL 4	EACH	1.000				
M8307420	LP WD 18.30 CL4 4.5MA	EACH	8.000				
M8307570	LP WD 30.48 CL2 4.5MA	EACH	8.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

62388

State Job # - C-91-050-02
 PPS NBR - 1-73777-0200
 County Name - COOK--
 Code - 31 - -
 District - 1 - -
 Section Number - 15VB-1-R-1

Project Number
 ACM-ACBRF-3578/010/

Route
 FAU 3578

* REVISED : DECEMBER 30, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M8360100	LIGHT POLE FDN 600	METER	9.000				
M8380095	BKWY DEV TR B 381BC	EACH	3.000				
M8731210	ELCBL C SIGNAL 14 2C	METER	585.000				
M8731220	ELCBL C SIGNAL 14 3C	METER	962.000				
M8731240	ELCBL C SIGNAL 14 5C	METER	649.000				
M8731250	ELCBL C SIGNAL 14 7C	METER	660.000				
M8731300	ELCBL C LEAD 14 1PR	METER	771.000				
M8731800	ELCBL C SERV 6 2C	METER	7.000				
M8750450	TS POST GALVS 3.00	EACH	2.000				
M8750510	TS POST GALVS 4.85	EACH	4.000				
M8770095	S MAA & P 15.24	EACH	1.000				
M8770740	STL COMB MAA&P 9.14	EACH	1.000				
M8770745	STL COMB MAA&P 9.75	EACH	1.000				
M8770750	STL COMB MAA&P 10.36	EACH	1.000				
M8780100	CONC FDN TY A	METER	6.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62388

State Job # - C-91-050-02
 PPS NBR - 1-73777-0200
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 15VB-1-R-1

Project Number
 ACM-ACBRF-3578/010/

Route
 FAU 3578

* REVISED : DECEMBER 30, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M8780150	CONC FDN TY C	METER	2.000				
M8780400	CONC FDN TY E 750D	METER	5.000				
XX002113	TEMP LIGHT CONTROLLER	EACH	1.000				
X0322141	REM TEMP WOOD POLE	EACH	1.000				
X0322215	CLEAN BRG SCUP/DWNSPT	EACH	8.000				
X0323426	SED CONT DR ST INL CL	EACH	100.000				
X0323792	LTG CONTR 1D CONS TY	EACH	1.000				
X0323817	SED CONT SILT CURTAIN	EACH	1.000				
X0323830	DRAINAGE SCUPPR DS-11	EACH	34.000				
X0324302	REM TEMP LTG FIX SALV	EACH	16.000				
X0324387	LUM SFTY CABLE ASMBLY	EACH	15.000				
X0325705	RE-OPTIMIZE SIG SYS 2	EACH	1.000				
X0326759	TIE ROD ASSEMBLIES	EACH	24.000				
X4021000	TEMP ACCESS- PRIV ENT	EACH	3.000				
X4022000	TEMP ACCESS- COM ENT	EACH	7.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

62388

State Job # - C-91-050-02
 PPS NBR - 1-73777-0200
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 15VB-1-R-1

Project Number
 ACM-ACBRF-3578/010/

Route
 FAU 3578

* REVISED : DECEMBER 30, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X5080600	MECHANICAL SPLICERS	EACH	1,094.000				
X6700410	ENGR FLD OFF A SPL	CAL MO	20.000				
X8050015	SERV INSTALL POLE MT	EACH	1.000				
X8250090	COMB POLE LTG CONTROL	EACH	1.000				
X8620020	UNINTER POWER SUPPLY	EACH	1.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0030020	IMP ATTEN FRD NAR TL2	EACH	4.000				
Z0030320	IMP ATTN REL FRD TL2	EACH	4.000				
Z0032300	JACK EXIST SUP-STR	L SUM	1.000				
Z0048665	RR PROT LIABILITY INS	L SUM	1.000				
Z0076600	TRAINEES	hour	1,500.000		0.800		1,200.000
20101100	TREE TRUNK PROTECTION	EACH	10.000				
25200200	SUPPLE WATERING	UNIT	114.000				
28000510	INLET FILTERS	EACH	20.000				
50100100	REM EXIST STRUCT	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62388

State Job # - C-91-050-02
 PPS NBR - 1-73777-0200
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 15VB-1-R-1

Project Number
 ACM-ACBRF-3578/010/

Route
 FAU 3578

* REVISED : DECEMBER 30, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50202901	COFFERDAM LOCATION 1	EACH	1.000				
50202902	COFFERDAM LOCATION 2	EACH	1.000				
50500505	STUD SHEAR CONNECTORS	EACH	26,212.000				
50800515	BAR SPLICERS	EACH	3,985.000				
51204650	PILE SHOES	EACH	276.000				
51500100	NAME PLATES	EACH	1.000				
52100010	ELAST BEARING ASSY T1	EACH	72.000				
52100020	ELAST BEARING ASSY T2	EACH	46.000				
56400100	FIRE HYDNNTS TO BE MVD	EACH	2.000				
60100060	CONC HDWL FOR P DRAIN	EACH	3.000				
60208240	CB TC T24F&G	EACH	2.000				
60237470	INLETS TA T24F&G	EACH	1.000				
60250200	CB ADJUST	EACH	6.000				
60252800	CB RECONST	EACH	2.000				
60255500	MAN ADJUST	EACH	5.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

62388

State Job # - C-91-050-02
 PPS NBR - 1-73777-0200
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 15VB-1-R-1

Project Number
 ACM-ACBRF-3578/010/

Route
 FAU 3578

* REVISED : DECEMBER 30, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60257900	MAN RECONST	EACH	1.000				
60260100	INLETS ADJUST	EACH	1.000				
60262700	INLETS RECONST	EACH	1.000				
60500050	REMOV CATCH BAS	EACH	7.000				
60500060	REMOV INLETS	EACH	4.000				
63100085	TRAF BAR TERM T6	EACH	2.000				
63100167	TR BAR TRM T1 SPL TAN	EACH	2.000				
* 66900450	SPL WASTE PLNS/REPORT	L SUM	1.000				
* 66900530	SOIL DISPOSAL ANALY	EACH	3.000				
67000600	ENGR FIELD LAB	CAL MO	20.000				
67100100	MOBILIZATION	L SUM	1.000				
70101800	TRAF CONT & PROT SPL	L SUM	1.000				
70103815	TR CONT SURVEILLANCE	CAL DA	515.000				
70106800	CHANGEABLE MESSAGE SN	CAL MO	80.000				
78100100	RAISED REFL PAVT MKR	EACH	199.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

62388

State Job # - C-91-050-02
 PPS NBR - 1-73777-0200
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 15VB-1-R-1

Project Number
 ACM-ACBRF-3578/010/

Route
 FAU 3578

* REVISED : DECEMBER 30, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
80400100	ELECT SERV INSTALL	EACH	3.000				
80400200	ELECT UTIL SERV CONN	L SUM	1.000		1,500.000		1,500.000
81400100	HANDHOLE	EACH	9.000				
81400200	HD HANDHOLE	EACH	4.000				
81400300	DBL HANDHOLE	EACH	2.000				
82102400	LUM SV HOR MT 400W	EACH	30.000				
84200500	REM EX LT UNIT SALV	EACH	15.000				
84500110	REMOV LIGHTING CONTR	EACH	1.000				
84500120	REMOV ELECT SERV INST	EACH	2.000				
84500130	REMOV LTG CONTR FDN	EACH	1.000				
85000200	MAIN EX TR SIG INSTAL	EACH	2.000				
85700205	FAC T4 CAB SPL	EACH	1.000				
86400100	TRANSCEIVER - FIB OPT	EACH	1.000				
87601200	PED P-B POST GALVS T2	EACH	3.000				
87900200	DRILL EX HANDHOLE	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

62388

State Job # - C-91-050-02
 PPS NBR - 1-73777-0200
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 15VB-1-R-1

Project Number
 ACM-ACBRF-3578/010/

Route
 FAU 3578

* REVISED : DECEMBER 30, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
88030020	SH LED 1F 3S MAM	EACH	8.000				
88030050	SH LED 1F 3S BM	EACH	2.000				
88030100	SH LED 1F 5S BM	EACH	2.000				
88030110	SH LED 1F 5S MAM	EACH	8.000				
88030240	SH LED 2F 1-3 1-5 BM	EACH	6.000				
88102717	PED SH LED 1F BM CDT	EACH	6.000				
88102740	PED SH LED 2F BM	EACH	3.000				
88200210	TS BACKPLATE LOU ALUM	EACH	16.000				
88500100	INDUCTIVE LOOP DETECT	EACH	13.000				
88800100	PED PUSH-BUTTON	EACH	11.000				
89000100	TEMP TR SIG INSTALL	EACH	1.000				
89501400	REL EM VEH PR SYS D U	EACH	1.000				
89501410	REL EM VEH PR SYS P U	EACH	1.000				
89502200	MOD EX CONTR	EACH	2.000				
89502375	REMOV EX TS EQUIP	EACH	2.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62388

State Job # - C-91-050-02
 PPS NBR - 1-73777-0200
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 15VB-1-R-1

Project Number
 ACM-ACBRF-3578/010/

Route
 FAU 3578

* REVISED : DECEMBER 30, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
89502380	REMOV EX HANDHOLE	EACH	12.000				
89502385	REMOV EX CONC FDN	EACH	4.000				

VARIABLY SPACED TINING (BDE)..... 199
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID) 200
FUEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) 203
STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) 207
NOTICE OF INTENT..... 211
STORM WATER POLLUTION PREVENTION PLAN..... 212
404 PERMIT..... 221
FLOODWAY PERMIT 234
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES 235

Revised 12/30/2009

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES

This work shall be according to Article 669 of the Standard Specifications and the following:

Qualifications. The term environmental firm shall mean an environmental firm with at least five (5) documented leaking underground storage tank (LUST) cleanups or that is pre-qualified in hazardous waste by the Department. Documentation includes but not limited to verifying remediation and special waste operations for sites contaminated with gasoline, diesel, or waste oil in accordance with all Federal, State, or local regulatory requirements and shall be provided to the Engineer for approval. The environmental firm selected shall not be a former or current consultant or have any ties with any of the properties contained within and/or adjacent to this construction project.

General. Implementation of this Special Provision will likely require the Contractor to subcontract for the execution of certain activities. It will be the Contractor's responsibility to assess the working conditions and adjust anticipated production rates accordingly.

All contaminated materials shall be managed as non-special waste. This work shall include monitoring and potential sampling, analytical testing, and management of a petroleum contaminated material.

Any soil classified as a non-special waste shall be excavated and disposed of as directed by this project or the Engineer. Any excavation or disposal beyond what is required by this project or the Engineer will be at no additional cost to the Department. The preliminary site investigation (PSI) report, available through the District's Environmental Studies Unit, estimated the excavation quantity of non-special waste at the following location. The information available at the time of plan preparation determined the limits of the contamination and the quantities estimated were based on soil excavation for construction purposes only. The lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit whichever is less. Any soil samples or analysis without the approval of the Engineer will be at no additional cost to the Department.

Added 12/30/2009

- A. The Environmental Firm shall continuously monitor for worker protection and the Contractor shall manage and dispose of all soils excavated within the following areas as classified below.
1. Station 4+550 to Station 4+600 0 to 15.24 meters (0 to 50 feet) LT (Radio Tower, Site 870V2-16, 6400 Block Janet Lane, Chicago Ridge) – non-special waste. Contaminants of concern sampling parameters: PNAs, Mercury, and Arsenic.
 2. Station 4+635 to Station 4+680 0 to 15.24 meters (0 to 50 feet) LT (Radio Tower, Site 870V2-16, 6400 Block Janet Lane, Chicago Ridge) – non-special waste. Contaminants of concern sampling parameters: PNAs, Mercury, and Arsenic.
 3. Station 4+750 to Station 4+800 0 to 15.24 meters (0 to 50 feet) RT (Office Depot, Site 870V2-11, 300 Commons Drive, Chicago Ridge) – non-special waste. Contaminants of concern sampling parameters: PNAs and Lead.
 4. Station 4+840 to Station 4+905 0 to 15.24 meters (0 to 50 feet) RT (Office Depot, Site 870V2-11, 300 Commons Drive, Chicago Ridge) – non-special waste. Contaminants of concern sampling parameters: PNAs and Lead.
 5. Station 6+050 to Station 6+105 0 to 15.24 meters (0 to 50 feet) RT (Vacant Building, Site 870V2-2, 10033 South Ridgeland Avenue, Oak Lawn) – non-special waste. Contaminants of concern sampling parameters: BETX and PNAs.
 6. Station 4+985 to Station 5+005 0 to 15.24 meters (0 to 50 feet) RT (Vacant Building, Site 870V2-2, 10033 South Ridgeland Avenue, Oak Lawn) – non-special waste. Contaminants of concern sampling parameters: BETX and PNAs.
 7. Station 5+005 to Station 5+045 0 to 15.24 meters (0 to 50 feet) RT (Atlantic Painting Company, Site 870V2-19, 10019-10021 Southwest Highway, Oak Lawn) – non-special waste. Contaminants of concern sampling parameters: PNAs and Lead.
 8. Station 5+060 to Station 5+100 0 to 15.24 meters (0 to 50 feet) RT (CITGO Gasoline Station, Site 870V2-18, 10001 Southwest Highway, Oak Lawn) – non-special waste. Contaminants of concern sampling parameters: PNAs and Lead.

Added 12/30/2009