


F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3578	15VB-1-R-1	COOK	243	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 62388				



SUMMARY OF QUANTITIES		UNIT	TOTAL QTY.	80% FEDERAL 20% STATE				80% FED 15% STATE 5% OAK LAWN	100% OAK LAWN	100% CHICAGO RIDGE			
				ROADWAY	BRIDGE	RETAINING WALL	TRAFFIC SIG. INTERCON.	SW HWY @ RIDGELAND	LIGHTING	LIGHTING	EMERGENCY PRE-EMPTION	PED. PUSH BUTTONS	BRIDGE SW BARRIER
CODE NO.	ITEM DESCRIPTION			J000-2A	X371-2A	Y007	Y031-1F	YO31-1F	YO30-1E	YO30-1E	Y031-3D	Y031-1F	SFTY-2A
* A2005020	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2 1/2" CALIPER, BALLED AND BURLAPPED	EACH	4	4									
* A2005616	TREE, OSTRYA VIRGINIANA (AMERICAN HOPHORNBEAM), 2" CALIPER, BALLED AND BURLAPPED	EACH	12	12									
* C2C05824	SHRUB, RHUS AROMATICA GRO-LOW (GRO-LOW FRAGRANT SUMAC), 2' WIDTH, CONTAINER	EACH	200	200									
* C2C06136	SHRUB, RHUS TYPHINA LACINIATA (CUTLEAF STAGHORN SUMAC), 3' HEIGHT, CONTAINER	EACH	50	50									
* C2008224	SHRUB, ROSA NEARLY WILD (NEARLY WILD ROSE), 24" HEIGHT, CONTAINER	EACH	75	75									
* C2011736	SHRUB, VIBURNUM DENTATUM (ARROWWOOD VIBURNUM), 3' HEIGHT, BALLED AND BURLAPPED	EACH	30	30									
M2010110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	49	49									
M2010210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	5	5									
M2011000	TEMPORARY FENCE	METER	64	64									
* M2011300	TREE PRUNING (25 TO 250 MM DIAMETER)	EACH	12	12									
* M2011350	TREE PRUNING (OVER 250 MM DIAMETER)	EACH	10	10									
* M2011400	NITROGEN FERTILIZER NUTRIENT	KG	26	26									
* M2011500	PHOSPHORUS FERTILIZER NUTRIENT	KG	26	26									
* M2011600	POTASSIUM FERTILIZER NUTRIENT	KG	26	26									
M2020010	EARTH EXCAVATION	CU M	741	741									
M2021200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU M	324	324									
M2030100	CHANNEL EXCAVATION	CU M	914	914									
M2040800	FURNISHED EXCAVATION	CU M	1,812	1,812									
M2070400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU M	192		171	21							
M2080150	TRENCH BACKFILL	CU M	141	141									
* M2113150	TOPSOIL FURNISH AND PLACE, 150MM	SQ M	3,650	3,650									
* M2500200	SEEDING, CLASS 2	HA	0.11	0.11									
* M2510630	EROSION CONTROL BLANKET	SQ M	1,128	1,128									
* M2520110	SODDING, SALT TOLERANT	SQ M	2,522	2,522									
M2800250	TEMPORARY EROSION CONTROL SEEDING	KG	41	41									
M2800400	PERIMETER EROSION BARRIER	METER	1,135	1,135									
M2810107	STONE RIPRAP, CLASS A4	SQ M	1,461	838	623								
M2820200	FILTER FABRIC	SQ M	1,355	732	623								
M4202255	PORTLAND CEMENT CONCRETE PAVEMENT 250MM (JOINTED)	SQ M	7,551	7,551									
M4205050	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ M	367	367									
M4205200	PROTECTIVE COAT	SQ M	9,076	9,076									

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAU 3578 (SOUTHWEST HIGHWAY)
 OVER B&O RAILROAD AND STONY CREEK
 SUMMARY OF QUANTITIES

SCALE: DRAWN BY: DES
 DATE: 6/17/09 CHECKED BY: JUC

+koeppen(Rdwy_Liste) 6/26/2009 1:32:38 AM PDF(Grey_Large).pht 0:\DOT\9556_A0\Drawings\RDWY\shts\RdV_S_02_sqa.dgn

