

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	*	McHENRY	502	12
STA. 9+35.22		TO STA. 142+08.53		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

* (105X & 106) WRS-2

McHenry County

100% HUNTLEY

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY URBAN	ROADWAY		SIDEWALK	BOX CULVERT	TRAFFIC SIGNALS		LIGHTING	WATER MAIN & SAN. SEWER				
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE			KREUTZER	MAIN			ALGONQUIN	REED	EVP	INTERCONNECT
				J000-2A	J000-2A			Y031-1F	Y031-1F			Y031-1F	Y031-1F	Y031-1F	Y031-1F
X0326723	WET REFLECTIVE PREFORMED PLASTIC PAVEMENT MARKINGS-LETTERS & SYMBOLS	SQ FT	473		473										
X0326724	WET REFLECTIVE PREFORMED PLASTIC PAVEMENT MARKINGS-LINE 4"	FOOT	8479		8479										
X0326725	WET REFLECTIVE PREFORMED PLASTIC PAVEMENT MARKINGS-LINE 6"	FOOT	3820		3820										
X0326726	WET REFLECTIVE PREFORMED PLASTIC PAVEMENT MARKINGS-LINE 12"	FOOT	668		668										
X0326727	WET REFLECTIVE PREFORMED PLASTIC PAVEMENT MARKINGS-LINE 24"	FOOT	121		121										
X0326732	HOT-MIX ASPHALT SURFACE REMOVAL FOR RECESSED PAVEMENT MARKINGS, 0.1 INCH DEPTH	SQ FT	6120		6120										
X0326720	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	167					42	50	25	50				
X0326728	WET PAVEMENT MARKING TAPE, TYPE III-LETTERS AND SYMBOLS	SQ FT	4196	364	3832										
X0326729	WET PAVEMENT MARKING TAPE, TYPE III-4 INCH	FOOT	191,486	23,480	168,006										
X0326730	WET PAVEMENT MARKING TAPE, TYPE III-6 INCH	FOOT	16,925	1,654	15,271										
X0326731	WET PAVEMENT MARKING TAPE, TYPE III-12 INCH	FOOT	2,481	458	2,023										
X0326733	SANITARY PVC SDR 26, 6"	FOOT	891								891				
X0326734	SANITARY PVC SDR 26, 8"	FOOT	1,918								1918				
X0326735	SANITARY PVC SDR 26, 10"	FOOT	270								270				
X0326736	SANITARY PVC SDR 26, 12"	FOOT	480								480				
X0326737	SANITARY PVC SDR 26 (WATER MAIN QUALITY), 8"	FOOT	204								204				
60226400	MANHOLES, DROP TYPE, 4'-DIAMETER, TYPE I FRAME, CLOSED LID	EACH	1								1				
X0326738	CLEAN SANITARY MANHOLE	EACH	2								2				
X0326740	LINE MANHOLE	FOOT	34								34				
X0326739	CLEAN SANITARY SEWER	FOOT	101								101				
XX006247	SANITARY SEWER REMOVAL	FOOT	3,171								3171				
X0326741	REPLACE FRAMES AND ADJUSTMENTS	EACH	2								2				
X0326744	PLUG PIPE PENETRATION	EACH	1								1				
X0326745	SANITARY SEWER LIFT STATION	L SUM	1								1				
X0326746	SANITARY SEWER LIFT STATION ABANDONMENT	L SUM	1								1				
X0326747	SANITARY FORCE MAIN, 6"	FOOT	945		650						295				
X0326748	CLEAN-OUT MANHOLE	EACH	1								1				
20061100	AIR RELEASE VALVE	EACH	1								1				
X0326750	STEEL CASING PIPE, BORE AND JACK, 18"	FOOT	70		70										
20067450	STEEL CASINGS 15'	FOOT	67								67				
X0326755	VALVE VAULT, 5' DIAMETER, WITH 12" VALVE	EACH	13								13				
X0326754	VALVE VAULT, 5' DIAMETER, WITH 10" VALVE	EACH	7		2						5				
X0326753	VALVE VAULT, 4' DIAMETER, WITH 8" VALVE	EACH	7								7				
X0326752	VALVE VAULT, 4' DIAMETER, WITH 6" VALVE	EACH	9								9				
X0326751	VALVE VAULT 4" VALVE	EACH	1								1				
X0326750	WATER MAIN REMOVAL	FOOT	7,196		370						6826				
60266500	VALVE VAULTS TO BE REMOVED	EACH	10								10				
60400500	FIRE HYDRANTS TO BE REMOVED	EACH	14								14				
X0326756	LIGHT POLE, COMPLETE IN PLACE, PE 1	EACH	78								78				
X0326757	LIGHT POLE, COMPLETE IN PLACE, TYPE 2	EACH	8								8				
X0326758	UNIT DUCT, 600V, 4/C #6, 2/C #8, 1/C #8 NEUTRAL & 1/C #6 (DLP TYPE-USE) 1 1/2" DIAMETER H-PIPE, IN TRENCH	FOOT	14,940								14940				
X4420540	CLASS B PATCHES, TYPE IV, 8 1/4 INCH	SQ YD	27		27										
20070600	TRAINERS	HR	2,000	2,000											

© Y080
SPECIALTY ITEM

REVISIONS	
NAME	DATE



ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 48
SUMMARY OF QUANTITIES

SCALE: VERT. NO SCALE
HORIZ. 1"=40'

DRAWN BY: E.D.
CHECKED BY: A.A.C.

PLOT DATE = Monday, August 15, 2009
FILE NAME = s:\11-csod\01-shs\084-012-sum-of-quant.dgn
USER NAME = 38590

Rev. 12-28-09

Rev.