

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
CODE NO.	ITEM DESCRIPTION	UNIT		ROADWAY 1000-2A QUANTITY	BRIDGE	
					SN 099-0001 X071-2A QUANTITY	SN 099-0002 X071-2A QUANTITY
40600300	AGGREGATE (PRIME COAT)	TON	223	223		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	144	144		
40601005	HOT MIX ASPHALT REPLACEMENT OVER PATCHES	TON	530	530		
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	2,286	2,286		
44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SQ YD	18,147	18,147		
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	37,548	37,548		
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	2366	2366		
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	901	901		
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	676	676		
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	676	676		
44300900	STRIP REFLECTIVE CRACK CONTROL TREATMENT SYSTEM A	FOOT	10,915	10,915		
63500105	DELINEATORS	EACH	133	133		
64200105	SHOULDER RUMBLE STRIP	FOOT	16,053	16,053		
X0322729	MATERIAL TRANSFER DEVICE	TON	10,138	10,138		
X0324685	TEST STRIP (STONE MATRIX ASPHALT)	EACH	2	2		
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	5,069	5,069		
40603148	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80	TON	5,069	5,069		



• SPECIALTY ITEM

Added Sheet 12-30-09



Excellence through Ownership

200 West Front Street
Wheaton, IL 60187

DESIGNED - KSD	REVISED - ADD. NO. 1
DRAWN - KSD	REVISED -
CHECKED - CMJ	REVISED -
DATE - 03-04-09	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

I-55 OVER THE KANKAKEE RIVER
SUMMARY OF QUANTITIES

SCALE: NTS SHEET NO. 1 OF 1 SHEETS STA. ---- TO STA. ----

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	88 (B&B-1) BR	WILL	72	4A
CONTRACT NO. 62930				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				