

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
				ROADWAY I000-1A	LANDSCAPING Y003	HIGHWAY ILLUMINATION Y030-1E	NON-PARTICIPATING
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	7	7	-	-	-
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	30	30	-	-	-
20101100	TREE TRUNK PROTECTION	EACH	3	3	-	-	-
20101200	TREE ROOT PRUNING	EACH	3	3	-	-	-
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	1	1	-	-	-
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	4	4	-	-	-
20200100	EARTH EXCAVATION	CU YD	1,040	1,040	-	-	-
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	417	417	-	-	-
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	417	417	-	-	-
20800150	TRENCH BACKFILL	CU YD	58	58	-	-	-
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	5,680	-	5,680	-	-
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	109	-	109	-	-
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	109	-	109	-	-
25100105	MULCH, METHOD 1	ACRE	1	-	1	-	-
25200110	SODDING, SALT TOLERANT	SQ YD	5,680	-	5,680	-	-
25200200	SUPPLEMENTAL WATERING	UNIT	90	-	90	-	-
* 25300500	TOPSOIL FOR PLANTING	CU YD	580	-	580	-	-
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	121	121	-	-	-
28000305	TEMPORARY DITCH CHECKS	FOOT	140	140	-	-	-
28000400	PERIMETER EROSION BARRIER	FOOT	2,660	2,660	-	-	-
28000510	INLET FILTERS	EACH	22	22	-	-	-
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	5,700	5,700	-	-	-
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	550	550	-	-	-
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	720	511	-	-	209
40600300	AGGREGATE (PRIME COAT)	TON	17	12	-	-	5
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	260	-	-	-	260
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	19	19	-	-	-
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	368	368	-	-	-
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	144	99	-	-	45
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	140	-	-	-	140

* INDICATES SPECIALTY ITEM

2009 BY BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 LICENSE NO. - 084-00121 - EXPIRES 4/30/2011
 1/18/2009 8:52:58 AM



DESIGNED - MWP	REVISED - IDOT REVIEW 2/19/09
DRAWN - CJC	REVISED - IDOT REVIEW 4/22/09
CHECKED - MDW	REVISED - IDOT REVIEW 6/3/09
DATE - 8-1-08	REVISED - IDOT REVIEW 11/17/09

VILLAGE OF WINTHROP HARBOR, ILLINOIS
ILLINOIS ROUTE 137 (SHERIDAN ROAD) AND 7th STREET
STREETSCAPE IMPROVEMENTS

SUMMARY OF QUANTITIES

SCALE: NONE

STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
.	06-00036-00-LS	LAKE	70	4
FED. ROAD DIST. NO. 1		CONTRACT NO. 63167		
JOB NO. C-91-197-10		ILLINOIS FED. AID PROJECT ARA-0001810		

* F.A.P. 352 ILLINOIS ROUTE 137 (SHERIDAN ROAD)