

DRIVEWAYS

STATION	EXISTING DRIVEWAY APRON (TYPE)	RESIDENTIAL OR COMMERCIAL	WIDTH AT ROW OR F/WALK (FOOT)	WIDTH AT CURB (FOOT)	LENGTH (FOOT)	DRIVEWAY PAVEMENT AREA (SQ YD)	HMA SURFACE COURSE, MIX 'C', N50, 2" (TON)	HMA BASE COURSE 8" (PAID FOR AS HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50) (TON)	PCC DRIVEWAY PAVEMENT 6" (SQ YD)	PCC DRIVEWAY PAVEMENT 8" (SQ YD)	STAMPED COLORED PCC SIDEWALK 6" (SQ FT)	STAMPED COLORED PCC SIDEWALK 8" (SQ FT)	AGGREGATE BASE COURSE TYPE B - 4" (SQ YD)	AGGREGATE BASE COURSE TYPE B - 6" (SQ YD)	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT (SPECIAL) (FOOT)	DRIVEWAY PAVEMENT REMOVAL (SQ YD)
ILLINOIS ROUTE 137 (SHERIDAN ROAD)																
47+28 LT	HMA	C	30	42	8	34	—	—	—	—	—	—	28	—	76	—
51+68 LT	HMA	C	24	31	8	25	2	5	—	—	—	180	27	20	50	25
52+93 LT	HMA	C	22	24	8	21	1	4	—	—	—	126	13	14	12	21
53+26 LT	HMA	C	50	52	8	46	2	8	—	—	—	279	22	31	12	46
47+47 RT	HMA	C	37	42	16	71	6	23	—	—	—	207	50	23	—	71
48+23 RT	HMA	C	21	23	8	20	2	6	—	—	—	126	20	14	22	20
51+68 RT	HMA	C	27	27	8	24	2	5	—	—	—	162	17	18	22	24
SUB TOTAL ILLINOIS ROUTE 137 (SHERIDAN ROAD)						241	15	51	0	0	0	1,080	177	120	194	207
7TH STREET																
8 + 50 LT	HMA	C	31	48	20	85	2	7	—	—	—	171	19	19	20	33
13 + 39 LT	CONC	C	20	26	18	46	—	—	—	46	—	108	8	58	31	40
14 + 71 LT	CONC	R	21	38	19	63	—	—	63	—	126	—	88	—	43	53
16 + 36 LT	CONC	C	23	32	19	59	—	—	—	59	—	126	9	73	38	50
17 + 15 LT	CONC	R	12	22	21	40	—	—	40	—	81	—	56	—	29	40
24 + 59 LT	HMA	C	40	50	10	50	6	23	—	—	—	252	88	28	160	345
25 + 21 LT	CONC	C	32	35	10	39	—	—	—	39	—	171	12	58	50	33
26 + 86 LT	CONC	C	16	24	10	23	—	—	—	23	—	108	7	35	30	20
27 + 46 LT	CONC	C	29	36	10	37	—	—	—	37	—	171	12	56	51	33
8 + 47 RT	HMA	C	26	36	22	76	9	35	—	—	—	153	76	17	—	76
11 + 69 RT	HMA	C	33	42	17	72	9	34	—	—	—	180	72	20	—	72
13 + 99 RT	CONC	R	14	24	19	41	—	—	41	—	81	—	57	—	30	41
16 + 63 RT	CONC	R	16	22	21	45	—	—	45	—	81	—	61	—	30	33
17 + 12 RT	CONC	R	12	22	21	40	—	—	40	—	81	—	61	—	30	33
18 + 10 RT	CONC	R	16	26	21	49	—	—	49	—	108	—	69	—	32	49
SUB TOTAL 7TH STREET						765	26	99	278	204	558	1,440	695	364	574	951
TOTALS						1,006	41	150	278	204	558	2,520	872	484	768	1,158

COPYRIGHT © 2009 BY BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 LICENSE NO. - 384-00191 - EXPIRES 4/30/2011
 488/CJC 4/09/09 4:00:06 PM \\winth\060807\p\dms\winth\060807\schedule.sht



DESIGNED - MWP	REVISED - IDOT REVIEW 2/19/09
DRAWN - CJC	REVISED - IDOT REVIEW 4/22/09
CHECKED - MDW	REVISED -
DATE - 8-1-08	FILE - 060807-schedule.sht

VILLAGE OF WINTHROP HARBOR, ILLINOIS
ILLINOIS ROUTE 137 (SHERIDAN ROAD) AND 7th STREET
STREETScape IMPROVEMENTS

SCHEDULE OF QUANTITIES

SCALE: NONE STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	06-00036-00-LS	LAKE	70	12
FED. ROAD DIST. NO. 1		CONTRACT NO. 63167		
JOB NO. C-91-197-10		ILLINOIS FED. AID PROJECT ARA-00018101		

* F.A.P. 352 ILLINOIS ROUTE 137 (SHERIDAN ROAD)