

CURB AND GUTTER

STATION BEGIN	STATION END	COMBINATION CURB AND GUTTER REMOVAL (FOOT)	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT (SPECIAL) (FOOT)	CONCRETE CURB, TYPE B (FOOT)	CONCRETE CURB, TYPE B (ABUTTING EXISTING PAVEMENT) (FOOT)	COMBINATION CONCRETE CURB AND GUTTER TYPE B-6.12 (SPECIAL) (FOOT)
ILLINOIS ROUTE 137 (SHERIDAN ROAD)						
46 + 69 LT	50 + 00 LT	--	--	--	108	--
50 + 00 LT	54 + 74 LT	--	--	--	108	--
46 + 69 RT	49 + 60 RT	--	--	--	198	--
50 + 30 RT	54 + 74 RT	--	--	--	126	--
FROM ILLINOIS ROUTE 137 (SHERIDAN ROAD) SIDEWALK SCHEDULE		--	--	--	--	--
FROM ILLINOIS ROUTE 137 (SHERIDAN ROAD) DRIVEWAY SCHEDULE		--	194	--	--	--
SUB TOTAL ILLINOIS ROUTE 137 (SHERIDAN ROAD)		0	194	0	540	0
7TH STREET						
6 + 44 LT	6 + 77 LT	--	--	--	--	--
7 + 07 LT	9 + 77 LT	--	--	--	--	--
10 + 39 LT	12 + 94 LT	219	50	--	--	332
12 + 94 LT	15 + 74 LT	--	10	--	--	50
15 + 74 LT	18 + 69 LT	--	--	--	--	--
18 + 96 LT	22 + 56 LT	--	--	--	--	--
22 + 81 LT	27 + 81 LT	--	--	--	--	--
6 + 48 RT	6 + 72 RT	--	--	--	--	--
6 + 92 RT	9 + 63 RT	--	--	--	--	--
10 + 50 RT	12 + 75 RT	45	--	117	--	159
13 + 03 RT	15 + 59 RT	--	--	--	--	--
15 + 86 RT	18 + 89 RT	--	--	--	--	--
19 + 18 RT	22 + 70 RT	--	--	--	--	--
22 + 70 RT	27 + 81 RT	--	--	--	--	--
FROM 7TH STREET SIDEWALK SCHEDULE		--	486	--	--	--
FROM 7TH STREET DRIVEWAY SCHEDULE		--	574	--	--	--
SUB TOTAL 7TH STREET		264	1,120	117	0	541
TOTAL		264	1,314	117	540	541

HOT-MIX ASPHALT

STATION BEGIN	STATION END	HOT-MIX ASPHALT SURFACE COURSE MIX "C", N50 2" (TON)	HOT-MIX ASPHALT BASE COURSE, 8" (PAID FOR AS HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 (TON))	AGGREGATE BASE COURSE TYPE B - 4" (SQ YD)
ILLINOIS ROUTE 137 (SHERIDAN ROAD)				
46 + 69 LT	50 + 00 LT	4	16	34
50 + 00 LT	54 + 74 LT	4	13	28
46 + 69 RT	49 + 60 RT	7	28	60
50 + 30 RT	54 + 74 RT	--	--	7
FROM DRIVEWAY SCHEDULE		15	51	--
SUB TOTAL ILLINOIS ROUTE 137 (SHERIDAN ROAD)		30	108	129
7TH STREET				
6 + 44 LT	6 + 77 LT	--	--	--
7 + 07 LT	9 + 77 LT	--	--	--
10 + 39 LT	12 + 94 LT	17	66	142
12 + 94 LT	15 + 74 LT	7	23	49
15 + 74 LT	18 + 69 LT	--	--	--
18 + 96 LT	22 + 56 LT	--	--	--
22 + 81 LT	27 + 81 LT	2	6	12
6 + 48 RT	6 + 72 RT	--	--	--
6 + 92 RT	9 + 63 RT	--	--	--
10 + 50 RT	12 + 75 RT	17	66	142
13 + 03 RT	15 + 59 RT	--	--	--
15 + 86 RT	18 + 89 RT	--	--	--
19 + 18 RT	22 + 70 RT	--	--	--
22 + 70 RT	27 + 81 RT	--	--	--
FROM DRIVEWAY SCHEDULE		26	99	--
SUB TOTAL 7TH STREET		69	260	345
TOTAL		99	368	474

COPYRIGHT © 2009 BY BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 LICENSE NO. 184-00021 - EXPIRES 4/30/2011
 4/06/2009 4:00:07 PM
 I:\winhr\060807\cognis\winhr\060807-schedule.sht



DESIGNED - MWP	REVISED - IDOT REVIEW 2/19/09
DRAWN - CJC	REVISED - IDOT REVIEW 4/22/09
CHECKED - MDW	REVISED -
DATE - 8-1-08	FILE - 060807-schedule.sht

**VILLAGE OF WINTHROP HARBOR, ILLINOIS
ILLINOIS ROUTE 137 (SHERIDAN ROAD) AND 7th STREET
STREETScape IMPROVEMENTS**

SCHEDULE OF QUANTITIES

SCALE: NONE STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	06-00036-00-LS	LAKE	70	13
FED. ROAD DIST. NO. 1		CONTRACT NO. 63167		
JOB NO. C-91-197-10		ILLINOIS FED. AID PROJECT ARA-00018101		

* F.A.P. 352 ILLINOIS ROUTE 137 (SHERIDAN ROAD)